Proposal:250129 **Let Date:**April 17, 2025 **Call Order:**855
J/P Num:25085(08) **Proj. Num:**STP-236C(110)CI
Counties:KAY
Description:GRADE, DRAIN, BRIDGE AND SURFACE
COUNTY ROAD (EW-9/PECKHAM ROAD): FROM 1.3 MILES
EAST OF US-177, EXTEND EAST NEAR BLACKWELL.
PROJECT LENGTH = 2.424 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	24,175.370	CY
0030	202(D)2500	UNCLASSIFIED BORROW	3,500.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	1,310.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	392.000	LF
0070	221(G)2800	TEMPORARY FIBER LOG	128.000	LF
0080	227 4120	(SP)TURF REINFORCEMENT MAT TYPE 4	4,033.330	SY
0090	228 5120	EROSION CONTROL MAT TYPE 4	11,648.890	SY
0100	230(A)7200	SOLID SLAB SODDING	107,515.470	SY
0110	233(A)0200	VEGETATIVE MULCHING	22.210	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	170.280	CY
0130	307(D)3500	LIME	204.210	TON
0140	307(G)3800	LIME PRETREATMENT	18,908.440	SY
0150	307(K)4200	STABILIZED SUBGRADE	37,378.840	SY
0160	311(B)6300	PROCESS EXISTING BASE & SURFACE,METHOD B	12,800.000	LF
0170	325 0100	SEPARATOR FABRIC	536.740	SY
0180	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	438.630	TON
0190	407(B)7300	TACK COAT	3,445.340	GAL
0200	408 8100	PRIME COAT	13,275.200	GAL
0210	411(B)1340	SUPERPAVE, TYPE S3(PG 58-28 OK)	11,862.420	TON
0220	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	3,686.210	TON
0230	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	67.310	CY
0240	501(G)1810	CLSM BACKFILL	20.000	CY
0250	509(A)0200	CLASS AA CONCRETE	183.310	CY
0260	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	8.430	CY
0270	509(D)0500	CLASS C CONCRETE	106.410	CY
0280	511(A)2200	REINFORCING STEEL	20,994.060	LB
0290	601(A)1100	TYPE I PLAIN RIPRAP	270.000	TON
0300	611(G)0354	INLET (SMD-TYPE 2)	1.000	EA
0310	611(G)0358	INLET (SMD-TYPE 2A)	1.000	EA
0320	611(L)1600	JUNCTION BOXES	191.520	CF
0330	613(A)5220	30" R.C.PIPE CLASS III	52.000	LF
0340	613(A)5244	66" R.C.PIPE CLASS III	176.000	LF
0350	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	68.000	LF
0360	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	154.000	LF
0370	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	310.000	LF
0380	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	17.000	LF
0390	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	58.000	LF
0400	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	16.000	LF
0410	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
0420	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	100.000	LF
0430	613(L)6608	21" X 15" PREFAB. CULVERT END SEC., ARCH	12.000	EA
0440	613(L)6612	22" X 13" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0450	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0460	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA

Proposal:250129 **Let Date:**April 17, 2025 **Call Order:**855
J/P Num:25085(08) **Proj. Num:**STP-236C(110)CI
Counties:KAY
Description:GRADE, DRAIN, BRIDGE AND SURFACE
COUNTY ROAD (EW-9/PECKHAM ROAD): FROM 1.3 MILES
EAST OF US-177, EXTEND EAST NEAR BLACKWELL.
PROJECT LENGTH = 2.424 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	613(M)6904	TYPE B3 CULVERT END TREATMENT	1.000	EA
0480	613(M)6924	TYPE BB3 CULVERT END TREATMENT	2.000	EA
0490	613(M)6937	TYPE FF3 CULVERT END TREATMENT	2.000	EA
0500	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0510	613(U)7950	PIPE UNDERDRAIN COVER MAT'L.	250.000	CY
0520	613(V)8000	TRENCH EXCAVATION	250.000	CY
0530	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0540	619(C)6600	SAWING PAVEMENT	22.000	LF
0550	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	3,561.340	LF
0560	629(D)7500	REMOVE AND RESET MAILBOX	1.000	EA
0002	BRIDGE 'A' - NBI NO.33418			
0570	202(A)2210	UNCLASSIFIED EXCAVATION	3,544.000	CY
0580	202(D)2510	UNCLASSIFIED BORROW	10.000	CY
0590	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	310.220	CY
0600	509(A)0210	CLASS AA CONCRETE	608.490	CY
0610	511(A)2210	REINFORCING STEEL	85,153.800	LB
0620	601(A)1110	TYPE I PLAIN RIPRAP	1,620.000	TON
0003	TRAFFIC			
0630	850(A)1200	SHEET ALUMINUM SIGNS	31.080	SF
0640	853 5125	DELINEATORS(TYPE 2, CODE 3)	12.000	EA
0650	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	45,500.000	LF
0660	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,960.000	SD
0670	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,080.000	SD
0680	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,420.000	SD
0690	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,400.000	SD
0700	880(E)6600	WARNING LIGHTS(TYPE A)	5,400.000	SD
0710	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	388.000	SD
0004	STAKING			
0720	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0730	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0740	641 2110	MOBILIZATION	1.000	LSUM