Proposal: 250130 **Let Date:** May 08, 2025 **Call Order:** 131
J/P Num: 35651(04) **Proj. Num:** STP-244B(116)3P
Counties: MCCLAIN
Description: RESURFACE (ASPHALT)
US-62: FROM 0.3 MILES EAST OF THE INTERSECTION OF SH-76/MAIN STREET, EXTEND NORTHEAST NEAR BLANCHARD.
PROJECT LENGTH = 4.22 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(B)7300	TACK COAT	12,536.000	GAL
0020	411(D)1520	SUPERPAVE, TYPE S5(PG 70-28 OK)	13,025.000	TON
0030	412 3100	COLD MILLING PAVEMENT	147,477.000	SY
0040	619(B)6396	REMOVAL OF GUARDRAIL	2,500.000	LF
0050	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	1,600.000	LF
0060	623(G)1820	GUARDRAIL END TREATMENT (31")	8.000	EA
0070	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	8.000	EA
0002	TRAFFIC			
0080	413(B)4300	RUMBLE STRIP-METHOD HMA-CYC GROUP	3.000	EAGP
0090	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	123,945.000	LF
0100	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	500.000	LF
0110	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	90.000	LF
0120	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	60.000	EA
0125	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	20.000	SD
0130	880(A)6220	ARROW DISPLAY(TYPE C)	45.000	SD
0140	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,814.000	SD
0150	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	804.000	SD
0160	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,206.000	SD
0170	880(D)6500	VERTICAL PANELS	7,200.000	SD
0180	880(E)6607	WARNING LIGHTS(TYPE B)	8,406.000	SD
0190	880(I)7000	FLAGGER	45.000	SD
0200	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	148.000	SD
0210	884(B)9300	BRIDGE PARAPET RETROFIT	80.000	LF