**Proposal:** 250134 **Let Date:** April 17, 2025 **Call Order:** 870
**J/P Num:** 30323(04) **Proj. Num:** STP-266C(096)PM
**Counties:** ROGERS
**Description:** GRADE, DRAIN, AND BRIDGE
SH-266 (E 46TH ST N): FROM 3.0 MILES EAST OF US-169,
EXTEND EAST NEAR TULSA PORT OF CATOOSA.
PROJECT LENGTH = 2.204 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0010 | 201(A)1200 | CLEARING AND GRUBBING | 1.000 | LSUM |
| 0020 | 202(A)2200 | UNCLASSIFIED EXCAVATION | 10,135.000 | CY |
| 0030 | 202(B)2300 | MUCK EXCAVATION | 4,690.000 | CY |
| 0040 | 202(D)2500 | UNCLASSIFIED BORROW | 92,808.000 | CY |
| 0050 | 205(A)6200 | TYPE A-SALVAGED TOPSOIL | 1.000 | LSUM |
| 0060 | 221(B)2300 | TEMPORARY SILT FENCE | 11,164.000 | LF |
| 0070 | 221(E)2600 | TEMPORARY SILT DIKE | 98.000 | LF |
| 0080 | 221(F)2720 | TEMPORARY ROCK FILTER DAM TYPE 3 | 37.000 | CY |
| 0090 | 221(F)2730 | TEMPORARY ROCK FILTER DAM TYPE 4 | 24.000 | CY |
| 0100 | 230(A)7200 | SOLID SLAB SODDING | 107,174.000 | SY |
| 0110 | 232(A)9200 | SEEDING METHOD A | 16.610 | AC |
| 0120 | 233(A)0200 | VEGETATIVE MULCHING | 16.610 | AC |
| 0130 | 241 3100 | MOWING | 33.220 | AC |
| 0140 | 242 4101 | STABILIZED CONSTRUCTION EXIT | 2.000 | EA |
| 0150 | 326(C)1100 | (SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC | 99,040.000 | SY |
| 0160 | 402(E)2600 | TRAFFIC BOUND SURFACE COURSE TYPE E | 1,840.000 | TON |
| 0170 | 509(A)0200 | CLASS AA CONCRETE | 171.000 | CY |
| 0180 | 511(A)2200 | REINFORCING STEEL | 25,113.000 | LB |
| 0190 | 613(A)5220 | 30" R.C.PIPE CLASS III | 22.000 | LF |
| 0200 | 613(L)6724 | 30" PREFAB. CULVERT END SEC., ROUND | 1.000 | EA |
| 0210 | 613(S)7700 | STANDARD BEDDING MATERIAL, CLASS B | 8.000 | CY |
| 0220 | 613(V)8000 | TRENCH EXCAVATION | 12.000 | CY |
| 0230 | 619(A)6200 | REMOVAL OF STRUCTURES & OBSTRUCTIONS | 1.000 | LSUM |
| **0002** | BRIDGE 'A' - NBI NO. 17988 | | | |
| 0240 | 202(A)2210 | UNCLASSIFIED EXCAVATION | 69.000 | CY |
| 0250 | 501(A)1210 | STRUCTURAL EXCAVATION UNCLASSIFIED | 145.000 | CY |
| 0260 | 509(A)0210 | CLASS AA CONCRETE | 268.400 | CY |
| 0270 | 511(A)2210 | REINFORCING STEEL | 41,940.000 | LB |
| 0280 | 619(B)6304 | REMOVAL OF BRIDGE ITEMS | 1.000 | LSUM |
| **0003** | TRAFFIC SIGNING AND STRIPING | | | |
| 0290 | 805(D)3528 | (PL)REMOVE & RESET EXISTING SIGNS | 6.000 | EA |
| **0004** | TRAFFIC CONTROL | | | |
| 0300 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 360.000 | SD |
| 0310 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 1,080.000 | SD |
| 0320 | 880(E)6607 | WARNING LIGHTS(TYPE B) | 1,080.000 | SD |
| 0330 | 880(F)6700 | DRUMS | 24,840.000 | SD |
| 0340 | 882(A)8210 | PORT.CHANGEABLE MESSAGE SIGN | 388.000 | SD |
| **0005** | STAKING | | | |
| 0350 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 | LSUM |
| **0006** | CONSTRUCTION | | | |
| 0360 | 220 1100 | SWPPP DOCUMENTATION AND MANAGEMENT | 1.000 | LSUM |
| 0370 | 641 2110 | MOBILIZATION | 1.000 | LSUM |