Proposal: 250140 **Let Date:** May 08, 2025 **Call Order:** 115
J/P Num: 36724(04) **Proj. Num:** STP-214D(175)AG
Counties: CLEVELAND
Description: PEDESTRIAN AND BIKE IMPROVEMENTS (TRAIL AND SIDEWALKS)
SH-77 (12TH AVE NE)/ CITY STREET (W BROOKS ST): SH-77, FROM THE INTERSECTION OF ROBINSON STREET, EXTEND NORTH. CITY STREET (W BROOKS ST), FROM WYLIE RD, EXTEND EAST.
PROJECT LENGTH = 1.965 MILES.

	Line #		Item Description	Quantity	Unit
0001	ROADWAY - BASE BID				
	0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
	0020	202(A)2200	UNCLASSIFIED EXCAVATION	2,052.000	CY
	0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
	0040	221(B)2300	TEMPORARY SILT FENCE	5,382.000	LF
	0050	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	8.000	EA
	0060	230(A)7200	SOLID SLAB SODDING	3,991.000	SY
	0070	233(A)0200	VEGETATIVE MULCHING	1.000	AC
	0080	240(A)2200	REMOVING TREES 6" TO 12" IN DIAMETER	2.000	EA
	0090	303(A)1200	AGGREGATE BASE TYPE A	1,172.000	CY
	0100	504(F)5600	HANDRAILING	75.000	LF
	0110	609(C)4400	CONCRETE HEADER CURB (6"X 16")	949.000	LF
	0120	610(A)5210	5" CONCRETE SIDEWALK	5,562.000	SY
	0130	610(B)5310	6" CONCRETE DRIVEWAY	185.000	SY
	0140	610(I)6000	TACTILE WARNING DEVICE-NEW	316.000	SF
	0150	612(A)3200	MANHOLES ADJUST TO GRADE	3.000	EA
	0160	612(F)3700	METER BOXES ADJUST TO GRADE	1.000	EA
	0170	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
	0180	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	185.000	SY
	0190	619(B)6400	REMOVAL OF CURB	36.000	LF
	0200	619(B)6404	REMOVAL OF SIDEWALK	274.000	SY
0002	TRAFFIC - BASE BID				
	0210	805(B)3300	(PL)RESET OF PULL BOX	1.000	EA
	0220	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	5.000	EA
	0230	853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	75.000	EA
	0240	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	1,202.000	LF
	0250	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	838.000	LF
0003	TRAFFIC CONTROL - BASE BID				
	0260	880(A)6200	ARROW DISPLAY(TYPE A)	720.000	SD
	0270	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	360.000	SD
	0280	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	450.000	SD
	0290	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	90.000	SD
	0300	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	180.000	SD
	0310	880(E)6600	WARNING LIGHTS(TYPE A)	720.000	SD
	0320	880(G)6805	CHANNELIZER CONES	5,580.000	SD
0004	STAKING - BASE BID				
	0330	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION - BASE BID				
	0340	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	0350	641 2110	MOBILIZATION	1.000	LSUM

Proposal: 250140 **Let Date:** May 08, 2025 **Call Order:** 115
J/P Num: 36724(04) **Proj. Num:** STP-214D(175)AG
Counties: CLEVELAND
Description: PEDESTRIAN AND BIKE IMPROVEMENTS (TRAIL AND SIDEWALKS)
SH-77 (12TH AVE NE)/ CITY STREET (W BROOKS ST): SH-77, FROM THE INTERSECTION OF ROBINSON STREET, EXTEND NORTH. CITY STREET (W BROOKS ST), FROM WYLIE RD, EXTEND EAST.
PROJECT LENGTH = 1.965 MILES.

	Line #		Item Description	Quantity	Unit
0006	ROADWAY - ADD ALTERNATE 1				
	0360	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
	0370	202(A)2200	UNCLASSIFIED EXCAVATION	133.000	CY
	0380	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
	0390	221(B)2300	TEMPORARY SILT FENCE	211.000	LF
	0400	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	2.000	EA
	0410	230(A)7200	SOLID SLAB SODDING	438.000	SY
	0420	303(A)1200	AGGREGATE BASE TYPE A	166.000	CY
	0430	609(C)4400	CONCRETE HEADER CURB (6"X 16")	180.000	LF
	0440	610(A)5210	5" CONCRETE SIDEWALK	594.000	SY
	0450	610(B)5310	6" CONCRETE DRIVEWAY	267.000	SY
	0460	610(I)6000	TACTILE WARNING DEVICE-NEW	60.000	SF
	0470	612(F)3700	METER BOXES ADJUST TO GRADE	19.000	EA
	0480	612(G)3810	FIRE HYDRANT RELOCATION	2.000	EA
	0490	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
	0500	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	267.000	SY
	0510	619(B)6404	REMOVAL OF SIDEWALK	30.000	SY
0007	TRAFFIC - ADD ALTERNATE 1				
	0520	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
	0530	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	79.000	LF
0008	TRAFFIC CONTROL - ADD ALTERNATE 1				
	0540	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	120.000	SD
	0550	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	180.000	SD
	0560	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	60.000	SD
	0570	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	60.000	SD
	0580	880(E)6600	WARNING LIGHTS(TYPE A)	240.000	SD
	0590	880(G)6805	CHANNELIZER CONES	990.000	SD
	0600	880(I)7000	FLAGGER	60.000	SD
0009	STAKING - ADD ALTERNATE 1				
	0610	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0010	CONSTRUCTION - ADD ALTERNATE 1				
	0620	641 2110	MOBILIZATION	1.000	LSUM

Proposal:250140 **Let Date:**May 08, 2025 **Call Order:**115
J/P Num:36724(04) **Proj. Num:**STP-214D(175)AG
Counties:CLEVELAND
Description:PEDESTRIAN AND BIKE IMPROVEMENTS (TRAIL AND SIDEWALKS)
SH-77 (12TH AVE NE)/ CITY STREET (W BROOKS ST): SH-77, FROM THE INTERSECTION OF ROBINSON STREET, EXTEND NORTH. CITY STREET (W BROOKS ST), FROM WYLIE RD, EXTEND EAST.
PROJECT LENGTH = 1.965 MILES.

	Line #		Item Description	Quantity	Unit
0011	ROADWAY - ADD ALTERNATE 2				
	0630	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
	0640	202(A)2200	UNCLASSIFIED EXCAVATION	288.000	CY
	0650	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
	0660	221(B)2300	TEMPORARY SILT FENCE	561.000	LF
	0670	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	4.000	EA
	0680	230(A)7200	SOLID SLAB SODDING	793.000	SY
	0690	240(A)2200	REMOVING TREES 6" TO 12" IN DIAMETER	2.000	EA
	0700	303(A)1200	AGGREGATE BASE TYPE A	282.000	CY
	0710	504(F)5600	HANDRAILING	31.000	LF
	0720	610(A)5210	5" CONCRETE SIDEWALK	1,056.000	SY
	0730	610(B)5310	6" CONCRETE DRIVEWAY	605.000	SY
	0740	610(I)6000	TACTILE WARNING DEVICE-NEW	60.000	SF
	0750	612(A)3200	MANHOLES ADJUST TO GRADE	5.000	EA
	0760	612(F)3700	METER BOXES ADJUST TO GRADE	22.000	EA
	0770	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
	0780	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	605.000	SY
	0790	619(B)6400	REMOVAL OF CURB	16.000	LF
	0800	619(B)6404	REMOVAL OF SIDEWALK	45.000	SY
0012	TRAFFIC - ADD ALTERNATE 2				
	0810	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	11.000	EA
	0820	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	106.000	LF
0013	TRAFFIC CONTROL - ADD ALTERNATE 2				
	0830	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	240.000	SD
	0840	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	360.000	SD
	0850	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	120.000	SD
	0860	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	120.000	SD
	0870	880(E)6600	WARNING LIGHTS(TYPE A)	480.000	SD
	0880	880(G)6805	CHANNELIZER CONES	1,980.000	SD
	0890	880(I)7000	FLAGGER	120.000	SD
0014	STAKING - ADD ALTERNATE 2				
	0900	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0015	CONSTRUCTION - ADD ALTERNATE 2				
	0910	641 2110	MOBILIZATION	1.000	LSUM