Proposal: 250143 **Let Date:** May 08, 2025 **Call Order:** 140
J/P Num: 31084(04) **Proj. Num:** NHPP-014N(134)PM
Counties: TULSA
Description: BRIDGE REHABILITATION
US-75: OVER BIRD CREEK OVERFLOW, 3.4 MILES
NORTH OF THE SH-11 INTERSECTION NEAR TULSA.
PROJECT LENGTH = 0.328 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,000.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,500.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	1,500.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	150.000	LF
0060	230(A)7200	SOLID SLAB SODDING	5,000.000	SY
0070	307(K)4200	STABILIZED SUBGRADE	2,140.000	SY
0080	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	733.000	TON
0090	407(B)7300	TACK COAT	642.000	GAL
0100	408 8100	PRIME COAT	1,068.000	GAL
0110	411(B)1300	SUPERPAVE, TYPE S3(PG 76-28 OK)	299.000	TON
0120	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,068.000	TON
0130	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	174.000	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	541.000	TON
0150	412 3100	COLD MILLING PAVEMENT	2,892.000	SY
0160	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	80.000	SY
0170	414(G)5800	P.C. CONCRETE FOR PAVEMENT	20.000	CY
0180	509(A)0200	CLASS AA CONCRETE	370.000	CY
0190	613(B)5500	12" CORR. GALV. STEEL PIPE	300.000	LF
0200	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,970.000	SY
0210	619(B)6396	REMOVAL OF GUARDRAIL	972.000	LF
0220	619(C)6600	SAWING PAVEMENT	206.000	LF
0230	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	850.000	LF
0240	623(G)1820	GUARDRAIL END TREATMENT (31")	3.000	EA
0250	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA

Proposal: 250143 **Let Date:** May 08, 2025 **Call Order:** 140
J/P Num: 31084(04) **Proj. Num:** NHPP-014N(134)PM
Counties: TULSA
Description: BRIDGE REHABILITATION
US-75: OVER BIRD CREEK OVERFLOW, 3.4 MILES
NORTH OF THE SH-11 INTERSECTION NEAR TULSA.
PROJECT LENGTH = 0.328 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE "A" - NBI NO.18135			
0260	501(G)1800	CLSM BACKFILL	140.000	CY
0270	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0280	504(A)5200	APPROACH SLAB	387.400	SY
0290	504(B)5300	SAW-CUT GROOVING	2,811.000	SY
0300	504(E)5520	42" F-SHAPED PARAPET	925.000	LF
0310	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	60.000	EA
0320	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	36.000	EA
0330	509(A)0210	CLASS AA CONCRETE	636.600	CY
0340	509(D)0510	CLASS C CONCRETE	8.000	CY
0350	511(B)2310	EPOXY COATED REINFORCING STEEL	210,720.000	LB
0360	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,132.000	SY
0370	517 9110	ELASTOMERIC COATING	2,386.000	SF
0380	518(B)0300	SEALED EXPANSION JOINTS	343.500	LF
0390	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF
0400	520(C)1400	EPOXY RESIN, ABOVE WATER	1.000	GAL
0410	521(A)2200	PNEUMATICALLY PLACED MORTAR	25.000	SY
0420	523(A)3200	SEALER CRACK PREPARATION	58.000	LF
0430	523(B)3300	SEALER RESIN	1.000	GAL
0440	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	250.000	SF
0450	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	40.000	SY
0460	540 8104	(PL)REPAIR BRIDGE ITEMS	5.000	EA
0470	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	BRIDGE "B" - NBI NO.22409			
0480	501(G)1800	CLSM BACKFILL	100.000	CY
0490	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0500	504(A)5200	APPROACH SLAB	275.600	SY
0510	504(B)5300	SAW-CUT GROOVING	398.000	SY
0520	504(E)5500	CONCRETE PARAPET	188.000	LF
0530	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	52.000	EA
0540	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0550	509(A)0210	CLASS AA CONCRETE	55.600	CY
0560	511(B)2310	EPOXY COATED REINFORCING STEEL	15,280.000	LB
0570	513(B)4300	CLASS B BRIDGE DECK REPAIR	100.000	SY
0580	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,977.000	SY
0590	517 9110	ELASTOMERIC COATING	1,715.000	SF
0600	518(B)0300	SEALED EXPANSION JOINTS	121.500	LF
0610	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF
0620	520(C)1400	EPOXY RESIN, ABOVE WATER	1.000	GAL
0630	521(A)2200	PNEUMATICALLY PLACED MORTAR	30.000	SY
0640	523(C)3400	DECK AREA SEALED (FLOODCOATS)	1,748.000	SY
0650	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	250.000	SF
0660	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	15.000	SY
0670	540 8104	(PL)REPAIR BRIDGE ITEMS	5.000	EA
0680	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal: 250143 **Let Date:** May 08, 2025 **Call Order:** 140
J/P Num: 31084(04) **Proj. Num:** NHPP-014N(134)PM
Counties: TULSA
Description: BRIDGE REHABILITATION
US-75: OVER BIRD CREEK OVERFLOW, 3.4 MILES
NORTH OF THE SH-11 INTERSECTION NEAR TULSA.
PROJECT LENGTH = 0.328 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0690	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	65,300.000	LF
0700	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	25,530.000	LF
0710	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	960.000	EA
0720	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	960.000	EA
0730	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,380.000	SD
0740	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	30.000	SD
0750	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	3,170.000	LF
0760	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,800.000	LF
0770	880(A)6220	ARROW DISPLAY(TYPE C)	720.000	SD
0780	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	138,060.000	SD
0790	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	25,110.000	SD
0800	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	29,130.000	SD
0810	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	16,950.000	SD
0820	880(E)6607	WARNING LIGHTS(TYPE B)	55,740.000	SD
0830	880(E)6616	WARNING LIGHTS(TYPE D)	48,720.000	SD
0840	880(F)6700	DRUMS	48,720.000	SD
0850	880(G)6800	TUBE CHANNELIZERS	345,600.000	SD
0860	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,440.000	SD
0005	SIGNING AND STRIPING			
0870	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	800.000	LF
0880	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
0890	850(A)1200	SHEET ALUMINUM SIGNS	12.000	SF
0900	851(C)2420	2 1/4" SQUARE TUBE POST	48.000	LF
0910	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	9,060.000	LF
0006	TRAFFIC SAFETY			
0920	619(B)6432	REMOVAL OF CABLE BARRIER	4,010.000	LF
0930	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	3,490.000	LF
0940	628(C)7400	END ANCHORS	12.000	EA
0950	628(F)7700	(PL)HIGH TENSION CABLE BARR. RE-TENSION	2.000	EA
0960	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	30.000	EA
0970	871(A)2200	IMPACT ATTENUATOR	1.000	EA
0007	STAKING			
0980	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION			
0990	641 2100	MOBILIZATION	1.000	LSUM