Proposal: 250149 **Let Date:** May 08, 2025 **Call Order:** 126
J/P Num: 37999(04) **Proj. Num:** TAP-224E(108)TP
Counties: GARFIELD
Description: PEDESTRIAN IMPROVEMENTS
CITY STREET (W. WILLOW RD): FROM THE INTERSECTION OF N OAKWOOD RD, EXTEND WEST IN THE CITY OF ENID.
PROJECT LENGTH = 0.518 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	1,200.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	500.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	500.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	35.000	LF
0050	221(G)2800	TEMPORARY FIBER LOG	96.000	LF
0060	230(A)7200	SOLID SLAB SODDING	11,200.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	2.300	AC
0080	240(A)2230	REMOVING TREES 25" & MORE IN DIAMETER	10.000	EA
0090	303(A)1200	AGGREGATE BASE TYPE A	582.140	CY
0100	325 0100	SEPARATOR FABRIC	3,492.830	SY
0110	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	360.110	SY
0120	414(G)5800	P.C. CONCRETE FOR PAVEMENT	60.020	CY
0130	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	92.110	CY
0140	501(G)1810	CLSM BACKFILL	3.000	CY
0150	509(A)0200	CLASS AA CONCRETE	175.760	CY
0160	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	5.370	CY
0170	509(D)0500	CLASS C CONCRETE	68.750	CY
0180	511(A)2200	REINFORCING STEEL	21,309.910	LB
0190	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	139.000	LF
0200	610(A)5220	6" CONCRETE SIDEWALK	2,809.870	SY
0210	610(I)6000	TACTILE WARNING DEVICE-NEW	200.000	SF
0220	611(G)0350	INLET (SMD-TYPE 1)	2.000	EA
0230	611(L)1600	JUNCTION BOXES	105.450	CF
0240	612(A)3200	MANHOLES ADJUST TO GRADE	2.000	EA
0250	612(E)3600	VALVE BOXES ADJUST TO GRADE	1.000	EA
0260	613(B)5516	24" CORR. GALV. STEEL PIPE	10.000	LF
0270	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	122.000	LF
0280	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	324.000	LF
0290	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	384.000	LF
0300	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0310	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0320	613(M)6900	TYPE A3 CULVERT END TREATMENT	2.000	EA
0330	613(M)6940	TYPE AAA3 CULVERT END TREATMENT	2.000	EA
0340	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0350	619(B)6356	REMOVAL OF CURB AND GUTTER	141.000	LF
0360	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	390.220	SY
0370	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	16.670	SY
0380	619(B)6392	REMOVAL OF EXISTING STRUCTURES	2.000	EA
0390	619(B)6404	REMOVAL OF SIDEWALK	435.000	SY
0400	619(C)6600	SAWING PAVEMENT	287.000	LF

Proposal: 250149 **Let Date:** May 08, 2025 **Call Order:** 126
J/P Num: 37999(04) **Proj. Num:** TAP-224E(108)TP
Counties: GARFIELD
Description: PEDESTRIAN IMPROVEMENTS
CITY STREET (W. WILLOW RD): FROM THE INTERSECTION OF N OAKWOOD RD, EXTEND WEST IN THE CITY OF ENID.
PROJECT LENGTH = 0.518 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0410	810(A)8210	REFLECTIVE SHEETING	28.000	SF
0420	836 7110	RECTANGULAR RAPID FLASHING BEACON	4.000	EA
0430	850(A)1200	SHEET ALUMINUM SIGNS	37.000	SF
0440	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	754.110	LF
0450	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	523.000	LF
0460	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	16.000	EA
0470	871(B)2300	CONST.ZONE IMPACT ATTEN.	600.000	SD
0475	871(C)2410	RELOCATION OF IMPACT ATTENUATOR	3.000	EA
0480	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	336.000	LF
0490	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	240.000	LF
0500	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,048.000	SD
0510	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,768.000	SD
0520	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	300.000	SD
0530	880(E)6600	WARNING LIGHTS(TYPE A)	600.000	SD
0540	880(G)6805	CHANNELIZER CONES	1,080.000	SD
0550	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	328.000	SD
0003	STAKING			
0560	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0570	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0580	641 2110	MOBILIZATION	1.000	LSUM