Proposal: 250152 **Let Date:** June 12, 2025 **Call Order:** 305
J/P Num: 37940(04) **Proj. Num:** TAP-209C(109)AG
Counties: CANADIAN
Description: PEDESTRIAN IMPROVEMENTS (MULTIMODAL TRAIL)
CITY STREET (S YUKON PKWY): FROM THE INTERSECTION OF NW 10TH ST, EXTEND NORTH IN THE CITY OF YUKON.
PROJECT LENGTH = 0.526 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	756.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	2,469.000	LF
0050	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	8.000	EA
0060	230(A)7200	SOLID SLAB SODDING	1,905.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	1.000	AC
0080	241 3100	MOWING	2.000	AC
0090	303(A)1200	AGGREGATE BASE TYPE A	283.000	CY
0100	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	231.000	TON
0110	501(F)1700	GRANULAR BACKFILL	11.000	CY
0120	504(F)5600	HANDRAILING	187.000	LF
0130	509(B)0300	CLASS A CONCRETE	59.000	CY
0140	511(A)2200	REINFORCING STEEL	4,030.000	LB
0150	511(B)2300	EPOXY COATED REINFORCING STEEL	2,050.000	LB
0160	518(C)0400	RAPID CURE JOINT SEALANT	187.000	LF
0170	610(A)5200	4" CONCRETE SIDEWALK	2,387.000	SY
0180	610(A)5220	6" CONCRETE SIDEWALK	41.000	SY
0190	610(B)5310	6" CONCRETE DRIVEWAY	245.000	SY
0200	610(B)5320	8" CONCRETE DRIVEWAY	281.000	SY
0210	610(I)6000	TACTILE WARNING DEVICE-NEW	245.000	SF
0220	611(G)0350	INLET (SMD-TYPE 1)	1.000	EA
0230	613(A)5216	24" R.C.PIPE CLASS III	72.000	LF
0240	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	115.000	LF
0250	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	20.000	LF
0260	613(M)6904	TYPE B3 CULVERT END TREATMENT	1.000	EA
0270	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0280	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	553.000	SY
0290	619(B)6400	REMOVAL OF CURB	39.000	LF
0300	619(B)6404	REMOVAL OF SIDEWALK	12.000	SY
0310	619(C)6600	SAWING PAVEMENT	103.000	LF
0320	631(A)9200	(SP)STATIONARY BOLLARD	11.000	EA

Proposal:250152 **Let Date:**June 12, 2025 **Call Order:**305
J/P Num:37940(04) **Proj. Num:**TAP-209C(109)AG
Counties:CANADIAN
Description:PEDESTRIAN IMPROVEMENTS (MULTIMODAL TRAIL)
CITY STREET (S YUKON PKWY): FROM THE INTERSECTION OF NW 10TH ST, EXTEND NORTH IN THE CITY OF YUKON.
PROJECT LENGTH = 0.526 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0330	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	10.000	DAY
0335	802(A)0265	3" GALV.STEEL ELECT.COND. TRENCHED	50.000	LF
0340	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
0350	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	320.000	LF
0360	803(A)1210	PULL BOX(SIZE I)	3.000	EA
0370	804(A)2200	STRUCTURAL CONCRETE	1.830	CY
0380	804(B)2300	REINFORCING STEEL	130.200	LB
0390	805(A)3208	REMOVAL OF PULL BOX	3.000	EA
0400	805(D)3500	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
0410	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0420	830 2100	PEDESTRIAN PUSH BUTTON	2.000	EA
0430	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	2.000	EA
0440	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	800.000	LF
0450	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	100.000	LF
0460	850(A)1200	SHEET ALUMINUM SIGNS	17.000	SF
0470	851(B)2305	2"@3.65 GALV.STL.PIPE POST	48.000	LF
0480	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	564.000	LF
0490	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	732.000	LF
0500	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	26.000	EA
0510	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	180.000	SD
0520	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	540.000	SD
0530	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	270.000	SD
0540	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	360.000	SD
0550	880(E)6607	WARNING LIGHTS(TYPE B)	270.000	SD
0560	880(E)6616	WARNING LIGHTS(TYPE D)	900.000	SD
0570	880(F)6700	DRUMS	900.000	SD
0580	880(G)6805	CHANNELIZER CONES	5,850.000	SD
0003	STAKING			
0590	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0600	641 2110	MOBILIZATION	1.000	LSUM