Proposal: 250156 **Let Date:** June 12, 2025 **Call Order:** 355
J/P Num: 35004(04) **Proj. Num:** STP-263D(114)CI
Counties: POTTAWATOMIE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-126/COLEMAN ROAD):
OVER UNNAMED TRIBUTARY OF LITTLE RIVER,
0.34 MILES WEST OF SH-9A NEAR HARJO.
PROJECT LENGTH = 0.127 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,683.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	25.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	220.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	84.000	LF
0070	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	6.000	CY
0080	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	2.000	EA
0090	230(A)7200	SOLID SLAB SODDING	2,787.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	0.580	AC
0110	241 3100	MOWING	1.000	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	318.000	CY
0130	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	104.000	TON
0140	611(G)9020	INLET CDI RCP DES. 6	1.000	EA
0150	611(G)9054	INLET CDI 30SK RCP DES.2	1.000	EA
0160	611(H)0734	ADD'L DEPTH IN INLET CDI RCP 30SK DES. 2	7.000	VF
0170	613(A)5216	24" R.C.PIPE CLASS III	28.000	LF
0180	613(A)5232	48" R.C.PIPE CLASS III	84.000	LF
0190	613(B)5516	24" CORR. GALV. STEEL PIPE	64.000	LF
0200	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	34.000	LF
0210	613(L)6736	48" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0220	613(P)7404	24" GALV. STEEL CULVERT END SEC. RND.	2.000	EA
0230	613(P)7450	21" X 15" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
0240	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0250	629(A)7200	MAILBOX INSTALLATION-SINGLE	1.000	EA
0260	629(E)7600	MAILBOX	1.000	EA
0002	BRIDGE A			
0270	202(A)2210	UNCLASSIFIED EXCAVATION	3,150.000	CY
0280	303(A)1200	AGGREGATE BASE TYPE A	17.000	CY
0290	326(B)1300	GEOGRID REINFORCEMENT	50.000	SY
0300	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	179.000	CY
0310	501(F)1700	GRANULAR BACKFILL	320.000	CY
0320	509(A)0210	CLASS AA CONCRETE	436.800	CY
0330	511(A)2210	REINFORCING STEEL	66,160.000	LB
0340	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	43.000	LF
0003	SIGNING, STRIPING, SAFETY			
0350	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
0360	853 5115	DELINEATORS(TYPE 2, CODE 1)	4.000	EA

Proposal:250156 **Let Date:**June 12, 2025 **Call Order:**355
J/P Num:35004(04) **Proj. Num:**STP-263D(114)CI
Counties:POTTAWATOMIE
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-126/COLEMAN ROAD):
OVER UNNAMED TRIBUTARY OF LITTLE RIVER,
0.34 MILES WEST OF SH-9A NEAR HARJO.
PROJECT LENGTH = 0.127 MILES

	Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL				
	0370	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,520.000	SD
	0380	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,440.000	SD
	0390	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
	0400	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,080.000	SD
	0410	880(E)6600	WARNING LIGHTS(TYPE A)	720.000	SD
0005	STAKING				
	0420	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION				
	0430	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	0440	641 2100	MOBILIZATION	1.000	LSUM