Proposal:250161 **Let Date:**June 19, 2025 **Call Order:**040
J/P Num:37900(05) **Proj. Num:**CR-34501A
Counties:TULSA
Description:BRIDGE REHABILITATION
CREEK TURNPIKE (SH-364): OVER HAIKEY CREEK,
1.2 MILES SOUTHEAST OF THE US-64 INTERCHANGE
IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.96 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	108,381.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,500.000	CY
0040	202(F)2700	EMBANKMENTS	27,889.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	15,040.000	LF
0070	221(G)2800	TEMPORARY FIBER LOG	238.000	LF
0080	221(M)3400	TEMPORARY ENVIRONMENTAL FENCE	4,048.000	LF
0090	230(A)7200	SOLID SLAB SODDING	29,360.000	SY
0100	242 4101	STABILIZED CONSTRUCTION EXIT	8.000	EA
0110	307(K)4200	STABILIZED SUBGRADE	7,937.000	SY
0120	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	29,360.000	SY
0130	402(D)2500	TRAFFIC BOUND SURFACE COURSE TYPE D	180,101.000	TON
0140	408 8100	PRIME COAT	2,778.000	GAL
0145	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	253.000	TON
0150	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	8,054.000	SY
0160	414(G)5800	P.C. CONCRETE FOR PAVEMENT	2,014.000	CY
0170	509(A)0200	CLASS AA CONCRETE	32.000	CY
0180	509(B)0300	CLASS A CONCRETE	63.000	CY
0190	509(B)0310	CLASS A CONCRETE(LONG. BAR. DES. 1-A)	39.000	CY
0200	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	3.000	CY
0210	511(A)2200	REINFORCING STEEL	7,186.000	LB
0215	610(A)5200	4" CONCRETE SIDEWALK	667.000	SY
0220	610(C)5400	4" CONCRETE DIVIDING STRIP	175.000	SY
0230	611(G)0350	INLET (SMD-TYPE 1)	1.000	EA
0240	611(G)8150	INLET - LONG. BARRIER - TYPE I, DES. 1	1.000	EA
0250	611(G)8170	INLET - LONG. BARRIER - TYPE II, DES. 1	1.000	EA
0260	611(H)0656	ADD'L DEPTH IN INLET MED. BAR. TYPE I, DES. 1	1.000	VF
0270	611(H)0660	ADD'L DEPTH IN INLET MED. BAR. TYPE II, DES. 1	5.000	VF
0280	611(H)0980	ADD'L DEPTH IN INLET SMD TYPE 1	1.000	VF
0290	613(B)5544	60" CORR. GALV. STEEL PIPE	400.000	LF
0300	613(E)5966	12” CORRUGATED HDPE SLOTTED DRAIN	1,482.000	LF
0310	616(P)4156	12" HDPE PIPE	48.000	LF
0320	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0330	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	784.000	SY
0340	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,978.000	SY
0350	619(B)6368	REMOVAL OF DRAINAGE INLETS	4.000	EA
0360	619(B)6396	REMOVAL OF GUARDRAIL	438.000	LF
0370	619(B)6416	REMOVAL OF CONCRETE MEDIAN BARRIER	740.000	LF
0380	619(B)6432	REMOVAL OF CABLE BARRIER	1,819.000	LF
0390	619(B)6460	REMOVAL OF 4" CONCRETE DIVIDING STRIP	135.000	SY
0400	619(C)6600	SAWING PAVEMENT	3,401.000	LF
0410	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	400.000	LF
0420	623(G)1800	GUARDRAIL END TREATMENT (GET)	1.000	EA
0430	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	1.000	EA

Proposal:250161 **Let Date:**June 19, 2025 **Call Order:**040
J/P Num:37900(05) **Proj. Num:**CR-34501A
Counties:TULSA
Description:BRIDGE REHABILITATION
CREEK TURNPIKE (SH-364): OVER HAIKEY CREEK,
1.2 MILES SOUTHEAST OF THE US-64 INTERCHANGE
IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.96 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0440	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	118.000	LF
0450	627(B)6300	CONCRETE LONGITUDINAL BARRIER END SEC.	1.000	EA
0002	RESTORATION			
0460	205(A)6210	TYPE A-SALVAGED TOPSOIL	760.000	CY
0470	231 8100	PLANTS	1.000	LSUM
0480	233(D)0500	EXCELSIOR MAT	3,560.000	SY
0003	BRIDGE NO 15.05S			
0490	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	39.000	CY
0500	501(G)1800	CLSM BACKFILL	6.000	CY
0510	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	24,395.190	LF
0520	504(A)5200	APPROACH SLAB	684.100	SY
0530	504(B)5300	SAW-CUT GROOVING	25,926.900	SY
0540	504(E)5520	42" F-SHAPED PARAPET	10,083.800	LF
0550	506(A)7200	STRUCTURAL STEEL	117,500.000	LB
0560	507(C)8400	ELASTOMERIC BEARING PADS	484.000	EA
0570	509(A)0210	CLASS AA CONCRETE	7,385.300	CY
0580	509(B)0320	CLASS A CONCRETE	16.300	CY
0590	509(D)0510	CLASS C CONCRETE	24.000	CY
0600	510(C)1450	SLOPE WALL (5")	965.000	SY
0610	511(A)2210	REINFORCING STEEL	2,320.000	LB
0620	511(B)2310	EPOXY COATED REINFORCING STEEL	1,777,570.000	LB
0630	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	55,077.000	SY
0640	517 9110	ELASTOMERIC COATING	14,291.000	SF
0650	518(B)0310	EXPANSION JOINT SYSTEM	736.340	LF
0660	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	40.000	LF
0670	520(C)1400	EPOXY RESIN, ABOVE WATER	3.400	GAL
0680	521(A)2200	PNEUMATICALLY PLACED MORTAR	12.000	SY
0690	523(A)3200	SEALER CRACK PREPARATION	1,788.000	LF
0700	523(B)3300	SEALER RESIN	17.900	GAL
0710	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	12.000	SY
0720	601(B)1230	TYPE I-A PLAIN RIPRAP	529.000	TON
0730	601(C)1310	TYPE I-A FILTER BLANKET	168.000	TON
0740	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	123.000	LF
0750	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
0760	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0770	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:250161 **Let Date:**June 19, 2025 **Call Order:**040
J/P Num:37900(05) **Proj. Num:**CR-34501A
Counties:TULSA
Description:BRIDGE REHABILITATION
CREEK TURNPIKE (SH-364): OVER HAIKEY CREEK,
1.2 MILES SOUTHEAST OF THE US-64 INTERCHANGE
IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.96 MILES

Line #		Item Description	Quantity	Unit
0004	BRIDGE NO 15.05N			
0780	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	39.000	CY
0790	501(G)1800	CLSM BACKFILL	6.000	CY
0800	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	24,509.040	LF
0810	504(A)5200	APPROACH SLAB	576.800	SY
0820	504(B)5300	SAW-CUT GROOVING	25,868.300	SY
0830	504(E)5520	42" F-SHAPED PARAPET	10,048.000	LF
0840	506(A)7200	STRUCTURAL STEEL	117,500.000	LB
0850	507(C)8400	ELASTOMERIC BEARING PADS	484.000	EA
0860	509(A)0210	CLASS AA CONCRETE	7,369.800	CY
0870	509(B)0320	CLASS A CONCRETE	16.300	CY
0880	510(C)1450	SLOPE WALL (5")	678.000	SY
0890	511(A)2210	REINFORCING STEEL	2,320.000	LB
0900	511(B)2310	EPOXY COATED REINFORCING STEEL	1,752,700.000	LB
0910	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	54,953.000	SY
0920	517 9110	ELASTOMERIC COATING	13,855.000	SF
0930	518(B)0310	EXPANSION JOINT SYSTEM	736.340	LF
0940	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF
0950	520(C)1400	EPOXY RESIN, ABOVE WATER	4.600	GAL
0960	521(A)2200	PNEUMATICALLY PLACED MORTAR	11.000	SY
0970	523(A)3200	SEALER CRACK PREPARATION	1,529.000	LF
0980	523(B)3300	SEALER RESIN	15.300	GAL
0990	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	11.000	SY
1000	601(B)1230	TYPE I-A PLAIN RIPRAP	584.000	TON
1010	601(C)1310	TYPE I-A FILTER BLANKET	186.000	TON
1020	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	105.000	LF
1030	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	80.000	LF
1040	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
1050	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
1060	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	4,217.000	LF
0005	TRAFFIC SIGNING AND STRIPING			
1070	804(A)2200	STRUCTURAL CONCRETE	24.000	CY
1080	804(B)2300	REINFORCING STEEL	2,075.000	LB
1090	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	7.000	EA
1100	805(D)3532	(PL)REMOVE & RESET OVERHEAD SIGN STR.	1.000	EA
1110	850(A)1200	SHEET ALUMINUM SIGNS	70.000	SF
1120	853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	3.000	EA
1130	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	39,903.000	LF
0006	TRAFFIC BARRIERS			
1140	628 7100	INSTALLATION OF CABLE BARRIER SYSTEM	1,819.000	LF
1150	628(C)7400	END ANCHORS	3.000	EA
1160	628(E)7600	CABLE BARRIER TENSION METER	2.000	EA
1170	870(A)1100	SAND FILLED IMPACT ATTEN.MODULE	37.000	EA
1180	870(C)1300	SAND FILLED IMPACT ATTEN.MODULE REMOVAL	1.000	LSUM

Proposal:250161 **Let Date:**June 19, 2025 **Call Order:**040
J/P Num:37900(05) **Proj. Num:**CR-34501A
Counties:TULSA
Description:BRIDGE REHABILITATION
CREEK TURNPIKE (SH-364): OVER HAIKEY CREEK,
1.2 MILES SOUTHEAST OF THE US-64 INTERCHANGE
IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.96 MILES

	Line #		Item Description	Quantity	Unit
0007	TRAFFIC CONTROL				
	1190	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	69,760.000	LF
	1200	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,220.000	SD
	1210	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	9,131.000	LF
	1220	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	17,056.000	LF
	1230	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	24,800.000	SD
	1240	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,680.000	SD
	1250	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	22,000.000	SD
	1260	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	6,280.000	SD
	1270	880(E)6607	WARNING LIGHTS(TYPE B)	15,960.000	SD
	1280	880(F)6700	DRUMS	75,285.000	SD
	1290	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,000.000	HOUR
	1300	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,677.000	SD
0008	STAKING				
	1310	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0009	CONSTRUCTION				
	1320	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1330	640(A)1200	FIELD OFFICE	1.000	EA
	1340	641 2100	MOBILIZATION	1.000	LSUM