Proposal:250163 **Let Date:**June 19, 2025 **Call Order:**425
J/P Num:20922(07) **Proj. Num:**STP-239B(057)PM
Counties:LATIMER
Description:WIDEN AND RESURFACE
US-270: FROM 3.2 MILES NORTHEAST OF THE SH-1 INTERSECTION,
EXTEND EAST NEAR HARTSHORNE.
PROJECT LENGTH = 2.574 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	21,887.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	6,961.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	3,110.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	1,274.000	LF
0070	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	192.000	CY
0080	230(A)7200	SOLID SLAB SODDING	109,803.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	23.000	AC
0100	241 3100	MOWING	46.000	AC
0110	303(A)1200	AGGREGATE BASE TYPE A	13,163.000	CY
0120	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	40,528.000	SY
0130	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,859.000	TON
0140	407(B)7300	TACK COAT	9,987.000	GAL
0150	408 8100	PRIME COAT	24,594.000	GAL
0160	409(A)9200	FABRIC REINFORCEMENT	12,791.000	SY
0170	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	6,090.000	TON
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	9,303.000	TON
0190	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	4,060.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	3,310.000	TON
0210	412 3100	COLD MILLING PAVEMENT	1,334.000	SY
0220	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	134.000	CY
0230	509(A)0200	CLASS AA CONCRETE	579.000	CY
0240	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	35.560	CY
0250	509(D)0500	CLASS C CONCRETE	142.650	CY
0260	511(A)2200	REINFORCING STEEL	94,318.000	LB
0270	611(G)0354	INLET (SMD-TYPE 2)	1.000	EA
0280	613(A)5208	18" R.C.PIPE CLASS III	200.000	LF
0290	613(A)5216	24" R.C.PIPE CLASS III	1,573.000	LF
0300	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	108.000	LF
0310	613(H)6210	8" PERFORATED PIPE UNDERDRAIN ROUND	966.000	LF
0320	613(I)6315	8" NON-PERF.PIPE UNDERDRAIN RND.	322.000	LF
0330	613(M)6960	TYPE A4 CULVERT END TREATMENT	3.000	EA
0340	613(M)6964	TYPE B4 CULVERT END TREATMENT	31.000	EA
0350	613(M)7004	TYPE A6 CULVERT END TREATMENT	5.000	EA
0360	613(M)7008	TYPE B6 CULVERT END TREATMENT	27.000	EA
0370	613(R)7600	STANDARD BEDDING MATERIAL, CLASS A	70.000	CY
0380	613(V)8000	TRENCH EXCAVATION	46.000	CY
0390	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0400	619(B)6300	REMOVAL OF HEADWALL	28.000	EA
0410	619(C)6600	SAWING PAVEMENT	27,187.000	LF
0420	624(A)3200	FENCE-STYLE WWF	104.000	LF
0430	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	9,928.000	LF
0440	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	2,920.000	LF
0450	624(E)3620	FENCE-STYLE CLF (6'HIGH, CLASS A)	243.000	LF
0460	624(F)3763	GATES-STYLE CLF (6'HIGH X 11.5'LONG)	2.000	EA

Proposal:250163 **Let Date:**June 19, 2025 **Call Order:**425
J/P Num:20922(07) **Proj. Num:**STP-239B(057)PM
Counties:LATIMER
Description:WIDEN AND RESURFACE
US-270: FROM 3.2 MILES NORTHEAST OF THE SH-1 INTERSECTION,
EXTEND EAST NEAR HARTSHORNE.
PROJECT LENGTH = 2.574 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	624(F)3772	GATES-STYLE CLF (6'HIGH X 16'LONG)	1.000	EA
0480	629(A)7200	MAILBOX INSTALLATION-SINGLE	12.000	EA
0490	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	12.000	EA
0500	629(E)7600	MAILBOX	12.000	EA
0002	TRAFFIC CONTROL			
0510	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	27,500.000	LF
0520	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	16,963.000	LF
0530	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	688.000	EA
0540	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,680.000	SD
0550	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	480.000	SD
0560	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	6,140.000	LF
0570	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,440.000	SD
0580	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,200.000	SD
0590	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,160.000	SD
0600	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,400.000	SD
0610	880(E)6607	WARNING LIGHTS(TYPE B)	18,240.000	SD
0620	880(E)6616	WARNING LIGHTS(TYPE D)	68,400.000	SD
0630	880(F)6700	DRUMS	39,600.000	SD
0640	880(G)6805	CHANNELIZER CONES	160,320.000	SD
0650	880(I)7000	FLAGGER	240.000	SD
0660	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,016.000	SD
0003	TRAFFIC SIGNING AND STRIPING			
0670	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	13,600.000	LF
0680	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	22,667.000	LF
0690	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	22.000	EA
0700	850(A)1200	SHEET ALUMINUM SIGNS	477.000	SF
0710	851(C)2430	2 1/2" SQUARE TUBE POST	735.000	LF
0720	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	49,123.000	LF
0730	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	91.000	LF
0004	STAKING			
0740	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0750	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0760	640(A)1210	FIELD OFFICE	1.000	EA
0770	641 2110	MOBILIZATION	1.000	LSUM