Proposal:250165 **Let Date:**June 19, 2025 **Call Order:**435
J/P Num:38090(04) **Proj. Num:**STP-255N(691)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION
CITY STREET (DANFORTH ROAD): AT
THE INTERSECTION OF KELLY AVENUE
IN THE CITY OF EDMOND.
PROJECT LENGTH = 0.915 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	9,703.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	1,973.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	2,207.000	LF
0060	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	3.600	CY
0070	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	178.000	EA
0080	230(A)7200	SOLID SLAB SODDING	8,435.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	1.640	AC
0100	241 3100	MOWING	3.280	AC
0110	307(K)4200	STABILIZED SUBGRADE	37,993.000	SY
0120	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,137.000	TON
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	6,383.000	TON
0140	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	840.000	SY
0150	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	34,035.000	SY
0160	414(G)5800	P.C. CONCRETE FOR PAVEMENT	9,688.000	CY
0170	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	3.000	CY
0180	509(D)0500	CLASS C CONCRETE	56.000	CY
0190	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	15,217.000	LF
0200	610(A)5200	4" CONCRETE SIDEWALK	6,477.000	SY
0210	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	2,929.000	SY
0220	610(C)5400	4" CONCRETE DIVIDING STRIP	1,705.000	SY
0230	610(I)6000	TACTILE WARNING DEVICE-NEW	581.000	SF
0240	611(A)7210	MANHOLE (4' DIA.)	5.000	EA
0250	611(A)7215	MANHOLE (5' DIA.)	1.000	EA
0260	611(G)0172	INLET W/LRG. JCT. BOX, CI, DES.3	14.000	EA
0270	611(G)0176	INLET W/LRG. JCT. BOX, CI, DES.3(B)	2.000	EA
0280	611(G)0180	INLET W/LRG. JCT. BOX, CI, DES.3(D)	1.000	EA
0290	611(G)7754	INLET CI DES. 2 (STD)	4.000	EA
0300	611(G)7758	INLET CI DES. 2 (B)	1.000	EA
0310	611(G)7766	INLET CI DES. 2 (D)	1.000	EA
0320	611(G)7786	INLET CI DES. 3 (STD)	18.000	EA
0330	611(G)7794	INLET CI DES. 3 (D)	1.000	EA
0340	611(L)1600	JUNCTION BOXES	76.000	CF
0350	613(A)5208	18" R.C.PIPE CLASS III	4,464.000	LF
0360	613(A)5216	24" R.C.PIPE CLASS III	154.000	LF
0370	613(A)5220	30" R.C.PIPE CLASS III	85.000	LF
0380	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	760.000	LF
0390	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	267.000	LF
0400	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0410	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0420	613(M)6984	TYPE BB4 CULVERT END TREATMENT	2.000	EA
0430	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0440	619(B)6356	REMOVAL OF CURB AND GUTTER	8,490.000	LF
0450	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	6,128.000	SY

Proposal:250165 **Let Date:**June 19, 2025 **Call Order:**435
J/P Num:38090(04) **Proj. Num:**STP-255N(691)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION
CITY STREET (DANFORTH ROAD): AT
THE INTERSECTION OF KELLY AVENUE
IN THE CITY OF EDMOND.
PROJECT LENGTH = 0.915 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0460	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	20,064.000	SY
0470	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	4,122.000	SY
0480	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	1,715.000	SY
0490	619(B)6404	REMOVAL OF SIDEWALK	5,299.000	SY
0500	619(C)6600	SAWING PAVEMENT	1,908.000	LF
0510	629(D)7500	REMOVE AND RESET MAILBOX	1.000	EA

Proposal:250165 **Let Date:**June 19, 2025 **Call Order:**435
J/P Num:38090(04) **Proj. Num:**STP-255N(691)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION
CITY STREET (DANFORTH ROAD): AT
THE INTERSECTION OF KELLY AVENUE
IN THE CITY OF EDMOND.
PROJECT LENGTH = 0.915 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC SIGNAL			
0520	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	415.000	LF
0530	802(B)0325	2" PVC SCH.80 PLASTIC CONDUIT TRENCHED	2,910.000	LF
0540	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	710.000	LF
0550	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	180.000	LF
0560	802(B)0356	3" PVC SCH. 80 PLASTIC CONDUIT BORED	1,090.000	LF
0570	803(A)1210	PULL BOX(SIZE I)	6.000	EA
0580	803(A)1220	PULL BOX(SIZE II)	10.000	EA
0590	803(A)1230	PULL BOX(SIZE III)	1.000	EA
0600	803(B)1330	GROUND BOX (GB36)	5.000	EA
0610	804(A)2200	STRUCTURAL CONCRETE	48.700	CY
0620	804(B)2300	REINFORCING STEEL	7,037.200	LB
0630	806(A)4240	32'MH POLE 25'TS & 10'LMA(G.STL.)	1.000	EA
0640	806(A)4248	32'MH POLE 35'TS & 10'LMA(G.STL.)	1.000	EA
0650	806(A)4260	32'MH POLE 50'TS & 10'LMA(G.STL.)	3.000	EA
0660	806(A)4268	32'MH POLE,60'TS & 10'LMA(G.STL.)	1.000	EA
0670	806(A)4320	POLE & 35' TS MST.ARM(G.STL.)	1.000	EA
0680	806(A)4324	POLE & 40' TS MST.ARM(G.STL.)	1.000	EA
0690	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	6.000	EA
0700	809(A)7200	ROADWAY LUMINAIRE	6.000	EA
0710	810(A)8200	SERVICE POLE	2.000	EA
0720	811 9120	1/C NO.6 ELECT.COND.	400.000	LF
0730	811 9130	1/C NO.10 ELECT.COND.	5,850.000	LF
0740	818(A)4200	(SP)FIBER OPTIC CABLE, 12 SMF	450.000	LF
0750	818(A)4215	(SP)FIBER OPTIC CABLE, 96 SMF	3,350.000	LF
0760	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
0770	830 2100	PEDESTRIAN PUSH BUTTON	12.000	EA
0780	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	12.000	EA
0790	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	17.000	EA
0800	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	8.000	EA
0810	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	3.000	EA
0820	831 3156	1WAY5SEC.ADJ.SIG.HD.S-19	2.000	EA
0830	833 5100	BACKPLATE	30.000	EA
0840	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	5,540.000	LF
0850	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	300.000	LF
0860	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,525.000	LF
0870	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	200.000	LF
0880	840(B)0300	E.P.S. OPTICAL DETECTOR	8.000	EA
0890	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	2,050.000	LF
0900	840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	2.000	EA
0910	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	155.250	SF
0920	890 1100	(PL)TRAFFIC ITEMS	1.000	LSUM

Proposal:250165 **Let Date:**June 19, 2025 **Call Order:**435
J/P Num:38090(04) **Proj. Num:**STP-255N(691)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION
CITY STREET (DANFORTH ROAD): AT
THE INTERSECTION OF KELLY AVENUE
IN THE CITY OF EDMOND.
PROJECT LENGTH = 0.915 MILES

	Line #		Item Description	Quantity	Unit
0003	TRAFFIC SIGNING AND STRIPING				
	0930	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	9.000	EA
	0940	850(A)1200	SHEET ALUMINUM SIGNS	266.000	SF
	0950	851(C)2420	2 1/4" SQUARE TUBE POST	620.000	LF
	0960	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	23,476.000	LF
	0970	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	292.000	LF
	0980	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	944.000	LF
	0990	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	51.000	EA
0004	TRAFFIC OPERATIONS				
	1000	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	219.000	LF
	1010	855(A)7221	(SP) TRAFFIC STRIPE(PLASTIC)(TAPE)(4" WIDE)	500.000	LF
	1020	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	7,060.000	LF
	1030	858(A)0204	PAVE.MARKERS CLASS A TYPE 1-A	4,794.000	EA
	1040	858(A)0208	PAVE.MARKERS CLASS A TYPE 1-B	2,616.000	EA
	1050	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	8,734.000	EA
	1060	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,363.000	SD
	1070	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	14,847.000	SD
	1080	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,515.000	SD
	1090	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	18,029.000	SD
	1100	880(E)6600	WARNING LIGHTS(TYPE A)	40,936.000	SD
	1110	880(F)6700	DRUMS	76,636.000	SD
	1120	880(N)7500	(SP) TEMP. TRAFF. SIGNAL SPAN WIRE EQUIP	1.000	LSUM
	1130	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,792.000	SD
0005	CONSTRUCTION				
	1140	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1150	641 2110	MOBILIZATION	1.000	LSUM
0006	STAKING				
	1160	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM