Proposal: 250167 **Let Date:** June 19, 2025 **Call Order:** 445
J/P Num: 35140(04) **Proj. Num:** SBR-266N(137)SB
Counties: ROGERS
Description: BRIDGE REHABILITATION
SH-20: OVER DOG CREEK, 0.98 MILES WEST OF I-44 IN THE CITY OF CLAREMORE.
PROJECT LENGTH = 0.030 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE "A"			
0010	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0020	509(D)0510	CLASS C CONCRETE	1.800	CY
0030	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0040	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0050	513(B)4300	CLASS B BRIDGE DECK REPAIR	130.000	SY
0060	513(C)4400	CLASS C BRIDGE DECK REPAIR	68.000	SY
0070	517 9110	ELASTOMERIC COATING	1,456.000	SF
0080	518(B)0300	SEALED EXPANSION JOINTS	146.140	LF
0090	518(C)0400	RAPID CURE JOINT SEALANT	357.500	LF
0100	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	44.000	LF
0110	520(C)1400	EPOXY RESIN, ABOVE WATER	3.600	GAL
0120	521(A)2200	PNEUMATICALLY PLACED MORTAR	72.500	SY
0130	523(C)3400	DECK AREA SEALED (FLOODCOATS)	1,556.600	SY
0140	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	190.000	SF
0150	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	107.400	SY
0160	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	32.000	EA
0170	540 8136	(PL)REPAIR BRIDGE ITEM (TYPE B)	40.000	EA
0180	540 8152	(PL)REPAIR BRIDGE ITEM (TYPE C)	30.000	EA
0190	545 0101	(PL)REPLACE BRIDGE ITEMS	32.000	EA
0002	TRAFFIC			
0200	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	18,635.000	LF
0210	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	350.000	LF
0220	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	600.000	LF
0230	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	84.000	LF
0240	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	9.000	EA
0250	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	19,669.000	LF
0260	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	9.000	EA
0003	TRAFFIC CONTROL			
0270	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	11,462.000	LF
0280	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	947.000	EA
0290	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	495.000	EA
0300	880(A)6220	ARROW DISPLAY(TYPE C)	495.000	SD
0310	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,188.000	SD
0320	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,980.000	SD
0330	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,168.000	SD
0340	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,673.000	SD
0350	880(E)6607	WARNING LIGHTS(TYPE B)	5,544.000	SD
0360	880(E)6616	WARNING LIGHTS(TYPE D)	27,621.000	SD
0370	880(F)6700	DRUMS	27,621.000	SD
0380	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	427.000	SD
0004	CONSTRUCTION			
0390	641 2100	MOBILIZATION	1.000	LSUM