Proposal:250171 **Let Date:**June 19, 2025 **Call Order:**490
J/P Num:31096(04) **Proj. Num:**NHPPI-4000-(202)FP
Counties:CADDO
Description:RESURFACE (ASPHALT AND UTBWC)
I-40: FROM 0.5 MILES EAST OF THE SH-58 JUNCTION, EXTEND WEST NEAR HYDRO.
PROJECT LENGTH = 3.722 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	1,000.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	2,184.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	48,630.000	LF
0050	221(C)2400	TEMPORARY SEDIMENT FILTER	14.000	EA
0060	221(E)2600	TEMPORARY SILT DIKE	917.000	LF
0070	230(A)7200	SOLID SLAB SODDING	51,629.000	SY
0080	241 3100	MOWING	11.000	AC
0090	404(C)4400	ULTRA-THIN BONDED WEARING COURSE, TYPE C	8,311.000	TON
0100	407(B)7300	TACK COAT	3,277.000	GAL
0110	407(C)7400	(SP) POLYMER MOD. CATIONIC RAPID SET - 1S	73,548.000	GAL
0120	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	4,999.000	TON
0130	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	33,926.000	TON
0140	412 3100	COLD MILLING PAVEMENT	167,344.000	SY
0150	509(A)0200	CLASS AA CONCRETE	8.000	CY
0160	511(A)2200	REINFORCING STEEL	1,496.000	LB
0170	513(B)4300	CLASS B BRIDGE DECK REPAIR	20.000	SY
0180	619(B)6396	REMOVAL OF GUARDRAIL	5,325.000	LF
0190	619(B)6432	REMOVAL OF CABLE BARRIER	20,083.000	LF
0200	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	5,163.000	LF
0210	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	5.000	EA
0220	623(G)1820	GUARDRAIL END TREATMENT (31")	10.000	EA
0230	623(I)2030	GUARDRAIL BRIDGE CONN-TRAIL END (31")	3.000	EA
0240	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	8.000	EA
0250	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	212.000	EA
0002	TRAFFIC			
0260	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	38,722.000	LF
0270	509(A)0200	CLASS AA CONCRETE	167.000	CY
0280	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	20,083.000	LF
0290	628(C)7400	END ANCHORS	10.000	EA
0300	628(E)7600	CABLE BARRIER TENSION METER	1.000	EA
0310	855(A)7205	(SP) TRAFFIC STRIPE(PLASTIC)(6" WIDE)	93,757.000	LF
0320	855(A)7213	(SP) TRAFFIC STRIPE(PLASTIC)(12" WIDE)	4,940.000	LF
0330	858(A)0248	PAVE.MARKERS CLASS C TYPE 1	65.000	EA

Proposal:250171 **Let Date:**June 19, 2025 **Call Order:**490
J/P Num:31096(04) **Proj. Num:**NHPPI-4000-(202)FP
Counties:CADDO
Description:RESURFACE (ASPHALT AND UTBWC)
I-40: FROM 0.5 MILES EAST OF THE SH-58 JUNCTION, EXTEND WEST NEAR HYDRO.
PROJECT LENGTH = 3.722 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0340	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	93,757.000	LF
0350	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	1,748.000	EA
0360	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	220.000	SD
0370	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,500.000	LF
0380	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,600.000	LF
0390	880(A)6220	ARROW DISPLAY(TYPE C)	220.000	SD
0400	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,060.000	SD
0410	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,640.000	SD
0420	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,600.000	SD
0430	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,500.000	SD
0440	880(E)6600	WARNING LIGHTS(TYPE A)	5,500.000	SD
0450	880(F)6700	DRUMS	7,700.000	SD
0460	880(G)6805	CHANNELIZER CONES	25,784.000	SD
0470	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	496.000	SD
0004	STAKING			
0480	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0490	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0500	641 2110	MOBILIZATION	1.000	LSUM