Proposal: 250175 **Let Date:** June 12, 2025 **Call Order:** 316
J/P Num: 29410(04) **Proj. Num:** STP-221C(064)CI
Counties: DELAWARE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (378): OVER DROWNING CREEK,
0.4 MILES SOUTHWEST OF THE SH-127 JUNCTION NEAR ZENA.
PROJECT LENGTH = 0.274 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	14,499.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	1,099.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	4,346.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	780.000	LF
0070	221(G)2800	TEMPORARY FIBER LOG	3,176.000	LF
0080	230(A)7200	SOLID SLAB SODDING	12,913.000	SY
0090	303(B)1300	AGGREGATE BASE TYPE B	705.000	CY
0100	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	174.000	SY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	302.000	TON
0120	407(B)7300	TACK COAT	308.000	GAL
0130	408 8100	PRIME COAT	1,050.000	GAL
0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	687.000	TON
0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	458.200	TON
0160	509(D)0500	CLASS C CONCRETE	11.200	CY
0170	511(A)2200	REINFORCING STEEL	541.300	LB
0180	601(A)1100	TYPE I PLAIN RIPRAP	12.000	TON
0190	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	1,725.000	TON
0200	613(B)5500	12" CORR. GALV. STEEL PIPE	30.000	LF
0210	613(B)5508	18" CORR. GALV. STEEL PIPE	24.000	LF
0220	613(P)7400	18" GALV. STEEL CULVERT END SEC. RND.	2.000	EA
0230	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0240	619(B)6352	REMOVAL OF FENCE	2,819.000	LF
0250	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	3,101.000	SY
0260	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	100.000	LF
0270	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0280	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	1.000	EA
0290	623(G)1800	GUARDRAIL END TREATMENT (GET)	3.000	EA
0300	629(E)7600	MAILBOX	1.000	EA
0002	BRIDGE "A"			
0310	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	1,313.000	CY
0320	501(F)1700	GRANULAR BACKFILL	463.000	CY
0330	509(A)0210	CLASS AA CONCRETE	212.440	CY
0340	511(A)2210	REINFORCING STEEL	34,588.000	LB
0350	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	1,020.000	TON
0360	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250175 **Let Date:**June 12, 2025 **Call Order:**316
J/P Num:29410(04) **Proj. Num:**STP-221C(064)CI
Counties:DELAWARE
Description:BRIDGE AND APPROACHES
COUNTY ROAD (378): OVER DROWNING CREEK,
0.4 MILES SOUTHWEST OF THE SH-127 JUNCTION NEAR ZENA.
PROJECT LENGTH = 0.274 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE "B"			
0370	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	430.000	CY
0380	501(C)1400	SUBSTRUCTURE EXCAVATION ROCK	46.000	CY
0390	501(F)1700	GRANULAR BACKFILL	20.200	CY
0400	501(G)1800	CLSM BACKFILL	225.600	CY
0410	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	508.000	LF
0420	504(B)5300	SAW-CUT GROOVING	422.800	SY
0430	504(D)5410	CONCRETE RAIL (TR3)	427.400	LF
0440	506(A)7200	STRUCTURAL STEEL	640.000	LB
0450	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	6.000	EA
0460	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	6.000	EA
0470	509(A)0210	CLASS AA CONCRETE	133.600	CY
0480	509(B)0320	CLASS A CONCRETE	237.500	CY
0490	511(A)2210	REINFORCING STEEL	52,890.000	LB
0500	511(B)2310	EPOXY COATED REINFORCING STEEL	3,528.000	LB
0510	514(A)5210	PILES, FURNISHED (HP 10X42)	56.000	LF
0520	514(A)5220	PILES, FURNISHED (HP 12X53)	161.000	LF
0530	514(B)5310	PILES, DRIVEN (HP 10X42)	56.000	LF
0540	514(B)5320	PILES, DRIVEN (HP 12X53)	161.000	LF
0550	514(K)6200	(PL)PILOT HOLES	208.000	LF
0560	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0570	516(A)8230	DRILLED SHAFTS 48" DIAMETER	56.000	LF
0580	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
0590	517 9110	ELASTOMERIC COATING	521.000	SF
0600	518(B)0300	SEALED EXPANSION JOINTS	33.060	LF
0610	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	3,747.000	TON
0620	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	100.000	LF
0630	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	70.000	LF
0640	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0004	TRAFFIC CONTROL			
0650	850(A)1200	SHEET ALUMINUM SIGNS	35.500	SF
0660	851(C)2420	2 1/4" SQUARE TUBE POST	66.000	LF
0670	853 5110	DELINEATORS(TYPE 1, CODE 3)	4.000	EA
0680	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	16.000	EA
0690	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	5,880.000	LF
0700	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	7,980.000	SD
0710	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,620.000	SD
0720	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,200.000	SD
0730	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,100.000	SD
0740	880(E)6600	WARNING LIGHTS(TYPE A)	4,200.000	SD
0005	STAKING			
0750	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 250175 **Let Date:** June 12, 2025 **Call Order:** 316
J/P Num: 29410(04) **Proj. Num:** STP-221C(064)CI
Counties: DELAWARE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (378): OVER DROWNING CREEK,
0.4 MILES SOUTHWEST OF THE SH-127 JUNCTION NEAR ZENA.
PROJECT LENGTH = 0.274 MILES

Line #		Item Description	Quantity	Unit
0006	CONSTRUCTION			
0760	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0770	641 2110	MOBILIZATION	1.000	LSUM