Proposal: 250177 **Let Date:** July 10, 2025 **Call Order:** 510
J/P Num: 31277(04) **Proj. Num:** STP-245C(093)CI
Counties: MCCURTAIN
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-213.5 / GOODWATER ROAD):
OVER RED BRANCH CREEK, 9.38 MILES SOUTH OF US-70 NEAR EAGLETOWN.
PROJECT LENGTH = 0.109 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	2,300.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,805.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	65.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	130.000	LF
0070	230(A)7200	SOLID SLAB SODDING	6,059.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	1.900	AC
0090	242 4101	STABILIZED CONSTRUCTION EXIT	1.000	EA
0100	303(A)1200	AGGREGATE BASE TYPE A	399.000	CY
0110	325 0100	SEPARATOR FABRIC	2,016.000	SY
0120	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	814.000	TON
0130	407(B)7300	TACK COAT	106.000	GAL
0140	408 8100	PRIME COAT	473.000	GAL
0150	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	403.000	TON
0160	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	198.000	TON
0170	509(D)0500	CLASS C CONCRETE	10.000	CY
0180	601(B)1220	TYPE I-A PLAIN RIPRAP	249.000	TON
0190	601(C)1300	TYPE I-A FILTER BLANKET	126.000	TON
0200	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	100.000	LF
0210	613(EE)5997	60" CORRUGATED POLYPROPYLENE PIPE	168.000	LF
0220	613(M)6960	TYPE A4 CULVERT END TREATMENT	4.000	EA
0230	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	197.000	CY
0240	613(V)8000	TRENCH EXCAVATION	51.000	CY
0250	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0260	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,107.000	SY

Proposal:250177 **Let Date:**July 10, 2025 **Call Order:**510
J/P Num:31277(04) **Proj. Num:**STP-245C(093)CI
Counties:MCCURTAIN
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-213.5 / GOODWATER ROAD):
OVER RED BRANCH CREEK, 9.38 MILES SOUTH OF US-70 NEAR EAGLETOWN.
PROJECT LENGTH = 0.109 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO. 33254			
0270	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0280	501(G)1800	CLSM BACKFILL	70.000	CY
0290	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	358.670	LF
0300	504(A)5200	APPROACH SLAB	141.600	SY
0310	504(B)5300	SAW-CUT GROOVING	395.600	SY
0320	504(D)5410	CONCRETE RAIL (TR3)	236.600	LF
0330	506(A)7200	STRUCTURAL STEEL	260.000	LB
0340	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
0350	509(A)0210	CLASS AA CONCRETE	109.500	CY
0360	509(B)0320	CLASS A CONCRETE	44.600	CY
0370	511(A)2210	REINFORCING STEEL	24,940.000	LB
0380	514(A)5210	PILES, FURNISHED (HP 10X42)	266.000	LF
0390	514(B)5310	PILES, DRIVEN (HP 10X42)	266.000	LF
0400	514(K)6200	(PL)PILOT HOLES	98.000	LF
0410	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0420	601(B)1230	TYPE I-A PLAIN RIPRAP	1,292.000	TON
0430	601(C)1310	TYPE I-A FILTER BLANKET	140.000	TON
0440	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	64.000	LF
0450	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000	LF
0460	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC			
0470	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	25.000	LF
0480	623(F)1716	GUARDRAIL ANCHOR UNIT (TYPE B)	2.000	EA
0490	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0500	623(G)1800	GUARDRAIL END TREATMENT (GET)	2.000	EA
0510	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
0520	850(A)1200	SHEET ALUMINUM SIGNS	4.500	SF
0530	851(C)2420	2 1/4" SQUARE TUBE POST	24.000	LF
0540	853 5115	DELINEATORS(TYPE 2, CODE 1)	8.000	EA
0550	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	2,320.000	LF
0560	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	300.000	LF
0570	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	720.000	SD
0580	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	720.000	SD
0590	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,440.000	SD
0600	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,080.000	SD
0610	880(E)6600	WARNING LIGHTS(TYPE A)	1,440.000	SD
0620	880(I)7000	FLAGGER	60.000	SD
0004	STAKING			
0630	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0640	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0650	641 2100	MOBILIZATION	1.000	LSUM