Proposal:250178 **Let Date:**July 10, 2025 **Call Order:**515
J/P Num:31247(04) **Proj. Num:**STP-246C(069)PM
Counties:MCINTOSH
Description:PAVEMENT REHABILITATION
US-69B: FROM 0.20 MILES NORTH OF THE SH-9/US-69B INTERSECTION,
EXTEND NORTH IN THE CITY OF EUFAULA.
PROJECT LENGTH = 0.90 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	460.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	130.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	780.000	LF
0060	230(A)7200	SOLID SLAB SODDING	680.000	SY
0070	307(K)4200	STABILIZED SUBGRADE	1,580.000	SY
0080	407(B)7300	TACK COAT	3,450.000	GAL
0090	408 8100	PRIME COAT	600.000	GAL
0100	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	130.000	TON
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,035.000	TON
0120	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	2,450.000	TON
0130	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,360.000	TON
0140	412 3100	COLD MILLING PAVEMENT	25,100.000	SY
0150	416 8100	DOWEL BAR RETROFIT	1,700.000	EA
0160	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	1,390.000	LF
0170	610(A)5200	4" CONCRETE SIDEWALK	200.000	SY
0180	610(B)5320	8" CONCRETE DRIVEWAY	300.000	SY
0190	610(D)5500	REMOVE & RELAY BRICK/STONE SIDEWALK	200.000	SY
0200	610(I)6000	TACTILE WARNING DEVICE-NEW	210.000	SF
0210	619(B)6356	REMOVAL OF CURB AND GUTTER	1,500.000	LF
0220	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,400.000	SY
0230	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	2,510.000	SY
0240	619(B)6400	REMOVAL OF CURB	400.000	LF
0250	619(B)6404	REMOVAL OF SIDEWALK	25.000	SY
0260	619(C)6600	SAWING PAVEMENT	1,500.000	LF
0002	TRAFFIC CONTROL			
0270	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	240.000	EA
0280	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,080.000	SD
0290	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	720.000	SD
0300	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,340.000	SD
0310	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	360.000	SD
0320	880(C)6420	WING BARRICADES	720.000	SD
0330	880(E)6607	WARNING LIGHTS(TYPE B)	4,680.000	SD
0340	880(E)6616	WARNING LIGHTS(TYPE D)	2,700.000	SD
0350	880(F)6700	DRUMS	2,700.000	SD
0360	880(I)7000	FLAGGER	90.000	SD

Proposal:250178 **Let Date:**July 10, 2025 **Call Order:**515
J/P Num:31247(04) **Proj. Num:**STP-246C(069)PM
Counties:MCINTOSH
Description:PAVEMENT REHABILITATION
US-69B: FROM 0.20 MILES NORTH OF THE SH-9/US-69B INTERSECTION,
EXTEND NORTH IN THE CITY OF EUFAULA.
PROJECT LENGTH = 0.90 MILES

Line #		Item Description	Quantity	Unit
0003	SIGNING AND STRIPING			
0370	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
0380	850(A)1200	SHEET ALUMINUM SIGNS	90.000	SF
0390	851(C)2405	1 1/2" SQUARE TUBE POST	35.000	LF
0400	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	2,250.000	LF
0410	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	16,500.000	LF
0420	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	700.000	LF
0430	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	14.000	EA
0440	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	3.000	EA
0004	TRAFFIC SIGNAL			
0450	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	330.000	LF
0460	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	210.000	LF
0470	803(A)1220	PULL BOX(SIZE II)	5.000	EA
0480	804(A)2200	STRUCTURAL CONCRETE	5.900	CY
0490	804(B)2300	REINFORCING STEEL	564.200	LB
0500	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0510	806(B)4416	12' MTG.HT.TS PED.POLE(ALUMINUM)	13.000	EA
0520	809(A)7200	ROADWAY LUMINAIRE	6.000	EA
0530	819(C)5400	(SP)WIRELESS DATA-VIDEO TRANSMISSION SYS	2.000	EA
0540	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
0550	825(B)8310	(SP) INTERSECTION INTEGRATION SYSTEM - NON-BIDDABLE	2.000	EA
0560	825(B)8320	(SP) INTERSECTION INTEGRATION SYSTEM SERVICE - NON-E	2.000	EA
0570	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0580	830 2100	PEDESTRIAN PUSH BUTTON	16.000	EA
0590	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	16.000	EA
0600	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	14.000	EA
0610	831 3148	1WAY4SEC.ADJ.SIG.HD.S-16	2.000	EA
0620	833 5100	BACKPLATE	16.000	EA
0625	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	2,200.000	LF
0630	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	2,310.000	LF
0640	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	100.000	LF
0650	834(A)6215	9/C TRAFFIC SIGNAL ELECTRICAL CABLE	390.000	LF
0660	850(C)1410	INSTALL MAST ARM MOUNTED ALUM SIGNS	81.000	SF
0005	STAKING			
0670	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0680	641 2110	MOBILIZATION	1.000	LSUM