Proposal:250180 **Let Date:**July 10, 2025 **Call Order:**530
J/P Num:20314(04) **Proj. Num:**STP-159B(032)PM
Counties:PAWNEE
Description:GRADE, DRAIN, AND SURFACE
US-64: FROM THE SH-18 INTERSECTION,
EXTEND SOUTH IN THE CITY OF PAWNEE.
PROJECT LENGTH = 1.988 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	16,838.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	1,000.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	7,741.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	7.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	602.000	LF
0080	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	20.000	CY
0090	230(A)7200	SOLID SLAB SODDING	43,309.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	9.000	AC
0110	241 3100	MOWING	38.000	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	3,305.000	CY
0130	307(K)4200	STABILIZED SUBGRADE	19,906.000	SY
0140	325 0100	SEPARATOR FABRIC	21,204.000	SY
0150	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	4,111.000	TON
0160	407(B)7300	TACK COAT	16,698.000	GAL
0170	409(A)9200	FABRIC REINFORCEMENT	9,481.000	SY
0180	409(B)9300	BITUMINOUS BINDER	2,134.000	GAL
0190	411(B)1300	SUPERPAVE, TYPE S3(PG 76-28 OK)	4,197.000	TON
0200	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	4,791.000	TON
0210	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,385.000	TON
0220	411(F)1700	STONE MATRIX ASPHALT	2,881.000	TON
0230	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	500.000	TON
0240	411(J)2100	(SP) RICH INTERMEDIATE LAYER	2,258.000	TON
0250	412 3100	COLD MILLING PAVEMENT	27,281.000	SY
0260	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	179.000	SY
0270	414(G)5800	P.C. CONCRETE FOR PAVEMENT	30.000	CY
0280	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	83.000	CY
0290	501(G)1810	CLSM BACKFILL	19.000	CY
0300	509(A)0200	CLASS AA CONCRETE	268.000	CY
0310	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	11.000	CY
0320	509(D)0500	CLASS C CONCRETE	439.000	CY
0330	510(A)1200	RETAINING WALL	190.000	SY
0340	510(C)1420	SLOPE WALL (4")	112.000	SY
0350	511(A)2200	REINFORCING STEEL	31,094.000	LB
0360	601(F)1610	TYPE IV GROUTED RIPRAP	119.000	SY
0370	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	1,401.000	LF
0380	610(A)5200	4" CONCRETE SIDEWALK	1,398.000	SY
0390	610(A)5240	4" DECORATIVE CONCRETE SIDEWALK	54.000	SY
0400	610(B)5310	6" CONCRETE DRIVEWAY	307.000	SY
0410	610(B)5320	8" CONCRETE DRIVEWAY	864.000	SY
0420	610(I)6000	TACTILE WARNING DEVICE-NEW	95.000	SF
0430	611(G)9000	INLET CDI RCP DES. 1	2.000	EA
0440	611(G)9004	INLET CDI RCP DES. 2	3.000	EA
0450	611(H)0680	ADD'L DEPTH IN INLET CDI RCP DES. 1	1.000	VF
0460	611(H)0684	ADD'L DEPTH IN INLET CDI RCP DES. 2	1.000	VF

Proposal:250180 **Let Date:**July 10, 2025 **Call Order:**530
J/P Num:20314(04) **Proj. Num:**STP-159B(032)PM
Counties:PAWNEE
Description:GRADE, DRAIN, AND SURFACE
US-64: FROM THE SH-18 INTERSECTION,
EXTEND SOUTH IN THE CITY OF PAWNEE.
PROJECT LENGTH = 1.988 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	611(K)1220	RPLC DROP INLET GRATE (SMD-TYPE 1)	3.000	EA
0480	611(L)1600	JUNCTION BOXES	45.000	CF
0490	612(A)3200	MANHOLES ADJUST TO GRADE	4.000	EA
0500	612(C)3400	INLET ADJUST TO GRADE	4.000	EA
0510	613(A)5208	18" R.C.PIPE CLASS III	122.000	LF
0520	613(A)5216	24" R.C.PIPE CLASS III	392.000	LF
0530	613(A)5220	30" R.C.PIPE CLASS III	43.000	LF
0540	613(A)5232	48" R.C.PIPE CLASS III	52.000	LF
0550	613(B)5508	18" CORR. GALV. STEEL PIPE	248.000	LF
0560	613(B)5516	24" CORR. GALV. STEEL PIPE	220.000	LF
0570	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	308.000	LF
0580	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	3,742.000	LF
0590	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	161.000	LF
0600	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	5.000	EA
0610	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0620	613(L)6736	48" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0630	613(M)6964	TYPE B4 CULVERT END TREATMENT	1.000	EA
0640	613(M)7004	TYPE A6 CULVERT END TREATMENT	12.000	EA
0650	613(M)7008	TYPE B6 CULVERT END TREATMENT	6.000	EA
0660	613(Q)7500	OUTLET LATERAL HEADWALL	5.000	EA
0670	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	203.000	CY
0680	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	41.000	CY
0690	613(V)8000	TRENCH EXCAVATION	1,072.000	CY
0700	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0710	619(B)6356	REMOVAL OF CURB AND GUTTER	424.000	LF
0720	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	502.000	SY
0730	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	5,909.000	SY
0740	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	282.000	SY
0750	619(B)6404	REMOVAL OF SIDEWALK	327.000	SY
0760	619(C)6600	SAWING PAVEMENT	21,780.000	LF
0770	622(A)0220	2" PIPE RAILING	1,130.000	LF
0780	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	325.000	LF
0790	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0800	624(A)3200	FENCE-STYLE WWF	784.000	LF
0810	624(B)3360	GATES-STYLE WWF (4.5'HIGH X 16'LONG)	1.000	EA
0820	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	474.000	LF
0830	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,596.000	LF
0840	624(E)3625	FENCE-STYLE CLF (6'HIGH, CLASS B)	52.000	LF
0850	629(A)7200	MAILBOX INSTALLATION-SINGLE	4.000	EA
0860	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	2.000	EA
0870	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	6.000	EA
0880	629(E)7600	MAILBOX	8.000	EA

Proposal:250180 **Let Date:**July 10, 2025 **Call Order:**530
J/P Num:20314(04) **Proj. Num:**STP-159B(032)PM
Counties:PAWNEE
Description:GRADE, DRAIN, AND SURFACE
US-64: FROM THE SH-18 INTERSECTION,
EXTEND SOUTH IN THE CITY OF PAWNEE.
PROJECT LENGTH = 1.988 MILES

Line #		Item Description	Quantity	Unit
0002	SIGNING AND STRIPING			
0890	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	16,761.000	LF
0900	804(A)2200	STRUCTURAL CONCRETE	2.000	CY
0910	804(B)2300	REINFORCING STEEL	258.000	LB
0920	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	12.000	EA
0930	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	7.000	EA
0940	850(A)1200	SHEET ALUMINUM SIGNS	411.000	SF
0950	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	39.000	SF
0960	851(A)2200	4"@13 GALV.STL.WD.FLANGE BM.POST	43.000	LF
0970	851(B)2315	3"@7.58 GALV.STL.PIPE POST	52.000	LF
0980	851(C)2430	2 1/2" SQUARE TUBE POST	655.000	LF
0990	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	9.000	EA
1000	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	43,000.000	LF
1010	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	340.000	LF
1020	890 1110	(PL)TRAFFIC ITEMS	4.000	EA
0003	CABLE BARRIER			
1030	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	1,685.000	LF
1040	628(C)7400	END ANCHORS	4.000	EA
1050	628(E)7600	CABLE BARRIER TENSION METER	1.000	EA
0004	TRAFFIC CONTROL			
1060	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	50.000	SD
1070	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	2,000.000	LF
1080	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	2,000.000	LF
1090	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	4,500.000	EA
1100	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	500.000	LF
1110	871(B)2300	CONST.ZONE IMPACT ATTEN.	100.000	SD
1120	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	240.000	SD
1130	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	450.000	LF
1140	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	450.000	LF
1150	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,840.000	SD
1160	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,160.000	SD
1170	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,840.000	SD
1180	880(C)6405	CONSTRUCTION BARRICADES(TYPE II)	960.000	SD
1190	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,840.000	SD
1200	880(D)6500	VERTICAL PANELS	8,400.000	SD
1210	880(E)6607	WARNING LIGHTS(TYPE B)	15,360.000	SD
1220	880(E)6616	WARNING LIGHTS(TYPE D)	3,360.000	SD
1230	880(F)6700	DRUMS	3,360.000	SD
1240	880(G)6805	CHANNELIZER CONES	56,880.000	SD
1250	880(I)7000	FLAGGER	240.000	SD
1260	880(W)7700	PILOT CAR	1.000	LSUM
1270	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	508.000	SD
1280	890 1100	(PL)TRAFFIC ITEMS	1.000	LSUM

Proposal:250180 **Let Date:**July 10, 2025 **Call Order:**530
J/P Num:20314(04) **Proj. Num:**STP-159B(032)PM
Counties:PAWNEE
Description:GRADE, DRAIN, AND SURFACE
US-64: FROM THE SH-18 INTERSECTION,
EXTEND SOUTH IN THE CITY OF PAWNEE.
PROJECT LENGTH = 1.988 MILES

Line #		Item Description	Quantity	Unit
0005	STAKING			
1290	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
1300	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1310	640(A)1210	FIELD OFFICE	1.000	EA
1320	641 2110	MOBILIZATION	1.000	LSUM