Proposal: 250181 **Let Date:** July 10, 2025 **Call Order:** 540
J/P Num: 31039(04) **Proj. Num:** STP-269C(113)PM
Counties: STEPHENS
Description: BRIDGE AND APPROACHES
SH-53: OVER UNNAMED CREEKS,
1.2, 1.1, AND 0.8 MILES WEST OF SH-89 NEAR LOCO.
PROJECT LENGTH = 0.715 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	23,955.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	10,608.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	3,307.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	546.000	LF
0070	229 6100	DITCH LINER PROTECTION	448.000	LF
0080	230(A)7200	SOLID SLAB SODDING	38,389.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	11.370	AC
0100	241 3100	MOWING	32.000	AC
0110	303(A)1210	AGGREGATE BASE TYPE A, PLANT MIXED	3,082.000	CY
0120	307(K)4200	STABILIZED SUBGRADE	21,711.000	SY
0130	325 0100	SEPARATOR FABRIC	16,486.000	SY
0140	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	2,824.000	TON
0150	407(B)7300	TACK COAT	2,752.000	GAL
0160	408 8100	PRIME COAT	11,230.000	GAL
0170	409(A)9200	FABRIC REINFORCEMENT	1,981.000	SY
0180	409(B)9300	BITUMINOUS BINDER	396.000	GAL
0190	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	5,942.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,772.000	TON
0210	412 3100	COLD MILLING PAVEMENT	7,046.000	SY
0220	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	648.000	CY
0230	509(A)0200	CLASS AA CONCRETE	213.000	CY
0240	509(D)0500	CLASS C CONCRETE	82.000	CY
0250	511(A)2200	REINFORCING STEEL	28,100.000	LB
0260	601(A)1100	TYPE I PLAIN RIPRAP	936.000	TON
0270	613(B)5516	24" CORR. GALV. STEEL PIPE	87.000	LF
0280	613(B)5528	36" CORR. GALV. STEEL PIPE	92.000	LF
0290	613(B)5544	60" CORR. GALV. STEEL PIPE	202.000	LF
0300	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	452.000	LF
0310	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	140.000	LF
0320	613(B)5644	83" X 57" CORR. GALV. STEEL PIPE ARCH	177.000	LF
0330	613(M)6960	TYPE A4 CULVERT END TREATMENT	1.000	EA
0340	613(M)6964	TYPE B4 CULVERT END TREATMENT	3.000	EA
0350	613(M)6980	TYPE AA4 CULVERT END TREATMENT	4.000	EA
0360	613(M)7004	TYPE A6 CULVERT END TREATMENT	1.000	EA
0370	613(M)7008	TYPE B6 CULVERT END TREATMENT	3.000	EA
0380	613(M)7024	TYPE AA6 CULVERT END TREATMENT	4.000	EA
0390	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0400	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	11,978.000	SY
0410	619(B)6396	REMOVAL OF GUARDRAIL	2,134.000	LF
0420	619(C)6600	SAWING PAVEMENT	4,456.000	LF
0440	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	7,210.000	LF
0450	629(A)7200	MAILBOX INSTALLATION-SINGLE	1.000	EA
0460	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	1.000	EA
0470	629(E)7600	MAILBOX	1.000	EA

Proposal:250181 **Let Date:**July 10, 2025 **Call Order:**540
J/P Num:31039(04) **Proj. Num:**STP-269C(113)PM
Counties:STEPHENS
Description:BRIDGE AND APPROACHES
SH-53: OVER UNNAMED CREEKS,
1.2, 1.1, AND 0.8 MILES WEST OF SH-89 NEAR LOCO.
PROJECT LENGTH = 0.715 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO. 32000			
0480	202(A)2210	UNCLASSIFIED EXCAVATION	1,250.000	CY
0490	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	520.000	CY
0500	509(A)0210	CLASS AA CONCRETE	923.000	CY
0510	511(A)2210	REINFORCING STEEL	201,100.000	LB
0520	601(B)1230	TYPE I-A PLAIN RIPRAP	1,040.000	TON
0530	601(C)1310	TYPE I-A FILTER BLANKET	240.000	TON
0540	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	BRIDGE 'B' - NBI NO. 02019			
0550	202(A)2210	UNCLASSIFIED EXCAVATION	470.000	CY
0560	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	85.000	CY
0570	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0580	509(A)0210	CLASS AA CONCRETE	221.000	CY
0590	511(A)2210	REINFORCING STEEL	32,770.000	LB
0600	601(B)1230	TYPE I-A PLAIN RIPRAP	220.000	TON
0610	601(C)1310	TYPE I-A FILTER BLANKET	55.000	TON
0620	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0004	BRIDGE 'C' - NBI NO. 31999			
0630	202(A)2210	UNCLASSIFIED EXCAVATION	1,250.000	CY
0640	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	207.000	CY
0650	509(A)0210	CLASS AA CONCRETE	417.000	CY
0660	511(A)2210	REINFORCING STEEL	85,330.000	LB
0670	601(B)1230	TYPE I-A PLAIN RIPRAP	660.000	TON
0680	601(C)1310	TYPE I-A FILTER BLANKET	145.000	TON
0690	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250181 **Let Date:**July 10, 2025 **Call Order:**540
J/P Num:31039(04) **Proj. Num:**STP-269C(113)PM
Counties:STEPHENS
Description:BRIDGE AND APPROACHES
SH-53: OVER UNNAMED CREEKS,
1.2, 1.1, AND 0.8 MILES WEST OF SH-89 NEAR LOCO.
PROJECT LENGTH = 0.715 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC CONTROL			
0700	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	31,545.000	LF
0710	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	376.000	EA
0720	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	9,455.000	LF
0730	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	1,510.000	EA
0740	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	1,496.000	EA
0750	871(B)2300	CONST.ZONE IMPACT ATTEN.	200.000	SD
0760	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	380.000	SD
0770	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	300.000	LF
0780	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	300.000	LF
0790	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,180.000	SD
0800	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	13,410.000	SD
0810	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,320.000	SD
0820	880(B)6340	VARIABLE SPEED LIMIT SIGN	380.000	SD
0830	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	9,710.000	SD
0840	880(D)6500	VERTICAL PANELS	12,720.000	SD
0850	880(E)6607	WARNING LIGHTS(TYPE B)	32,240.000	SD
0860	880(E)6616	WARNING LIGHTS(TYPE D)	53,200.000	SD
0870	880(F)6700	DRUMS	24,280.000	SD
0880	880(G)6805	CHANNELIZER CONES	22,420.000	SD
0890	880(I)7000	FLAGGER	380.000	SD
0900	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	812.000	SD
0006	TRAFFIC SIGNING AND STRIPING			
0910	413(F)4700	SINUSOIDAL RUMBLE STRIP	10,805.000	LF
0920	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
0930	850(A)1200	SHEET ALUMINUM SIGNS	17.790	SF
0940	851(C)2430	2 1/2" SQUARE TUBE POST	14.000	LF
0950	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	15,875.000	LF
0007	STAKING			
0960	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION			
0970	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0980	640(A)1200	FIELD OFFICE	1.000	EA
0990	641 2100	MOBILIZATION	1.000	LSUM