Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	407,304.000	CY
0030	202(C)2400	ROCK EXCAVATION	49,006.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	1,405.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	13,711.000	LF
0070	221(C)2400	TEMPORARY SEDIMENT FILTER	108.000	EA
0080	221(C)2410	REINFORCED SILT FENCE	462.000	LF
0090	221(E)2600	TEMPORARY SILT DIKE	2,555.000	LF
0100	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	26.000	CY
0110	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	130.000	CY
0120	221(G)2800	TEMPORARY FIBER LOG	19,672.000	LF
0130	229 6100	DITCH LINER PROTECTION	3,195.000	LF
0140	230(A)7200	SOLID SLAB SODDING	266,603.000	SY
0150	232(B)9300	SEEDING METHOD B	110.210	AC
0160	233(A)0200	VEGETATIVE MULCHING	55.140	AC
0170	241 3100	MOWING	220.420	AC
0180	242 4101	STABILIZED CONSTRUCTION EXIT	6.000	EA
0190	307(K)4200	STABILIZED SUBGRADE	171,083.000	SY
0200	317 7100	CEMENT TREATED BASE	102,633.000	SY
0210	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,410.000	TON
0220	407(B)7300	TACK COAT	2,697.000	GAL
0230	408 8100	PRIME COAT	57,011.000	GAL
0235	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	67.000	TON
0240	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,841.000	TON
0250	412 3100	COLD MILLING PAVEMENT	5,853.000	SY
0260	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	37,285.000	SY
0270	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	100,100.000	SY
0280	414(G)5800	P.C. CONCRETE FOR PAVEMENT	36,728.000	CY
0290	504(E)5520	42" F-SHAPED PARAPET	7,358.000	LF
0300	509(A)0200	CLASS AA CONCRETE	156.000	CY
0310	509(B)0300	CLASS A CONCRETE	2,523.200	CY
0320	509(D)0500	CLASS C CONCRETE	370.000	CY
0330	510(A)1200	RETAINING WALL	398.600	SY
0340	510(D)1500	GRAFFITI TREATMENT	13,220.000	SF
0350	511(A)2200	REINFORCING STEEL	22,675.000	LB
0360	511(B)2300	EPOXY COATED REINFORCING STEEL	395,380.000	LB
0370	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	4,094.000	SY
0380	601(B)1220	TYPE I-A PLAIN RIPRAP	447.000	TON
0390	601(C)1300	TYPE I-A FILTER BLANKET	128.000	TON
0400	601(I)1700	FILTER FABRIC (RIPRAP)	458.000	SY
0410	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	14,497.000	LF
0420	609(A)4250	CONC.CURB(6" MNTBLE-INTEGRAL)	3,538.000	LF
0430	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	324.000	LF
0440	609(B)4315	COMBINED CURB & GUTTER(8" BARRIER)	43.000	LF
0450	610(B)5310	6" CONCRETE DRIVEWAY	1,053.000	SY
0460	610(B)5320	8" CONCRETE DRIVEWAY	3,366.000	SY

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	610(C)5400	4" CONCRETE DIVIDING STRIP	950.000	SY
0480	611(A)7210	MANHOLE (4' DIA.)	7.000	EA
0490	611(A)7215	MANHOLE (5' DIA.)	5.000	EA
0500	611(A)7220	MANHOLE (6' DIA.)	1.000	EA
0510	611(A)7257	PRECAST CONC RND 5' DIA MANHOLE	1.000	EA
0520	611(A)7262	PRECAST CONC RND 6' DIA MANHOLE	2.000	EA
0530	611(A)7277	PRECAST CONC SQ 6' WIDE MANHOLE	1.000	EA
0540	611(B)7247	ADD'L DEPTH PRECAST RND 5' MANHOLE	6.510	VF
0550	611(B)7252	ADD'L DEPTH PRECAST RND 6' MANHOLE	22.580	VF
0560	611(B)7282	ADD'L DEPTH PRECAST SQ 6' MANHOLE	4.470	VF
0570	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	13.790	VF
0580	611(B)7305	ADD'L.DEPTH IN MANHOLE (5' DIA.)	10.760	VF
0590	611(B)7310	ADD'L.DEPTH IN MANHOLE (6' DIA.)	2.580	VF
0600	611(G)0264	INLET W/SMALL JCT. BOX, CI, DES.2	20.000	EA
0610	611(G)0268	INLET W/SMALL JCT. BOX, CI, DES.2(B)	5.000	EA
0620	611(G)0276	INLET W/SMALL JCT. BOX, CI, DES.2(D)	1.000	EA
0630	611(G)0304	INLET W/SMALL JCT. BOX, CI, DES.3	1.000	EA
0640	611(G)0312	INLET W/SMALL JCT. BOX, CI, DES.3(D)	1.000	EA
0650	611(G)0354	INLET (SMD-TYPE 2)	15.000	EA
0660	611(G)0358	INLET (SMD-TYPE 2A)	1.000	EA
0670	611(G)7754	INLET CI DES. 2 (STD)	30.000	EA
0680	611(G)7758	INLET CI DES. 2 (B)	7.000	EA
0690	611(G)7766	INLET CI DES. 2 (D)	3.000	EA
0700	611(G)7786	INLET CI DES. 3 (STD)	1.000	EA
0710	611(G)7794	INLET CI DES. 3 (D)	2.000	EA
0720	611(G)7934	INLET GPI TYPE 1 (DES. 2)	1.000	EA
0730	611(G)7958	INLET GPI TYPE 2 (DES. 8)	1.000	EA
0740	611(G)7962	INLET GPI TYPE 2 (DES. 9)	1.000	EA
0750	611(G)7986	INLET GPI TYPE 2 (DES. 14)	1.000	EA
0760	611(G)8150	INLET - LONG. BARRIER - TYPE I, DES. 1	1.000	EA
0770	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	73.920	VF
0780	611(H)0416	ADD'L DEPTH IN INLET CI DES. 2B	10.140	VF
0790	611(H)0418	ADD'L DEPTH IN INLET CI DES. 2(D)	9.570	VF
0800	611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	1.230	VF
0810	611(H)0426	ADD'L DEPTH IN INLET CI DES. 3D	4.000	VF
0820	611(H)0470	ADD'L DEPTH IN INLET GPI TYPE 1	3.820	VF
0830	611(H)0474	ADD'L DEPTH IN INLET GPI TYPE 2	4.020	VF
0840	611(H)0920	ADD'L DEPTH IN INLET W/SJB, CI, DES. 2	88.310	VF
0850	611(H)0924	ADD'L DEPTH IN INLET W/SJB, CI, DES. 2(B)	14.130	VF
0860	611(H)0928	ADD'L DEPTH IN INLET W/SJB, CI, DES. 2(D)	3.020	VF
0870	611(H)0944	ADD'L DEPTH IN INLET W/SJB, CI, DES. 3	6.020	VF
0880	611(H)0952	ADD'L DEPTH IN INLET W/SJB, CI, DES. 3(D)	1.760	VF
0890	613(A)5208	18" R.C.PIPE CLASS III	6,134.000	LF
0900	613(A)5216	24" R.C.PIPE CLASS III	1,767.000	LF
0910	613(A)5220	30" R.C.PIPE CLASS III	955.000	LF
0920	613(A)5224	36" R.C.PIPE CLASS III	985.000	LF
0930	613(A)5228	42" R.C.PIPE CLASS III	278.000	LF

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0940	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	43.000	LF
0950	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	1,615.000	LF
0960	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	539.000	LF
0970	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	14.000	EA
0980	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	10.000	EA
0990	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	5.000	EA
1000	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	3.000	EA
1010	613(L)6732	42" PREFAB. CULVERT END SEC., ROUND	3.000	EA
1020	613(M)7004	TYPE A6 CULVERT END TREATMENT	1.000	EA
1030	613(Q)7500	OUTLET LATERAL HEADWALL	3.000	EA
1040	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
1050	619(B)6352	REMOVAL OF FENCE	5,755.000	LF
1060	619(B)6356	REMOVAL OF CURB AND GUTTER	6,684.000	LF
1070	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	20,756.000	SY
1080	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	106,555.000	SY
1090	619(B)6396	REMOVAL OF GUARDRAIL	8,386.000	LF
1100	619(B)6460	REMOVAL OF 4" CONCRETE DIVIDING STRIP	554.000	SY
1110	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	3,396.000	LF
0002	BRIDGE "A"			
1120	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	634.670	LF
1130	504(A)5200	APPROACH SLAB	480.200	SY
1140	504(B)5300	SAW-CUT GROOVING	988.600	SY
1150	504(E)5520	42" F-SHAPED PARAPET	342.700	LF
1160	505(D)6500	ASPHALT MEMBRANE OVERLAY	1,389.000	SY
1170	506(A)7200	STRUCTURAL STEEL	680.000	LB
1180	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	7.000	EA
1190	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	7.000	EA
1200	509(A)0210	CLASS AA CONCRETE	139.200	CY
1210	509(B)0320	CLASS A CONCRETE	153.500	CY
1220	509(D)0510	CLASS C CONCRETE	34.000	CY
1230	510(C)1450	SLOPE WALL (5")	98.000	SY
1240	510(D)1510	MSE RETAINING WALL	872.000	SY
1250	511(B)2310	EPOXY COATED REINFORCING STEEL	52,200.000	LB
1260	514(A)5210	PILES, FURNISHED (HP 10X42)	176.000	LF
1270	514(A)5220	PILES, FURNISHED (HP 12X53)	756.000	LF
1280	514(B)5310	PILES, DRIVEN (HP 10X42)	176.000	LF
1290	514(B)5320	PILES, DRIVEN (HP 12X53)	756.000	LF
1300	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1310	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	243.000	SY
1320	517 9110	ELASTOMERIC COATING	784.000	SF
1330	518(B)0300	SEALED EXPANSION JOINTS	56.280	LF
1340	542 9110	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	LSUM
1350	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE "B"			
1360	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
1370	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	634.670	LF
1380	504(A)5200	APPROACH SLAB	480.200	SY
1390	504(B)5300	SAW-CUT GROOVING	988.600	SY
1400	504(E)5520	42" F-SHAPED PARAPET	342.700	LF
1410	506(A)7200	STRUCTURAL STEEL	680.000	LB
1420	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	7.000	EA
1430	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	7.000	EA
1440	509(A)0210	CLASS AA CONCRETE	139.200	CY
1450	509(B)0320	CLASS A CONCRETE	150.800	CY
1460	509(D)0510	CLASS C CONCRETE	35.300	CY
1470	510(C)1450	SLOPE WALL (5")	97.000	SY
1480	510(D)1510	MSE RETAINING WALL	840.000	SY
1490	511(B)2310	EPOXY COATED REINFORCING STEEL	52,000.000	LB
1500	514(A)5210	PILES, FURNISHED (HP 10X42)	190.000	LF
1510	514(A)5220	PILES, FURNISHED (HP 12X53)	819.000	LF
1520	514(B)5310	PILES, DRIVEN (HP 10X42)	190.000	LF
1530	514(B)5320	PILES, DRIVEN (HP 12X53)	819.000	LF
1540	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1550	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	245.000	SY
1560	517 9110	ELASTOMERIC COATING	733.000	SF
1570	518(B)0300	SEALED EXPANSION JOINTS	56.280	LF
1580	542 9110	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	LSUM
1590	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0004	BRIDGE "C"			
1600	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	255.000	CY
1610	501(G)1800	CLSM BACKFILL	245.600	CY
1620	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,110.000	LF
1630	504(A)5200	APPROACH SLAB	305.800	SY
1640	504(B)5300	SAW-CUT GROOVING	1,282.400	SY
1650	504(E)5500	CONCRETE PARAPET	126.600	LF
1660	504(E)5520	42" F-SHAPED PARAPET	577.400	LF
1670	506(A)7200	STRUCTURAL STEEL	1,450.000	LB
1680	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	10.000	EA
1690	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
1700	509(A)0210	CLASS AA CONCRETE	267.600	CY
1710	509(B)0320	CLASS A CONCRETE	349.400	CY
1720	509(D)0510	CLASS C CONCRETE	4.900	CY
1730	510(C)1450	SLOPE WALL (5")	963.000	SY
1740	510(D)1500	GRAFFITI TREATMENT	16,581.000	SF
1750	511(A)2210	REINFORCING STEEL	440.000	LB
1760	511(B)2310	EPOXY COATED REINFORCING STEEL	133,980.000	LB
1770	514(A)5210	PILES, FURNISHED (HP 10X42)	188.000	LF
1780	514(A)5220	PILES, FURNISHED (HP 12X53)	401.000	LF
1790	514(B)5310	PILES, DRIVEN (HP 10X42)	188.000	LF
1800	514(B)5320	PILES, DRIVEN (HP 12X53)	401.000	LF
1810	514(K)6200	(PL)PILOT HOLES	247.000	LF
1820	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1830	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	284.000	SY
1840	516(A)8240	DRILLED SHAFTS 60" DIAMETER	48.000	LF
1850	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
1860	517 9110	ELASTOMERIC COATING	1,192.000	SF
1870	518(B)0300	SEALED EXPANSION JOINTS	41.000	LF
1880	523(A)3200	SEALER CRACK PREPARATION	40.000	LF
1890	523(B)3300	SEALER RESIN	0.400	GAL
1900	535 7160	ORNAMENTAL MEDALLION	2.000	EA
1910	610(C)5400	4" CONCRETE DIVIDING STRIP	16.000	SY
1920	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	330.000	LF
1930	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	126.000	LF
1940	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	23.000	CY

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0005	BRIDGE "D"			
1950	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	255.000	CY
1960	501(G)1800	CLSM BACKFILL	245.600	CY
1970	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
1980	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,110.000	LF
1990	504(A)5200	APPROACH SLAB	305.800	SY
2000	504(B)5300	SAW-CUT GROOVING	1,282.400	SY
2010	504(E)5520	42" F-SHAPED PARAPET	577.400	LF
2020	506(A)7200	STRUCTURAL STEEL	1,450.000	LB
2030	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	10.000	EA
2040	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
2050	509(A)0210	CLASS AA CONCRETE	267.600	CY
2060	509(B)0320	CLASS A CONCRETE	325.100	CY
2070	509(D)0510	CLASS C CONCRETE	18.900	CY
2080	510(C)1450	SLOPE WALL (5")	963.000	SY
2090	510(D)1500	GRAFFITI TREATMENT	15,462.000	SF
2100	511(A)2210	REINFORCING STEEL	460.000	LB
2110	511(B)2310	EPOXY COATED REINFORCING STEEL	127,950.000	LB
2120	514(A)5210	PILES, FURNISHED (HP 10X42)	172.000	LF
2130	514(A)5220	PILES, FURNISHED (HP 12X53)	388.000	LF
2140	514(B)5310	PILES, DRIVEN (HP 10X42)	172.000	LF
2150	514(B)5320	PILES, DRIVEN (HP 12X53)	388.000	LF
2160	514(K)6200	(PL)PILOT HOLES	456.000	LF
2170	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
2180	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	284.000	SY
2190	516(A)8240	DRILLED SHAFTS 60" DIAMETER	48.000	LF
2200	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
2210	517 9110	ELASTOMERIC COATING	1,192.000	SF
2220	518(B)0300	SEALED EXPANSION JOINTS	41.000	LF
2230	523(A)3200	SEALER CRACK PREPARATION	40.000	LF
2240	523(B)3300	SEALER RESIN	0.400	GAL
2250	535 7160	ORNAMENTAL MEDALLION	2.000	EA
2260	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	330.000	LF
2270	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	126.000	LF

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0006	BRIDGE "E"			
2280	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	310.000	CY
2290	501(G)1800	CLSM BACKFILL	300.800	CY
2300	504(A)5200	APPROACH SLAB	511.400	SY
2310	504(B)5300	SAW-CUT GROOVING	2,736.200	SY
2320	504(E)5520	42" F-SHAPED PARAPET	1,232.200	LF
2330	505(D)6500	ASPHALT MEMBRANE OVERLAY	1,749.000	SY
2340	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	797,460.000	LB
2350	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	20.000	EA
2360	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
2370	509(A)0210	CLASS AA CONCRETE	585.000	CY
2380	509(B)0320	CLASS A CONCRETE	639.900	CY
2390	509(D)0510	CLASS C CONCRETE	28.600	CY
2400	510(C)1450	SLOPE WALL (5")	2,623.000	SY
2410	510(D)1500	GRAFFITI TREATMENT	36,821.000	SF
2420	511(A)2210	REINFORCING STEEL	2,900.000	LB
2430	511(B)2310	EPOXY COATED REINFORCING STEEL	277,330.000	LB
2440	513(B)4300	CLASS B BRIDGE DECK REPAIR	200.000	SY
2450	513(C)4400	CLASS C BRIDGE DECK REPAIR	200.000	SY
2460	514(A)5210	PILES, FURNISHED (HP 10X42)	360.000	LF
2470	514(A)5220	PILES, FURNISHED (HP 12X53)	1,086.000	LF
2480	514(B)5310	PILES, DRIVEN (HP 10X42)	360.000	LF
2490	514(B)5320	PILES, DRIVEN (HP 12X53)	1,086.000	LF
2500	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
2510	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	603.000	SY
2520	516(A)8240	DRILLED SHAFTS 60" DIAMETER	228.000	LF
2530	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
2540	517 9110	ELASTOMERIC COATING	2,136.000	SF
2550	518(B)0300	SEALED EXPANSION JOINTS	114.310	LF
2560	523(A)3200	SEALER CRACK PREPARATION	57.000	LF
2570	523(B)3300	SEALER RESIN	0.500	GAL
2580	535 7160	ORNAMENTAL MEDALLION	3.000	EA
2590	542 9110	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	LSUM
2600	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	581.000	LF
2610	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	124.000	LF
2620	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0007	BRIDGE "F"			
2630	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	310.000	CY
2640	501(G)1800	CLSM BACKFILL	299.500	CY
2650	504(A)5200	APPROACH SLAB	511.400	SY
2660	504(B)5300	SAW-CUT GROOVING	2,736.200	SY
2670	504(E)5520	42" F-SHAPED PARAPET	1,232.200	LF
2680	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	797,460.000	LB
2690	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	20.000	EA
2700	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
2710	509(A)0210	CLASS AA CONCRETE	585.000	CY
2720	509(B)0320	CLASS A CONCRETE	643.700	CY
2730	509(D)0510	CLASS C CONCRETE	29.300	CY
2740	510(C)1450	SLOPE WALL (5")	2,953.000	SY
2750	510(D)1500	GRAFFITI TREATMENT	39,739.000	SF
2760	511(A)2210	REINFORCING STEEL	2,690.000	LB
2770	511(B)2310	EPOXY COATED REINFORCING STEEL	276,750.000	LB
2780	513(B)4300	CLASS B BRIDGE DECK REPAIR	200.000	SY
2790	513(C)4400	CLASS C BRIDGE DECK REPAIR	200.000	SY
2800	514(A)5210	PILES, FURNISHED (HP 10X42)	332.000	LF
2810	514(A)5220	PILES, FURNISHED (HP 12X53)	989.000	LF
2820	514(B)5310	PILES, DRIVEN (HP 10X42)	332.000	LF
2830	514(B)5320	PILES, DRIVEN (HP 12X53)	989.000	LF
2840	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
2850	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	603.000	SY
2860	516(A)8240	DRILLED SHAFTS 60" DIAMETER	231.000	LF
2870	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
2880	517 9110	ELASTOMERIC COATING	2,112.000	SF
2890	518(B)0300	SEALED EXPANSION JOINTS	114.310	LF
2900	523(A)3200	SEALER CRACK PREPARATION	57.000	LF
2910	523(B)3300	SEALER RESIN	0.500	GAL
2920	535 7160	ORNAMENTAL MEDALLION	3.000	EA
2930	542 9110	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	LSUM
2940	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	607.000	LF
2950	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	124.000	LF
2960	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0008	BRIDGE "G"			
2970	412 3100	COLD MILLING PAVEMENT	458.000	SY
2980	425 0100	DIAMOND GRINDING CONCRETE PAVEMENT	458.000	SY
2990	504(E)5500	CONCRETE PARAPET	342.500	LF
3000	509(D)0510	CLASS C CONCRETE	20.300	CY
3010	510(C)1450	SLOPE WALL (5")	673.000	SY
3020	510(D)1500	GRAFFITI TREATMENT	14,780.000	SF
3030	513(B)4300	CLASS B BRIDGE DECK REPAIR	20.000	SY
3040	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	197.000	SY
3050	517 9110	ELASTOMERIC COATING	147.000	SF
3060	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	20.000	LF
3070	520(C)1400	EPOXY RESIN, ABOVE WATER	1.000	GAL
3080	521(A)2200	PNEUMATICALLY PLACED MORTAR	20.000	SY
3090	523(C)3400	DECK AREA SEALED (FLOODCOATS)	458.000	SY
3100	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	221.000	LF
3110	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	20.000	LF
3120	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0009	BRIDGE "H"			
3130	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0010	TRAFFIC SIGNING AND STRIPING			
3140	516(A)8240	DRILLED SHAFTS 60" DIAMETER	324.000	LF
3150	804(A)2200	STRUCTURAL CONCRETE	20.120	CY
3160	804(B)2300	REINFORCING STEEL	3,210.000	LB
3170	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	98.000	EA
3180	805(D)3536	(PL)REMOVE & RESET GROUND MOUNTED SIGN	2.000	EA
3190	850(A)1200	SHEET ALUMINUM SIGNS	808.600	SF
3200	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	1,596.000	SF
3210	850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	1,633.250	SF
3220	851(A)2205	6"@15 GALV.STL.WD.FLANGE BM.POST	310.000	LF
3230	851(A)2210	6"@20 GALV.STL.WD.FLANGE BM.POST	39.000	LF
3240	851(A)2215	6"@25 GALV.STL.WD.FLANGE BM.POST	144.000	LF
3250	851(C)2420	2 1/4" SQUARE TUBE POST	799.300	LF
3260	852(D)3512	OVHD.SN.STR., MONOTUBE TYPE B 70'	3.000	EA
3270	852(D)3528	OVHD.SN.STR., MONOTUBE TYPE B 90'	1.000	EA
3280	852(E)3600	OVHD.SN.STR., MONOTUBE TYPE C	1.000	EA
3290	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	95,240.000	LF
3310	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	10,320.000	LF
3320	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	315.000	LF
3330	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	70.000	EA
3340	856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	2.000	EA
3350	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	175.000	EA
3360	880(C)6425	PERMANENT BARRICADE UNIT	1.000	EA

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0011	TRAFFIC SAFETY			
3370	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	358.000	LF
3380	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	22,506.000	LF
3390	509(A)0200	CLASS AA CONCRETE	60.000	CY
3400	619(B)6432	REMOVAL OF CABLE BARRIER	7,681.000	LF
3410	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	487.500	LF
3420	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	1.000	EA
3430	623(G)1820	GUARDRAIL END TREATMENT (31")	5.000	EA
3440	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
3450	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	6,847.000	LF
3460	628(C)7400	END ANCHORS	14.000	EA
3470	628(F)7700	(PL)HIGH TENSION CABLE BARR. RE-TENSION	2.000	EA
3480	871(A)2200	IMPACT ATTENUATOR	19.000	EA
0012	TRAFFIC LIGHTING AND SIGNALS			
3490	516(A)8225	DRILLED SHAFTS 42" DIAMETER	96.000	LF
3500	610(A)5200	4" CONCRETE SIDEWALK	127.620	SY
3510	802(A)0210	1" GALV.STEEL ELECT.COND. EXPOSED	175.000	LF
3520	802(A)0240	2" GALV.STEEL ELECT.COND. EXPOSED	2,600.000	LF
3530	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	30,500.000	LF
3540	802(B)0325	2" PVC SCH.80 PLASTIC CONDUIT TRENCHED	4,100.000	LF
3550	803(A)1200	PULL BOX	4.000	EA
3560	803(A)1220	PULL BOX(SIZE II)	106.000	EA
3570	804(A)2200	STRUCTURAL CONCRETE	157.440	CY
3580	804(B)2300	REINFORCING STEEL	27,264.000	LB
3590	805(A)3216	REMOVAL OF HIGH MAST TOWER	3.000	EA
3600	805(A)3228	(PL)REMOVAL OF LIGHT POLE	84.000	EA
3610	806(C)4503	40' MTG & 4' HLMA(G.STL.)	4.000	EA
3620	806(C)4508	40' MTG & 8' HLMA(G.STL.)	96.000	EA
3630	807 5100	BREAKAWAY BASE	96.000	EA
3640	809(A)7200	ROADWAY LUMINAIRE	100.000	EA
3650	809(B)7300	UNDERPASS LUMINAIRE	6.000	EA
3660	809(E)7600	HIGH MAST LUMINAIRE	36.000	EA
3670	810(A)8200	SERVICE POLE	4.000	EA
3680	811 9115	1/C NO.4 ELECT.COND.	109,000.000	LF
3690	811 9120	1/C NO.6 ELECT.COND.	35,000.000	LF
3700	811 9125	1/C NO.8 ELECT.COND.	10,300.000	LF
3710	812 0105	80' HIGH MAST POLE(G.STL.)	6.000	EA

Proposal:250182 **Let Date:**July 17, 2025 **Call Order:**600
J/P Num:31842(04) **Proj. Num:**NHPPI-4000-(223)PM
Counties:CUSTER
Description:GRADE, DRAIN, BRIDGE AND SURFACE
I-40: FROM THE I-40B INTERCHANGE, EXTEND EAST IN THE CITY OF CLINTON.
PROJECT LENGTH = 1.351 MILES

Line #		Item Description	Quantity	Unit
0013	TRAFFIC CONTROL			
3720	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	960.000	DAY
3730	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	170,378.000	LF
3740	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	2,000.000	EA
3750	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	147,493.000	LF
3760	871(B)2300	CONST.ZONE IMPACT ATTEN.	3,723.000	SD
3770	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	8,813.000	LF
3780	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	44,300.000	LF
3790	878(B)5300	MODULAR GLARE SCREEN (TEMPORARY)	55,434.000	SD
3800	880(A)6220	ARROW DISPLAY(TYPE C)	3,057.000	SD
3810	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	110,670.000	SD
3820	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	31,850.000	SD
3830	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	75,306.000	SD
3840	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	22,845.000	SD
3850	880(E)6600	WARNING LIGHTS(TYPE A)	40,700.000	SD
3860	880(F)6700	DRUMS	265,620.000	SD
3870	880(G)6805	CHANNELIZER CONES	73,857.000	SD
3880	880(I)7000	FLAGGER	1,620.000	SD
3890	880(K)7200	SURVEILLANCE TRAFFIC CONTROL	1,247.000	SD
3900	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,000.000	HOUR
3910	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	13,454.000	SD
0014	STAKING			
3920	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0015	CONSTRUCTION			
3930	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
3940	641 2110	MOBILIZATION	1.000	LSUM