Proposal: 250183 **Let Date:** July 17, 2025 **Call Order:** 605
J/P Num: 32349(04) **Proj. Num:** STP-239D(060)CI
Counties: LATIMER
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW 1430 RD/ E CENTER POINT RD):
OVER CUNNEO TUBBY CREEK, 1.55 MILES NORTH
OF US-270 NEAR WILBURTON.
PROJECT LENGTH = 0.061 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	196.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	50.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	570.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	35.000	LF
0070	230(A)7200	SOLID SLAB SODDING	480.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	0.380	AC
0090	303(A)1200	AGGREGATE BASE TYPE A	249.000	CY
0100	325 0100	SEPARATOR FABRIC	1,160.000	SY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	44.000	TON
0120	407(B)7300	TACK COAT	65.000	GAL
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	248.000	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	122.000	TON
0150	509(D)0500	CLASS C CONCRETE	10.000	CY
0160	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0170	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	673.000	SY
0180	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	330.000	LF
0190	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	337.000	LF
0002	BRIDGE			
0200	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
0210	501(G)1800	CLSM BACKFILL	110.000	CY
0220	503(A)4200	PRESTRESSED CONCRETE BEAMS	280.000	LF
0230	504(B)5300	SAW-CUT GROOVING	124.220	SY
0240	504(D)5420	CONCRETE RAIL (TR4)	112.000	LF
0250	507(C)8400	ELASTOMERIC BEARING PADS	28.000	EA
0260	509(A)0210	CLASS AA CONCRETE	25.420	CY
0270	509(B)0320	CLASS A CONCRETE	51.680	CY
0280	511(A)2210	REINFORCING STEEL	10,780.000	LB
0290	514(A)5210	PILES, FURNISHED (HP 10X42)	230.000	LF
0300	514(B)5310	PILES, DRIVEN (HP 10X42)	10.000	LF
0310	514(K)6200	(PL)PILOT HOLES	190.000	LF
0320	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	60.700	SY
0330	601(B)1230	TYPE I-A PLAIN RIPRAP	350.000	TON
0340	601(C)1310	TYPE I-A FILTER BLANKET	50.000	TON
0350	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250183 **Let Date:**July 17, 2025 **Call Order:**605
J/P Num:32349(04) **Proj. Num:**STP-239D(060)CI
Counties:LATIMER
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW 1430 RD/ E CENTER POINT RD):
OVER CUNNEO TUBBY CREEK, 1.55 MILES NORTH
OF US-270 NEAR WILBURTON.
PROJECT LENGTH = 0.061 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
0360	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	4.000	EA
0370	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0380	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
0390	850(A)1200	SHEET ALUMINUM SIGNS	12.000	SF
0400	851(C)2430	2 1/2" SQUARE TUBE POST	40.000	LF
0410	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	8.000	EA
0420	855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1,304.000	LF
0430	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	10,800.000	SD
0440	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,920.000	SD
0450	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0460	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0470	880(E)6600	WARNING LIGHTS(TYPE A)	2,400.000	SD
0480	880(F)6700	DRUMS	2,400.000	SD
0490	880(G)6805	CHANNELIZER CONES	2,400.000	SD
0004	STAKING			
0500	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0510	641 2100	MOBILIZATION	1.000	LSUM