Proposal: 250184 **Let Date:** November 20, 2025 **Call Order:** 635
J/P Num: 31236(04) **Proj. Num:** CIRB-240C(092)RB
Counties: LEFLORE
Description: RESURFACE (ASPHALT)
COUNTY ROAD (WALKER MOUNTAIN ROAD):
FROM 4.7 MILES EAST OF US-270,
EXTEND SOUTH NEAR HEAVENER.
PROJECT LENGTH = 3.204 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	3,487.000	CY
0020	221(B)2300	TEMPORARY SILT FENCE	7,555.000	LF
0030	303(A)1200	AGGREGATE BASE TYPE A	2,487.000	CY
0040	307(C)3400	PORTLAND CEMENT	738.000	TON
0050	307(E)3600	CEMENTITIOUS STABILIZED SUBGRADE	52,580.000	SY
0060	311(D)6500	PROCESS EXISTING BASE & SURFACE,METHOD D	16,920.000	LF
0070	326(B)1300	GEOGRID REINFORCEMENT	7,460.000	SY
0080	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	3,786.000	TON
0090	407(C)7500	NT TACK MATERIAL	3,149.000	GAL
0100	408 8100	PRIME COAT	11,280.000	GAL
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	7,132.000	TON
0120	411(D)1530	SUPERPAVE, TYPE S5(PG 64-22 OK)	4,754.000	TON
0130	619(C)6600	SAWING PAVEMENT	44.000	LF
0140	629(D)7500	REMOVE AND RESET MAILBOX	10.000	EA
0002	TRAFFIC			
0150	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	60.000	SD
0160	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	67,680.000	LF
0170	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	680.000	SD
0180	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,400.000	SD
0190	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,400.000	SD
0200	880(E)6600	WARNING LIGHTS(TYPE A)	1,400.000	SD
0210	880(G)6805	CHANNELIZER CONES	4,000.000	SD
0220	880(I)7000	FLAGGER	60.000	SD
0230	880(W)7700	PILOT CAR	1.000	LSUM
0003	STAKING			
0240	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0250	641 2110	MOBILIZATION	1.000	LSUM