Proposal:250186 **Let Date:**July 17, 2025 **Call Order:**625
J/P Num:31075(04) **Proj. Num:**STP-257B(094)PM
Counties:OSAGE
Description:BRIDGE AND APPROACHES
SH-18: OVER SALT CREEK,
5.2 MILES NORTH OF THE SH-20 INTERSECTION NEAR FAIRFAX.
PROJECT LENGTH = 0.441 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	16,346.590	CY
0030	202(D)2500	UNCLASSIFIED BORROW	12,732.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	5,303.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	6.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	168.000	LF
0080	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	9.080	CY
0090	230(A)7200	SOLID SLAB SODDING	22,648.330	SY
0100	233(A)0200	VEGETATIVE MULCHING	5.070	AC
0110	241 3100	MOWING	17.520	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	2,339.680	CY
0130	307(K)4200	STABILIZED SUBGRADE	20,725.000	SY
0140	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	11,357.030	SY
0150	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,102.480	TON
0160	407(B)7300	TACK COAT	1,743.800	GAL
0170	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	6,741.930	TON
0180	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,219.060	TON
0190	412 3100	COLD MILLING PAVEMENT	205.510	SY
0200	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	23.710	CY
0210	509(A)0200	CLASS AA CONCRETE	87.590	CY
0220	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	1.040	CY
0230	509(D)0500	CLASS C CONCRETE	21.500	CY
0240	511(A)2200	REINFORCING STEEL	11,103.730	LB
0250	609(B)4370	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	146.000	LF
0260	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	1,509.000	LF
0270	610(A)5200	4" CONCRETE SIDEWALK	937.690	SY
0280	611(G)0350	INLET (SMD-TYPE 1)	1.000	EA
0290	611(G)7754	INLET CI DES. 2 (STD)	1.000	EA
0300	611(G)7790	INLET CI DES. 3 (B)	2.000	EA
0310	611(G)7794	INLET CI DES. 3 (D)	1.000	EA
0320	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	1.250	VF
0330	611(H)0424	ADD'L DEPTH IN INLET CI DES. 3B	3.600	VF
0340	611(H)0426	ADD'L DEPTH IN INLET CI DES. 3D	1.510	VF
0350	611(L)1600	JUNCTION BOXES	71.140	CF
0360	613(A)5208	18" R.C.PIPE CLASS III	48.000	LF
0370	613(A)5216	24" R.C.PIPE CLASS III	292.000	LF
0380	613(A)5220	30" R.C.PIPE CLASS III	52.000	LF
0390	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	1,698.000	LF
0400	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	100.000	LF
0410	613(M)6964	TYPE B4 CULVERT END TREATMENT	2.000	EA
0420	613(M)6968	TYPE C4 CULVERT END TREATMENT	2.000	EA
0430	613(M)7004	TYPE A6 CULVERT END TREATMENT	2.000	EA
0440	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0450	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	16,106.500	SY
0460	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	182.920	SY

Proposal:250186 **Let Date:**July 17, 2025 **Call Order:**625
J/P Num:31075(04) **Proj. Num:**STP-257B(094)PM
Counties:OSAGE
Description:BRIDGE AND APPROACHES
SH-18: OVER SALT CREEK,
5.2 MILES NORTH OF THE SH-20 INTERSECTION NEAR FAIRFAX.
PROJECT LENGTH = 0.441 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	263.720	SY
0480	619(B)6396	REMOVAL OF GUARDRAIL	343.000	LF
0490	619(C)6600	SAWING PAVEMENT	2,978.000	LF
0500	623 1100	(PL)GUARDRAIL CURBING	1.000	EA
0510	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	25.000	LF
0520	623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
0530	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	1.000	EA
0540	624(A)3200	FENCE-STYLE WWF	397.000	LF
0550	624(B)3350	GATES-STYLE WWF (4.5'HIGH X 14'LONG)	1.000	EA
0560	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	2.000	EA
0002	BRIDGE 'A' - NBI NO. 32317			
0570	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	250.000	CY
0580	501(G)1800	CLSM BACKFILL	298.800	CY
0590	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0600	502(A)3200	ENGINEERED FALSEWORK	1.000	LSUM
0610	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	1,493.000	LF
0620	504(A)5200	APPROACH SLAB	321.800	SY
0630	504(B)5300	SAW-CUT GROOVING	2,618.400	SY
0640	504(D)5420	CONCRETE RAIL (TR4)	1,533.900	LF
0650	504(F)5600	HANDRAILING	1,022.600	LF
0660	506(A)7200	STRUCTURAL STEEL	300,990.000	LB
0670	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	20.000	EA
0680	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	30.000	EA
0690	509(A)0210	CLASS AA CONCRETE	576.300	CY
0700	509(B)0320	CLASS A CONCRETE	270.800	CY
0710	511 2100	MECHANICAL SPLICES	20.000	EA
0720	511(A)2210	REINFORCING STEEL	2,080.000	LB
0730	511(B)2310	EPOXY COATED REINFORCING STEEL	232,180.000	LB
0740	514(A)5220	PILES, FURNISHED (HP 12X53)	829.000	LF
0750	514(B)5320	PILES, DRIVEN (HP 12X53)	829.000	LF
0760	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0770	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,701.000	SY
0780	516(A)8230	DRILLED SHAFTS 48" DIAMETER	354.000	LF
0790	516(C)8400	CROSSHOLE SONIC LOGGING	3.000	EA
0800	517 9110	ELASTOMERIC COATING	1,889.600	SF
0810	518(B)0300	SEALED EXPANSION JOINTS	96.600	LF
0820	523(A)3200	SEALER CRACK PREPARATION	549.000	LF
0830	523(B)3300	SEALER RESIN	6.200	GAL
0840	601(B)1230	TYPE I-A PLAIN RIPRAP	4,340.000	TON
0850	601(C)1310	TYPE I-A FILTER BLANKET	585.000	TON
0860	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	96.000	LF
0870	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
0880	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0890	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250186 **Let Date:**July 17, 2025 **Call Order:**625
J/P Num:31075(04) **Proj. Num:**STP-257B(094)PM
Counties:OSAGE
Description:BRIDGE AND APPROACHES
SH-18: OVER SALT CREEK,
5.2 MILES NORTH OF THE SH-20 INTERSECTION NEAR FAIRFAX.
PROJECT LENGTH = 0.441 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0900	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	9,340.000	LF
0910	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	2,000.000	LF
0920	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	2,000.000	EA
0930	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	9,340.000	LF
0940	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,680.000	SD
0950	871(C)2410	RELOCATION OF IMPACT ATTENUATOR	7.000	EA
0960	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	420.000	SD
0970	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,837.500	LF
0980	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	4,187.500	LF
0990	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,720.000	SD
1000	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	13,020.000	SD
1010	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,720.000	SD
1020	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	11,340.000	SD
1030	880(E)6607	WARNING LIGHTS(TYPE B)	27,720.000	SD
1040	880(E)6616	WARNING LIGHTS(TYPE D)	5,880.000	SD
1050	880(F)6700	DRUMS	5,880.000	SD
1060	880(G)6805	CHANNELIZER CONES	13,020.000	SD
1070	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	868.000	SD
0004	SIGNING AND STRIPING			
1080	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
1090	850(A)1200	SHEET ALUMINUM SIGNS	127.000	SF
1100	851(C)2415	2" SQUARE TUBE POST	289.000	LF
1110	851(C)2430	2 1/2" SQUARE TUBE POST	233.000	LF
1120	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	10,800.000	LF
1130	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	42.000	LF
0005	STAKING			
1140	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
1150	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1160	640(A)1200	FIELD OFFICE	1.000	EA
1170	641 2100	MOBILIZATION	1.000	LSUM