Proposal: 250189 **Let Date:** August 07, 2025 **Call Order:** 700
J/P Num: 38176(04) **Proj. Num:** BRO-210F(119)CB
Counties: CARTER, MURRAY
Description: BRIDGE REPAIR
COUNTY ROADS: OVER SANDY BEAR CREEK, WILD HORSE CREEK, LICK CREEK AND UNNAMED CREEK AT MULTIPLE LOCATIONS IN DISTRICT VII.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE 'A' - NBI 21582			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2210	UNCLASSIFIED EXCAVATION	50.000	CY
0030	501(G)1800	CLSM BACKFILL	4.000	CY
0040	506(A)7200	STRUCTURAL STEEL	50.000	LB
0050	509(B)0320	CLASS A CONCRETE	6.000	CY
0060	511(A)2210	REINFORCING STEEL	650.000	LB
0070	514(H)5900	SHEET PILING, FURNISHED	205.000	SY
0080	514(I)6000	SHEET PILING, DRIVEN	205.000	SY
0090	601(A)1110	TYPE I PLAIN RIPRAP	220.000	TON
0002	BRIDGE 'B' - NBI 21903			
0100	202(A)2210	UNCLASSIFIED EXCAVATION	50.000	CY
0110	506(A)7200	STRUCTURAL STEEL	100.000	LB
0120	509(B)0320	CLASS A CONCRETE	10.000	CY
0130	511(A)2210	REINFORCING STEEL	1,200.000	LB
0140	601(A)1110	TYPE I PLAIN RIPRAP	50.000	TON
0003	BRIDGE 'C' - NBI 23347			
0150	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0160	202(A)2210	UNCLASSIFIED EXCAVATION	50.000	CY
0170	202(D)2510	UNCLASSIFIED BORROW	4,500.000	CY
0180	506(A)7200	STRUCTURAL STEEL	150.000	LB
0190	509(B)0320	CLASS A CONCRETE	10.000	CY
0200	511(A)2210	REINFORCING STEEL	1,200.000	LB
0210	514(H)5900	SHEET PILING, FURNISHED	1,600.000	SY
0220	514(I)6000	SHEET PILING, DRIVEN	1,600.000	SY
0230	601(A)1110	TYPE I PLAIN RIPRAP	2,200.000	TON
0240	601(C)1310	TYPE I-A FILTER BLANKET	360.000	TON
0004	BRIDGE 'D' - NBI 06143			
0250	201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
0260	514(H)5900	SHEET PILING, FURNISHED	100.000	SY
0270	514(I)6000	SHEET PILING, DRIVEN	100.000	SY
0280	601(F)1600	TYPE IV GROUTED RIPRAP	50.000	SY
0290	613(Z)8400	DEWATERING	7.000	DAY
0005	TRAFFIC CONTROL			
0300	880(J)7110	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
0006	CONSTRUCTION			
0310	641 2100	MOBILIZATION	1.000	LSUM