Proposal: 250194 **Let Date:** August 07, 2025 **Call Order:** 725
J/P Num: 38144(04) **Proj. Num:** BRO-226F(134)CB
Counties: CADDO, GRADY
Description: BRIDGE REPAIR
COUNTY ROADS: OVER WINTER CREEK, ROCK HOLLOW CREEK, AND UNNAMED CREEKS IN MULTIPLE LOCATION IN DISTRICT VII.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE 'A' - NBI 11096			
0010	202(A)2210	UNCLASSIFIED EXCAVATION	10.000	CY
0020	202(D)2510	UNCLASSIFIED BORROW	200.000	CY
0030	509(B)0320	CLASS A CONCRETE	10.000	CY
0040	511(A)2210	REINFORCING STEEL	2,500.000	LB
0050	514(H)5900	SHEET PILING, FURNISHED	100.000	SY
0060	514(I)6000	SHEET PILING, DRIVEN	100.000	SY
0070	601(A)1110	TYPE I PLAIN RIPRAP	55.000	TON
0080	613(Z)8400	DEWATERING	14.000	DAY
0002	BRIDGE 'B' - NBI 12269			
0090	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0100	501(G)1800	CLSM BACKFILL	4.000	CY
0110	506(A)7200	STRUCTURAL STEEL	500.000	LB
0120	509(B)0320	CLASS A CONCRETE	15.000	CY
0130	511(A)2210	REINFORCING STEEL	2,700.000	LB
0140	514(A)5210	PILES, FURNISHED (HP 10X42)	120.000	LF
0150	514(B)5310	PILES, DRIVEN (HP 10X42)	120.000	LF
0160	514(H)5900	SHEET PILING, FURNISHED	50.000	SY
0170	514(I)6000	SHEET PILING, DRIVEN	50.000	SY
0180	601(A)1110	TYPE I PLAIN RIPRAP	55.000	TON
0190	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0003	BRIDGE 'C' - NBI 21653			
0200	202(A)2210	UNCLASSIFIED EXCAVATION	20.000	CY
0210	202(D)2510	UNCLASSIFIED BORROW	500.000	CY
0220	506(A)7200	STRUCTURAL STEEL	100.000	LB
0230	509(B)0320	CLASS A CONCRETE	5.000	CY
0240	511(A)2210	REINFORCING STEEL	700.000	LB
0250	514(H)5900	SHEET PILING, FURNISHED	1,000.000	SY
0260	514(I)6000	SHEET PILING, DRIVEN	1,000.000	SY
0270	601(A)1110	TYPE I PLAIN RIPRAP	750.000	TON
0280	601(C)1310	TYPE I-A FILTER BLANKET	160.000	TON
0004	BRIDGE 'D' - NBI 22189			
0290	202(A)2210	UNCLASSIFIED EXCAVATION	20.000	CY
0300	501(G)1800	CLSM BACKFILL	8.000	CY
0310	506(A)7200	STRUCTURAL STEEL	1,600.000	LB
0320	514(H)5900	SHEET PILING, FURNISHED	68.000	SY
0330	514(I)6000	SHEET PILING, DRIVEN	68.000	SY

Proposal: 250194 **Let Date:** August 07, 2025 **Call Order:** 725
J/P Num: 38144(04) **Proj. Num:** BRO-226F(134)CB
Counties: CADDO, GRADY
Description: BRIDGE REPAIR
COUNTY ROADS: OVER WINTER CREEK, ROCK HOLLOW CREEK, AND UNNAMED CREEKS IN MULTIPLE LOCATION IN DISTRICT VII.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0005	BRIDGE 'E' - NBI 09579			
0340	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0350	501(G)1800	CLSM BACKFILL	15.000	CY
0360	514(H)5900	SHEET PILING, FURNISHED	45.000	SY
0370	514(I)6000	SHEET PILING, DRIVEN	45.000	SY
0380	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	50.000	LF
0390	520(C)1400	EPOXY RESIN, ABOVE WATER	2.000	GAL
0400	601(A)1110	TYPE I PLAIN RIPRAP	350.000	TON
0410	613(Z)8400	DEWATERING	4.000	DAY
0006	BRIDGE 'F' - NBI 27099			
0420	506(A)7200	STRUCTURAL STEEL	500.000	LB
0430	509(B)0320	CLASS A CONCRETE	13.000	CY
0440	511(A)2210	REINFORCING STEEL	1,650.000	LB
0450	514(A)5210	PILES, FURNISHED (HP 10X42)	106.000	LF
0460	514(B)5310	PILES, DRIVEN (HP 10X42)	106.000	LF
0470	514(H)5900	SHEET PILING, FURNISHED	18.000	SY
0480	514(I)6000	SHEET PILING, DRIVEN	18.000	SY
0490	613(Z)8400	DEWATERING	8.000	DAY
0500	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0007	TRAFFIC CONTROL			
0510	880(J)7110	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
0008	CONSTRUCTION			
0520	641 2100	MOBILIZATION	1.000	LSUM