Proposal:250196 **Let Date:**August 07, 2025 **Call Order:**735
J/P Num:38356(04) **Proj. Num:**BRO-232F(082)CB
Counties:HUGHES, OKFUSKEE
Description:BRIDGE REPAIR
COUNTY ROADS: OVER LITTLE WEWOKA CREEK, SPRING CREEK, GABBLER CREEK, AND UNNAMED CREEKS AT MULTIPLE LOCATIONS IN DISTRICT III.
PROJECT LENGTH = 0.000 MILES

	Line #		Item Description	Quantity	Unit
0001	BRIDGE 'A' - NBI NO. 20258				
	0010	201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
	0020	202(A)2210	UNCLASSIFIED EXCAVATION	8.000	CY
	0030	202(D)2510	UNCLASSIFIED BORROW	45.000	CY
	0040	501(G)1800	CLSM BACKFILL	2.000	CY
	0050	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
	0060	509(B)0320	CLASS A CONCRETE	28.000	CY
	0070	511(B)2310	EPOXY COATED REINFORCING STEEL	1,400.000	LB
	0080	601(B)1230	TYPE I-A PLAIN RIPRAP	248.000	TON
	0090	601(C)1310	TYPE I-A FILTER BLANKET	50.000	TON
0002	BRIDGE 'B' - NBI NO. 20795				
	0100	202(A)2210	UNCLASSIFIED EXCAVATION	20.000	CY
	0110	202(D)2510	UNCLASSIFIED BORROW	378.000	CY
	0120	501(G)1800	CLSM BACKFILL	7.000	CY
	0130	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
	0140	509(B)0320	CLASS A CONCRETE	42.000	CY
	0150	511(B)2310	EPOXY COATED REINFORCING STEEL	4,200.000	LB
	0160	601(B)1230	TYPE I-A PLAIN RIPRAP	270.000	TON
	0170	601(C)1310	TYPE I-A FILTER BLANKET	39.000	TON
0003	BRIDGE 'C' - NBI NO. 27707				
	0180	201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
	0190	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
	0200	509(B)0320	CLASS A CONCRETE	14.000	CY
	0210	511(B)2310	EPOXY COATED REINFORCING STEEL	1,300.000	LB
0004	BRIDGE 'D' - NBI NO. 04098				
	0220	202(A)2210	UNCLASSIFIED EXCAVATION	10.000	CY
	0230	202(D)2510	UNCLASSIFIED BORROW	23.000	CY
	0240	501(G)1800	CLSM BACKFILL	3.000	CY
	0250	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
	0260	509(B)0320	CLASS A CONCRETE	8.000	CY
	0270	511(B)2310	EPOXY COATED REINFORCING STEEL	1,200.000	LB
	0280	601(B)1230	TYPE I-A PLAIN RIPRAP	126.000	TON
	0290	601(C)1310	TYPE I-A FILTER BLANKET	26.000	TON
0005	BRIDGE 'E' - NBI NO. 05942				
	0300	201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
	0310	501(G)1800	CLSM BACKFILL	2.000	CY
	0320	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
	0330	601(F)1600	TYPE IV GROUTED RIPRAP	69.000	SY

Proposal: 250196 **Let Date:** August 07, 2025 **Call Order:** 735
J/P Num: 38356(04) **Proj. Num:** BRO-232F(082)CB
Counties: HUGHES, OKFUSKEE
Description: BRIDGE REPAIR
COUNTY ROADS: OVER LITTLE WEWOKA CREEK, SPRING CREEK, GABBLER CREEK, AND UNNAMED CREEKS AT MULTIPLE LOCATIONS IN DISTRICT III.
PROJECT LENGTH = 0.000 MILES

	Line #		Item Description	Quantity	Unit
0006	BRIDGE 'F' - NBI NO. 05611				
	0340	201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
	0350	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
	0360	509(B)0320	CLASS A CONCRETE	14.000	CY
	0370	511(B)2310	EPOXY COATED REINFORCING STEEL	1,200.000	LB
0007	TRAFFIC CONTROL				
	0380	880(J)7110	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
0008	CONSTRUCTION				
	0390	641 2100	MOBILIZATION	1.000	LSUM