Proposal:250197 **Let Date:**August 07, 2025 **Call Order:**740
J/P Num:31272(04) **Proj. Num:**STP-248D(061)CI
Counties:MARSHALL
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-203): OVER UNNAMED CREEK,
0.96 MILES EAST OF THE US-70 INTERSECTION NEAR MADILL.
PROJECT LENGTH = 0.160 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	538.600	CY
0030	202(D)2500	UNCLASSIFIED BORROW	1,723.800	CY
0040	221(B)2300	TEMPORARY SILT FENCE	1,545.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	60.000	LF
0060	230(A)7200	SOLID SLAB SODDING	2,181.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	0.500	AC
0080	303(A)1200	AGGREGATE BASE TYPE A	500.000	CY
0090	407(B)7300	TACK COAT	155.700	GAL
0100	408 8100	PRIME COAT	1,492.300	GAL
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	400.000	TON
0120	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	210.000	TON
0130	623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	4.000	EA
0140	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0150	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	1,741.800	LF
0002	BRIDGE 70' TYPE III P.C. BEAM			
0160	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
0170	501(G)1800	CLSM BACKFILL	88.000	CY
0180	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	209.000	LF
0190	504(A)5200	APPROACH SLAB	156.500	SY
0200	504(B)5300	SAW-CUT GROOVING	181.100	SY
0210	504(D)5410	CONCRETE RAIL (TR3)	213.300	LF
0220	506(A)7200	STRUCTURAL STEEL	580.000	LB
0230	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	3.000	EA
0240	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	3.000	EA
0250	509(A)0210	CLASS AA CONCRETE	58.800	CY
0260	509(B)0320	CLASS A CONCRETE	74.200	CY
0270	511(A)2210	REINFORCING STEEL	23,550.000	LB
0280	514(A)5210	PILES, FURNISHED (HP 10X42)	87.000	LF
0290	514(A)5220	PILES, FURNISHED (HP 12X53)	177.300	LF
0300	514(B)5310	PILES, DRIVEN (HP 10X42)	87.000	LF
0310	514(B)5320	PILES, DRIVEN (HP 12X53)	177.300	LF
0320	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0330	518(B)0300	SEALED EXPANSION JOINTS	33.100	LF
0340	601(B)1230	TYPE I-A PLAIN RIPRAP	290.000	TON
0350	601(C)1310	TYPE I-A FILTER BLANKET	60.000	TON
0360	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250197 **Let Date:**August 07, 2025 **Call Order:**740
J/P Num:31272(04) **Proj. Num:**STP-248D(061)CI
Counties:MARSHALL
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-203): OVER UNNAMED CREEK,
0.96 MILES EAST OF THE US-70 INTERSECTION NEAR MADILL.
PROJECT LENGTH = 0.160 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0370	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	4,180.000	LF
0380	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	600.000	SD
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	760.000	SD
0400	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,200.000	SD
0410	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	480.000	SD
0420	880(C)6420	WING BARRICADES	1,200.000	SD
0430	880(E)6600	WARNING LIGHTS(TYPE A)	2,160.000	SD
0004	STAKING			
0440	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0450	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0460	641 2100	MOBILIZATION	1.000	LSUM