Proposal: 250207 **Let Date:** January 22, 2026 **Call Order:** 810

J/P Num: 31800(04) **Proj. Num:** STP-216C(126)CI

31118(04) STP-216C(125)CI

Counties: COMANCHE

Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-165/CACHE ROAD): OVER WEST CACHE CREEK
AND ROCK CREEK, 1.1 MILES SOUTH OF US-62 IN THE CITY OF CACHE.
PROJECT LENGTH = 0.528 MILES

	Line #		Item Description	Quantity	Unit
0001	ROADWAY - STP-216C(126)CI				
	0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
	0020	202(A)2200	UNCLASSIFIED EXCAVATION	858.000	CY
	0030	202(D)2500	UNCLASSIFIED BORROW	1,536.000	CY
	0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
	0050	221(B)2300	TEMPORARY SILT FENCE	2,956.000	LF
	0060	221(E)2600	TEMPORARY SILT DIKE	91.000	LF
	0070	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	53.000	CY
	0080	230(A)7200	SOLID SLAB SODDING	4,476.000	SY
	0090	233(A)0200	VEGETATIVE MULCHING	4.200	AC
	0100	307(K)4200	STABILIZED SUBGRADE	4,719.000	SY
	0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,449.000	TON
	0120	407(B)7300	TACK COAT	259.000	GAL
	0130	408 8100	PRIME COAT	1,644.000	GAL
	0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	785.000	TON
	0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	422.000	TON
	0160	412 3100	COLD MILLING PAVEMENT	2,909.000	SY
	0170	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	34.000	CY
	0180	509(A)0200	CLASS AA CONCRETE	86.200	CY
	0190	509(D)0500	CLASS C CONCRETE	10.000	CY
	0200	511(A)2200	REINFORCING STEEL	12,173.000	LB
	0210	613(B)5516	24" CORR. GALV. STEEL PIPE	58.000	LF
	0220	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
	0230	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
	0240	619(B)6300	REMOVAL OF HEADWALL	2.000	EA
	0250	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
	0260	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
	0270	624(A)3200	FENCE-STYLE WWF	351.000	LF
	0280	629(D)7500	REMOVE AND RESET MAILBOX	1.000	EA

Proposal: 250207 **Let Date:** January 22, 2026 **Call Order:** 810
J/P Num: 31800(04) **Proj. Num:** STP-216C(126)CI
31118(04) STP-216C(125)CI
Counties: COMANCHE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-165/CACHE ROAD): OVER WEST CACHE CREEK
AND ROCK CREEK, 1.1 MILES SOUTH OF US-62 IN THE CITY OF CACHE.
PROJECT LENGTH = 0.528 MILES

	Line #		Item Description	Quantity	Unit
0002	BRIDGE - STP-216C(126)CI				
	0290	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
	0300	501(G)1800	CLSM BACKFILL	92.000	CY
	0310	503(A)4220	PRESTRESSED CONCRETE BEAMS (TYPE II)	636.010	LF
	0320	504(B)5300	SAW-CUT GROOVING	503.300	SY
	0330	504(D)5410	CONCRETE RAIL (TR3)	388.200	LF
	0340	506(A)7200	STRUCTURAL STEEL	1,290.000	LB
	0350	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
	0360	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	16.000	EA
	0370	509(A)0210	CLASS AA CONCRETE	158.200	CY
	0380	509(B)0320	CLASS A CONCRETE	140.600	CY
	0390	511(A)2210	REINFORCING STEEL	63,230.000	LB
	0400	514(A)5210	PILES, FURNISHED (HP 10X42)	152.000	LF
	0410	514(A)5220	PILES, FURNISHED (HP 12X53)	356.000	LF
	0420	514(B)5310	PILES, DRIVEN (HP 10X42)	152.000	LF
	0430	514(B)5320	PILES, DRIVEN (HP 12X53)	356.000	LF
	0440	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	0450	516(A)8230	DRILLED SHAFTS 48" DIAMETER	156.000	LF
	0460	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
	0470	518(B)0300	SEALED EXPANSION JOINTS	39.990	LF
	0480	601(B)1230	TYPE I-A PLAIN RIPRAP	2,710.000	TON
	0490	601(C)1310	TYPE I-A FILTER BLANKET	610.000	TON
	0500	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	72.000	LF
	0510	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
	0520	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC - STP-216C(126)CI				
	0530	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
	0540	850(A)1200	SHEET ALUMINUM SIGNS	5.180	SF
	0550	851(C)2415	2" SQUARE TUBE POST	13.000	LF
	0560	853 5165	BARRIER DELINEATORS(TYPE 2, CODE 1)	8.000	EA
	0570	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	4,800.000	LF
0004	CONSTRUCTION - STP-216C(126)CI				
	0580	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM

Proposal: 250207 **Let Date:** January 22, 2026 **Call Order:** 810
J/P Num: 31800(04) **Proj. Num:** STP-216C(126)CI
31118(04) STP-216C(125)CI
Counties: COMANCHE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-165/CACHE ROAD): OVER WEST CACHE CREEK
AND ROCK CREEK, 1.1 MILES SOUTH OF US-62 IN THE CITY OF CACHE.
PROJECT LENGTH = 0.528 MILES

Line #		Item Description	Quantity	Unit
0005	ROADWAY - STP-216C(125)CI			
0590	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0600	202(A)2200	UNCLASSIFIED EXCAVATION	1,009.000	CY
0610	202(D)2500	UNCLASSIFIED BORROW	2,543.000	CY
0620	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0630	221(B)2300	TEMPORARY SILT FENCE	2,875.000	LF
0640	221(E)2600	TEMPORARY SILT DIKE	203.000	LF
0650	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	50.000	CY
0660	230(A)7200	SOLID SLAB SODDING	8,742.000	SY
0670	233(A)0200	VEGETATIVE MULCHING	4.540	AC
0680	307(K)4200	STABILIZED SUBGRADE	3,720.000	SY
0690	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	876.000	TON
0700	407(B)7300	TACK COAT	251.000	GAL
0710	408 8100	PRIME COAT	1,734.000	GAL
0720	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	764.000	TON
0730	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	485.000	TON
0740	412 3100	COLD MILLING PAVEMENT	3,180.000	SY
0750	509(D)0500	CLASS C CONCRETE	10.000	CY
0760	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0770	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	250.000	LF
0780	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0790	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0800	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	437.000	LF

Proposal: 250207 **Let Date:** January 22, 2026 **Call Order:** 810
J/P Num: 31800(04) **Proj. Num:** STP-216C(126)CI
31118(04) STP-216C(125)CI
Counties: COMANCHE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-165/CACHE ROAD): OVER WEST CACHE CREEK
AND ROCK CREEK, 1.1 MILES SOUTH OF US-62 IN THE CITY OF CACHE.
PROJECT LENGTH = 0.528 MILES

	Line #		Item Description	Quantity	Unit
0006	BRIDGE - STP-216C(125)CI				
	0810	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
	0820	501(G)1800	CLSM BACKFILL	86.000	CY
	0830	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,594.680	LF
	0840	504(A)5200	APPROACH SLAB	141.600	SY
	0850	504(B)5300	SAW-CUT GROOVING	1,341.400	SY
	0860	504(D)5410	CONCRETE RAIL (TR3)	864.600	LF
	0870	506(A)7200	STRUCTURAL STEEL	1,240.000	LB
	0880	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
	0890	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	24.000	EA
	0900	507(C)8400	ELASTOMERIC BEARING PADS	24.000	EA
	0910	509(A)0210	CLASS AA CONCRETE	404.600	CY
	0920	509(B)0320	CLASS A CONCRETE	147.800	CY
	0930	511(A)2210	REINFORCING STEEL	113,340.000	LB
	0940	514(A)5210	PILES, FURNISHED (HP 10X42)	808.000	LF
	0950	514(B)5310	PILES, DRIVEN (HP 10X42)	808.000	LF
	0960	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	0970	516(A)8240	DRILLED SHAFTS 60" DIAMETER	304.000	LF
	0980	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
	0990	601(B)1230	TYPE I-A PLAIN RIPRAP	4,290.000	TON
	1000	601(C)1310	TYPE I-A FILTER BLANKET	980.000	TON
	1010	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	64.000	LF
	1020	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	22.000	LF
	1030	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0007	TRAFFIC - STP-216C(125)CI				
	1040	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	3.000	EA
	1050	850(A)1200	SHEET ALUMINUM SIGNS	16.250	SF
	1060	851(C)2415	2" SQUARE TUBE POST	41.000	LF
	1070	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	4,794.000	LF
	1080	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,760.000	SD
	1090	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,588.000	SD
	1100	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	828.000	SD
	1110	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,208.000	SD
	1120	880(E)6600	WARNING LIGHTS(TYPE A)	5,244.000	SD
	1130	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	568.000	SD
0008	STAKING - STP-216C(125)CI				
	1140	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0009	CONSTRUCTION - STP-216C(125)CI				
	1150	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1160	641 2110	MOBILIZATION	1.000	LSUM