Proposal: 250226 **Let Date:** September 11, 2025 **Call Order:** 112
J/P Num: 38445(04) **Proj. Num:** STP-209C(135)PM
Counties: CANADIAN
Description: INTERSECTION MODIFICATION
SH-66: AT THE GRANT BLVD INTERSECTION,
0.018 MILES EAST OF US-344 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.275 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	1,682.000	CY
0020	202(F)2700	EMBANKMENTS	12.000	CY
0030	205(A)6210	TYPE A-SALVAGED TOPSOIL	239.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	217.000	LF
0050	221(G)2800	TEMPORARY FIBER LOG	24.000	LF
0060	230(A)7200	SOLID SLAB SODDING	751.000	SY
0070	303(A)1200	AGGREGATE BASE TYPE A	1,080.000	CY
0080	325 0100	SEPARATOR FABRIC	3,822.000	SY
0100	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	3,822.000	SY
0110	414(G)5800	P.C. CONCRETE FOR PAVEMENT	851.000	CY
0120	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	2,313.000	LF
0130	610(A)5200	4" CONCRETE SIDEWALK	195.000	SY
0140	610(C)5410	6" CONCRETE DIVIDING STRIP	510.000	SY
0150	610(I)6000	TACTILE WARNING DEVICE-NEW	96.000	SF
0160	611(G)0350	INLET (SMD-TYPE 1)	1.000	EA
0170	619(B)6300	REMOVAL OF HEADWALL	1.000	EA
0180	619(B)6356	REMOVAL OF CURB AND GUTTER	537.000	LF
0190	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	920.000	SY
0200	619(B)6404	REMOVAL OF SIDEWALK	36.000	SY

Proposal:250226 **Let Date:**September 11, 2025 **Call Order:**112
J/P Num:38445(04) **Proj. Num:**STP-209C(135)PM
Counties:CANADIAN
Description:INTERSECTION MODIFICATION
SH-66: AT THE GRANT BLVD INTERSECTION,
0.018 MILES EAST OF US-344 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.275 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0210	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	110.000	LF
0220	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	880.000	LF
0230	803(A)1200	PULL BOX	4.000	EA
0240	804(A)2200	STRUCTURAL CONCRETE	25.000	CY
0250	804(B)2300	REINFORCING STEEL	3,545.000	LB
0260	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	5.000	EA
0270	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	3.000	EA
0280	806(A)4244	32'MH POLE,30'TS & 10'LMA(G.STL.)	2.000	EA
0290	806(A)4264	32'MH POLE,55'TS & 10'LMA(G.STL.)	2.000	EA
0300	806(B)4420	15' MTG.HT.TS PED.POLE(G.STL.)	3.000	EA
0310	809(A)7200	ROADWAY LUMINAIRE	4.000	EA
0320	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
0330	828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0340	830 2100	PEDESTRIAN PUSH BUTTON	8.000	EA
0350	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	8.000	EA
0360	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	10.000	EA
0370	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	4.000	EA
0380	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	4.000	EA
0390	833 5100	BACKPLATE	18.000	EA
0400	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	80.000	LF
0410	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	320.000	LF
0420	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	180.000	LF
0430	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	465.000	LF
0440	850(A)1200	SHEET ALUMINUM SIGNS	30.000	SF
0450	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	20.000	SF
0460	851(C)2420	2 1/4" SQUARE TUBE POST	40.000	LF
0470	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	11,890.000	LF
0480	854(B)6301	(SP) TRAFFIC STRIPE(PAINT)(ARROW)	8.000	EA
0490	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	6,990.000	LF
0500	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	4,150.000	LF
0510	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	750.000	LF
0520	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	8.000	EA
0530	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,700.000	LF
0003	TRAFFIC CONTROL			
0540	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,320.000	SD
0550	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	960.000	SD
0560	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,200.000	SD
0570	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	720.000	SD
0580	880(E)6600	WARNING LIGHTS(TYPE A)	960.000	SD
0590	880(E)6610	WARNING LIGHTS(TYPE C)	960.000	SD
0600	880(F)6700	DRUMS	31,680.000	SD
0004	CONSTRUCTION			
0610	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0620	641 2110	MOBILIZATION	1.000	LSUM