Proposal:250281 **Let Date:**October 09, 2025 **Call Order:**348
J/P Num:35921(04) **Proj. Num:**STP-255N(562)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION
SH-3 (NORTHWEST EXPRESSWAY): AT THE INTERSECTION OF
SH-74 (LAKE HEFNER PARKWAY) IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.383 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	5,561.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	2,248.000	LF
0050	221(C)2400	TEMPORARY SEDIMENT FILTER	5.000	EA
0060	230(A)7200	SOLID SLAB SODDING	3,786.000	SY
0070	303(A)1200	AGGREGATE BASE TYPE A	488.000	CY
0080	310(B)5300	SUBGRADE, METHOD B	1,488.000	SY
0081	325 0100	SEPARATOR FABRIC	1,488.000	SY
0090	407(B)7300	TACK COAT	1,730.000	GAL
0100	409(A)9200	FABRIC REINFORCEMENT	10,355.000	SY
0110	409(B)9300	BITUMINOUS BINDER	3,107.000	GAL
0120	411(B)1340	SUPERPAVE, TYPE S3(PG 58-28 OK)	660.000	TON
0130	411(D)1520	SUPERPAVE, TYPE S5(PG 70-28 OK)	1,235.000	TON
0140	411(E)1620	SUPERPAVE, TYPE S6(PG 64-22 OK)	435.000	TON
0150	412 3100	COLD MILLING PAVEMENT	10,355.000	SY
0160	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	23.000	SY
0170	414(G)5800	P.C. CONCRETE FOR PAVEMENT	346.000	CY
0180	600(B)0300	(PL) AUDIO/VIDEO CONSTRUCTION RECORDING	1.000	LSUM
0190	609(B)4370	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	2,165.000	LF
0200	610(A)5200	4" CONCRETE SIDEWALK	1,472.000	SY
0210	610(B)5320	8" CONCRETE DRIVEWAY	321.000	SY
0220	610(I)6000	TACTILE WARNING DEVICE-NEW	120.000	SF
0230	611(A)7210	MANHOLE (4' DIA.)	1.000	EA
0240	611(G)7754	INLET CI DES. 2 (STD)	2.000	EA
0250	611(G)7758	INLET CI DES. 2 (B)	1.000	EA
0260	611(G)7786	INLET CI DES. 3 (STD)	3.000	EA
0270	611(G)7794	INLET CI DES. 3 (D)	2.000	EA
0280	612(A)3200	MANHOLES ADJUST TO GRADE	2.000	EA
0290	613(A)5208	18" R.C.PIPE CLASS III	204.000	LF
0300	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	8.000	LF
0310	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0320	619(B)6356	REMOVAL OF CURB AND GUTTER	2,024.000	LF
0330	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	967.000	SY
0340	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	123.000	SY
0350	619(B)6368	REMOVAL OF DRAINAGE INLETS	5.000	EA
0360	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	434.000	SY
0361	619(B)6440	REMOVAL OF EXISTING PIPE	49.000	LF
0370	619(C)6600	SAWING PAVEMENT	920.000	LF

Proposal:250281 **Let Date:**October 09, 2025 **Call Order:**348
J/P Num:35921(04) **Proj. Num:**STP-255N(562)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION
SH-3 (NORTHWEST EXPRESSWAY): AT THE INTERSECTION OF
SH-74 (LAKE HEFNER PARKWAY) IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.383 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0371	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	155.000	LF
0372	803(A)1210	PULL BOX(SIZE I)	2.000	EA
0375	804(A)2200	STRUCTURAL CONCRETE	8.800	CY
0376	804(B)2300	REINFORCING STEEL	1,206.000	LB
0380	805(D)3500	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
0390	806(A)4264	32'MH POLE,55'TS & 10'LMA(G.STL.)	1.000	EA
0400	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	4.000	EA
0405	811 9130	1/C NO.10 ELECT.COND.	1,420.000	LF
0410	830 2100	PEDESTRIAN PUSH BUTTON	4.000	EA
0420	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	4.000	EA
0430	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	3.000	EA
0440	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	1.000	EA
0445	833 5100	BACKPLATE	8.000	EA
0450	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	20.000	LF
0460	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,667.000	LF
0470	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	380.000	LF
0003	SIGNING AND STRIPING			
0480	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
0490	850(A)1200	SHEET ALUMINUM SIGNS	44.000	SF
0500	851(C)2410	1 3/4" SQUARE TUBE POST	60.000	LF
0520	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	5,401.000	LF
0530	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	1,063.000	LF
0540	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	204.000	LF
0550	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	19.000	EA
0560	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	5.000	EA
0004	LIGHTING			
0570	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	523.000	LF
0580	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	442.000	LF
0590	803(A)1210	PULL BOX(SIZE I)	14.000	EA
0600	804(A)2200	STRUCTURAL CONCRETE	3.250	CY
0610	805(A)3208	REMOVAL OF PULL BOX	9.000	EA
0620	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	5.000	EA
0630	811 9150	2/C NO.4 ELECTRICAL CONDUCTOR	1,650.000	LF
0005	TRAFFIC CONTROL			
0640	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	3,662.000	LF
0660	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	650.000	LF
0670	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	650.000	LF
0680	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	150.000	SD
0690	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,550.000	SD
0700	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,250.000	SD
0710	880(E)6600	WARNING LIGHTS(TYPE A)	3,000.000	SD
0720	880(F)6700	DRUMS	12,300.000	SD
0730	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	141.000	SD

Proposal:250281 **Let Date:**October 09, 2025 **Call Order:**348
J/P Num:35921(04) **Proj. Num:**STP-255N(562)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION
SH-3 (NORTHWEST EXPRESSWAY): AT THE INTERSECTION OF
SH-74 (LAKE HEFNER PARKWAY) IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.383 MILES

Line #		Item Description	Quantity	Unit
0006	STAKING			
0740	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
0750	641 2110	MOBILIZATION	1.000	LSUM