Proposal: 250286 **Let Date:** January 22, 2026 **Call Order:** 850
J/P Num: 36595(04) **Proj. Num:** STP-272B(446)IG
Counties: TULSA
Description: GRADE, DRAIN, AND SURFACE
CITY STREET (E PINE ST): FROM THE INTERSECTION OF SH-11, EXTEND EAST IN THE CITY OF TULSA.
PROJECT LENGTH = 4.59 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	591.000	CY
0030	221(E)2600	TEMPORARY SILT DIKE	280.000	LF
0040	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	5.000	EA
0050	230(A)7200	SOLID SLAB SODDING	214.000	SY
0060	231(E)8600	(PL) LANDSCAPING	1.000	LSUM
0070	303(A)1200	AGGREGATE BASE TYPE A	421.000	CY
0080	310(B)5300	SUBGRADE, METHOD B	1,068.000	SY
0090	325 0100	SEPARATOR FABRIC	1,990.000	SY
0100	409(A)9200	FABRIC REINFORCEMENT	24,774.000	SY
0110	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	2,780.000	TON
0120	411(E)1600	SUPERPAVE, TYPE S6(PG 76-28 OK)	2,899.000	TON
0130	412 3100	COLD MILLING PAVEMENT	24,784.000	SY
0140	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	1,068.000	SY
0150	610(B)5320	8" CONCRETE DRIVEWAY	185.000	SY
0160	610(G)5800	ASPHALT DRIVEWAY	84.000	TON
0170	612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0180	612(E)3600	VALVE BOXES ADJUST TO GRADE	9.000	EA
0190	613(L)6700	12" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0200	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	8.000	EA
0210	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0220	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0230	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0240	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	185.000	SY
0250	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	187.000	SY
0002	TEMPORARY TRAFFIC			
0270	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	23,347.000	LF
0280	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,260.000	SD
0290	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,950.000	SD
0300	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,870.000	SD
0310	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	7,620.000	SD
0320	880(E)6607	WARNING LIGHTS(TYPE B)	7,170.000	SD
0330	880(F)6700	DRUMS	26,910.000	SD
0340	880(G)6805	CHANNELIZER CONES	2,550.000	SD

Proposal:250286 **Let Date:**January 22, 2026 **Call Order:**850
J/P Num:36595(04) **Proj. Num:**STP-272B(446)IG
Counties:TULSA
Description:GRADE, DRAIN, AND SURFACE
CITY STREET (E PINE ST): FROM THE INTERSECTION OF SH-11, EXTEND EAST IN THE CITY OF TULSA.
PROJECT LENGTH = 4.59 MILES

Line #		Item Description	Quantity	Unit
0003	PERMANENT TRAFFIC			
0350	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	17.000	EA
0360	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	6.000	EA
0370	850(A)1200	SHEET ALUMINUM SIGNS	111.000	SF
0380	850(D)1510	SPECIAL SIGNS	2.000	EA
0390	851(C)2405	1 1/2" SQUARE TUBE POST	6.000	LF
0400	851(C)2410	1 3/4" SQUARE TUBE POST	176.000	LF
0410	851(C)2415	2" SQUARE TUBE POST	54.000	LF
0420	855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	21,970.000	LF
0430	855(A)7209	(SP) TRAFFIC STRIPE(PLASTIC)(8" WIDE)	568.000	LF
0440	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	272.000	LF
0450	855(B)7305	(SP) TRAFFIC STRIPE(PLASTIC)(ARROWS)	24.000	EA
0460	855(B)7313	(SP) TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	1.000	EA
0004	TRAFFIC SIGNALS			
0470	802(A)0230	1 1/2" GALV. STEEL ELECT COND EXPOSED	18.000	LF
0480	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	26.000	LF
0490	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	988.000	LF
0500	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	183.000	LF
0510	803(A)1220	PULL BOX(SIZE II)	5.000	EA
0520	803(A)1230	PULL BOX(SIZE III)	1.000	EA
0530	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0540	811 9120	1/C NO.6 ELECT.COND.	488.000	LF
0550	811 9135	1/C NO.12 ELECT.COND.	729.000	LF
0560	811 9160	2/C NO.12 ELECT.COND.	380.000	LF
0570	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
0580	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0590	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	4.000	EA
0600	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	4.000	EA
0610	831 3156	1WAY5SEC.ADJ.SIG.HD.S-19	4.000	EA
0620	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	64.000	LF
0630	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,226.000	LF
0640	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	677.000	LF
0650	850(A)1200	SHEET ALUMINUM SIGNS	66.000	SF
0005	STAKING			
0660	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0670	641 2110	MOBILIZATION	1.000	LSUM