Proposal:250288 **Let Date:**November 13, 2025 **Call Order:**595
J/P Num:33317(04) **Proj. Num:**STP-272B(445)IG
Counties:TULSA
Description:INTERSECTION MODIFICATION
COUNTY ROAD (E 106TH ST N): AT THE INTERSECTION
OF N 129TH E AVE, 0.48 MILES WEST OF US-169 IN THE CITY OF OWASSO.
PROJECT LENGTH = 0.382 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	15,668.000	CY
0030	205(A)6210	TYPE A-SALVAGED TOPSOIL	1,444.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	1,165.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	189.000	LF
0060	221(G)2800	TEMPORARY FIBER LOG	360.000	LF
0070	230(A)7200	SOLID SLAB SODDING	10,395.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	3.000	AC
0090	241 3100	MOWING	6.000	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	8,278.000	CY
0110	310(B)5300	SUBGRADE, METHOD B	21,793.000	SY
0120	325 0100	SEPARATOR FABRIC	23,232.000	SY
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,953.000	TON
0140	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	506.000	TON
0150	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	15.000	TON
0160	412 3100	COLD MILLING PAVEMENT	2,406.000	SY
0170	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	16,855.000	SY
0180	414(G)5800	P.C. CONCRETE FOR PAVEMENT	3,980.000	CY
0190	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	110.000	CY
0200	501(E)1600	SELECT BACKFILL	254.000	CY
0210	501(G)1810	CLSM BACKFILL	135.000	CY
0220	509(A)0200	CLASS AA CONCRETE	695.000	CY
0230	509(D)0500	CLASS C CONCRETE	15.000	CY
0240	511(A)2200	REINFORCING STEEL	78,440.000	LB
0250	511(B)2300	EPOXY COATED REINFORCING STEEL	14,230.000	LB
0260	601(A)1100	TYPE I PLAIN RIPRAP	98.000	TON
0270	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	3,652.000	LF
0280	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	106.000	LF
0290	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	177.000	LF
0300	610(A)5200	4" CONCRETE SIDEWALK	2,557.000	SY
0310	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	412.000	SY
0320	610(G)5800	ASPHALT DRIVEWAY	103.000	TON
0330	610(I)6000	TACTILE WARNING DEVICE-NEW	80.000	SF
0340	611(A)7210	MANHOLE (4' DIA.)	2.000	EA
0350	611(A)7215	MANHOLE (5' DIA.)	1.000	EA
0360	611(A)7277	PRECAST CONC SQ 6' WIDE MANHOLE	6.000	EA
0370	611(G)0264	INLET W/SMALL JCT. BOX, CI, DES.2	10.000	EA
0380	611(G)7754	INLET CI DES. 2 (STD)	4.000	EA
0390	611(G)7786	INLET CI DES. 3 (STD)	4.000	EA
0400	611(G)8012	INLET CDI RCB DES. 4	2.000	EA
0410	611(G)9000	INLET CDI RCP DES. 1	5.000	EA
0420	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	6.000	VF
0430	611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	4.000	VF
0440	611(H)0532	ADD'L DEPTH IN INLET CDI RCB DES. 4	4.000	VF
0450	611(H)0680	ADD'L DEPTH IN INLET CDI RCP DES. 1	8.000	VF
0460	611(H)0920	ADD'L DEPTH IN INLET W/SJB, CI, DES. 2	13.000	VF

Proposal:250288 **Let Date:**November 13, 2025 **Call Order:**595
J/P Num:33317(04) **Proj. Num:**STP-272B(445)IG
Counties:TULSA
Description:INTERSECTION MODIFICATION
COUNTY ROAD (E 106TH ST N): AT THE INTERSECTION
OF N 129TH E AVE, 0.48 MILES WEST OF US-169 IN THE CITY OF OWASSO.
PROJECT LENGTH = 0.382 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	613(A)5204	15" R.C.PIPE CLASS III	309.000	LF
0480	613(A)5208	18" R.C.PIPE CLASS III	2,110.000	LF
0490	613(A)5216	24" R.C.PIPE CLASS III	268.000	LF
0500	613(A)5220	30" R.C.PIPE CLASS III	2.000	LF
0510	613(B)5504	15" CORR. GALV. STEEL PIPE	147.000	LF
0520	613(B)5508	18" CORR. GALV. STEEL PIPE	32.000	LF
0530	613(B)5516	24" CORR. GALV. STEEL PIPE	188.000	LF
0540	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	3,652.000	LF
0550	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0560	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0570	613(N)7100	TYPE A4 SLOPED CONCRETE END SECTION	16.000	EA
0580	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0590	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	8,803.000	SY
0600	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	215.000	SY
0610	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	584.000	SY
0620	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	163.000	SY
0630	625(B)4300	REMOVE AND RECONSTRUCT FENCE	944.000	LF
0640	629(A)7200	MAILBOX INSTALLATION-SINGLE	4.000	EA

Proposal:250288 **Let Date:**November 13, 2025 **Call Order:**595
J/P Num:33317(04) **Proj. Num:**STP-272B(445)IG
Counties:TULSA
Description:INTERSECTION MODIFICATION
COUNTY ROAD (E 106TH ST N): AT THE INTERSECTION
OF N 129TH E AVE, 0.48 MILES WEST OF US-169 IN THE CITY OF OWASSO.
PROJECT LENGTH = 0.382 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC SIGNALS			
0650	802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	13.000	LF
0660	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	178.000	LF
0670	802(B)0336	4" PVC SCH.40 PLASTIC CONDUIT BORED	347.000	LF
0680	802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	26.000	LF
0700	803(A)1220	PULL BOX(SIZE II)	4.000	EA
0710	804(A)2200	STRUCTURAL CONCRETE	31.000	CY
0720	804(B)2300	REINFORCING STEEL	4,356.000	LB
0730	806(A)4256	32'MH POLE 45'TS & 10'LMA(G.STL.)	1.000	EA
0740	806(A)4260	32'MH POLE 50'TS & 10'LMA(G.STL.)	3.000	EA
0750	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	7.000	EA
0760	809(A)7200	ROADWAY LUMINAIRE	4.000	EA
0770	810(A)8200	SERVICE POLE	1.000	EA
0780	811 9120	1/C NO.6 ELECT.COND.	13.000	LF
0790	811 9130	1/C NO.10 ELECT.COND.	1,282.000	LF
0800	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
0810	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0820	830 2100	PEDESTRIAN PUSH BUTTON	8.000	EA
0830	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	8.000	EA
0840	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
0850	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	4.000	EA
0860	833 5100	BACKPLATE	12.000	EA
0870	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	392.000	LF
0880	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	280.000	LF
0890	834(A)6225	15/C TRAFFIC SIGNAL ELECTRICAL CABLE	608.000	LF
0900	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,224.000	LF
0910	850(A)1200	SHEET ALUMINUM SIGNS	38.000	SF
0920	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	80.000	SF
0003	PERMANENT TRAFFIC			
0930	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
0940	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0950	850(A)1200	SHEET ALUMINUM SIGNS	117.000	SF
0960	851(C)2430	2 1/2" SQUARE TUBE POST	158.000	LF
0970	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	23,022.000	LF
0980	854(B)6301	(SP) TRAFFIC STRIPE(PAINT)(ARROW)	24.000	EA
0990	854(B)6321	(SP) TRAFFIC STRIPE(PAINT)(SYMBOLS)	10.000	EA
1000	880(C)6415	BARRICADES(TYPE III)	7.000	EA

Proposal:250288 **Let Date:**November 13, 2025 **Call Order:**595
J/P Num:33317(04) **Proj. Num:**STP-272B(445)IG
Counties:TULSA
Description:INTERSECTION MODIFICATION
COUNTY ROAD (E 106TH ST N): AT THE INTERSECTION
OF N 129TH E AVE, 0.48 MILES WEST OF US-169 IN THE CITY OF OWASSO.
PROJECT LENGTH = 0.382 MILES

Line #		Item Description	Quantity	Unit
0004	TEMPORARY TRAFFIC			
1010	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	39,420.000	LF
1020	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	12,700.000	LF
1030	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	420.000	LF
1040	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,260.000	LF
1050	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	11,220.000	SD
1060	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,000.000	SD
1070	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,580.000	SD
1080	880(B)6330	CONSTRUCTION SIGNS 33.0 SF & OVER	1,000.000	SD
1090	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,820.000	SD
1100	880(E)6600	WARNING LIGHTS(TYPE A)	8,760.000	SD
1110	880(F)6700	DRUMS	5,000.000	SD
1120	880(G)6805	CHANNELIZER CONES	54,630.000	SD
1130	880(I)7000	FLAGGER	50.000	SD
1140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	90.000	SD

Proposal:250288 **Let Date:**November 13, 2025 **Call Order:**595
J/P Num:33317(04) **Proj. Num:**STP-272B(445)IG
Counties:TULSA
Description:INTERSECTION MODIFICATION
COUNTY ROAD (E 106TH ST N): AT THE INTERSECTION
OF N 129TH E AVE, 0.48 MILES WEST OF US-169 IN THE CITY OF OWASSO.
PROJECT LENGTH = 0.382 MILES

Line #		Item Description	Quantity	Unit
0005	WATER LINE			
1150	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
1160	202(A)2200	UNCLASSIFIED EXCAVATION	1,683.000	CY
1170	230(A)7200	SOLID SLAB SODDING	4,427.000	SY
1180	616(A)2220	12" DUCTILE IRON PIPE	45.000	LF
1190	616(B)2332	4" POLYVINYL CHLORIDE (PVC) PIPE	30.000	LF
1200	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	102.000	LF
1210	616(B)2352	12" POLYVINYL CHLORIDE (PVC) PIPE	3,310.000	LF
1220	616(D)2630	2" GATE VALVE	2.000	EA
1230	616(D)2642	4" GATE VALVE	2.000	EA
1240	616(D)2646	6" GATE VALVE	12.000	EA
1250	616(D)2658	12" GATE VALVE	26.000	EA
1260	616(D)2800	STANDARD VALVE BOX	42.000	EA
1270	616(D)2804	VALVE BOX EXTENSION	42.000	EA
1280	616(F)3030	METER INSTALLATION 3/4"	4.000	EA
1290	616(G)3100	FIRE HYDRANTS	8.000	EA
1300	616(G)3105	FIRE HYDRANT EXTENSION	8.000	EA
1310	616(I)3333	24" STEEL CASING	127.000	LF
1320	616(J)3440	BORE AND JACK 24" CASING	335.000	LF
1330	616(K)3500	2" SOLID SLEEVE	2.000	EA
1340	616(K)3508	4" SOLID SLEEVE	3.000	EA
1350	616(K)3512	6" SOLID SLEEVE	2.000	EA
1360	616(K)3524	12" SOLID SLEEVE	4.000	EA
1370	616(L)3600	(PL) FLANGE ADAPTER	8.000	EA
1380	616(L)3610	6" BLIND FLANGE	1.000	EA
1390	616(L)3620	12" BLIND FLANGE	2.000	EA
1400	616(N)3800	SERVICE CONNECTION (SHORT)	5.000	EA
1410	616(N)3805	SERVICE CONNECTION (LONG)	3.000	EA
1420	616(O)3935	2" 90 DEGREE FITTING	1.000	EA
1430	616(O)3960	4" FIITTING	4.000	EA
1440	616(O)3975	6" 11 1/4 DEGREE FITTING	2.000	EA
1450	616(O)3990	6" 90 DEGREE FITTING	2.000	EA
1460	616(O)4035	12" 11 1/4 DEGREE FITTING	2.000	EA
1470	616(O)4040	12" 22 1/2 DEGREE FITTING	6.000	EA
1480	616(O)4045	12" 45 DEGREE FITTING	5.000	EA
1490	616(O)4050	12" 90 DEGREE FITTING	7.000	EA
1500	616(P)4108	2" HDPE PIPE	30.000	LF
1510	616(R)4344	12" X 6" REDUCER	2.000	EA
1520	616(T)4525	6" X 4" TEE	1.000	EA
1530	616(T)4535	6" X 6" X 6" TEE	2.000	EA
1540	616(T)4590	12" X 12" X 4" TEE	1.000	EA
1550	616(T)4595	12" X 12" X 6" TEE	7.000	EA
1560	616(T)4610	12" X 12" X 12" TEE	4.000	EA
0006	STAKING			
1570	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal:250288 **Let Date:**November 13, 2025 **Call Order:**595
J/P Num:33317(04) **Proj. Num:**STP-272B(445)IG
Counties:TULSA
Description:INTERSECTION MODIFICATION
COUNTY ROAD (E 106TH ST N): AT THE INTERSECTION
OF N 129TH E AVE, 0.48 MILES WEST OF US-169 IN THE CITY OF OWASSO.
PROJECT LENGTH = 0.382 MILES

Line #		Item Description	Quantity	Unit
0007	CONSTRUCTION			
1580	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1590	641 2110	MOBILIZATION	1.000	LSUM
0008	WATER LINE -NON-PARTICIPATING			
1600	202(A)2200	UNCLASSIFIED EXCAVATION	587.000	CY
1610	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	100.000	LF
1620	616(B)2352	12" POLYVINYL CHLORIDE (PVC) PIPE	1,445.000	LF
1630	616(J)3425	BORE AND JACK 16" CASING	80.000	LF
1640	616(O)4045	12" 45 DEGREE FITTING	4.000	EA