Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY - NHPPI-4000(201)FP			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	212,435.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,000.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	1,000.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	17.000	EA
0070	221(C)2410	REINFORCED SILT FENCE	5,890.000	LF
0080	221(E)2600	TEMPORARY SILT DIKE	2,814.000	LF
0090	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	74.200	CY
0100	230(A)7200	SOLID SLAB SODDING	242,748.530	SY
0110	233(A)0200	VEGETATIVE MULCHING	100.300	AC
0120	241 3100	MOWING	100.300	AC
0130	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0140	303(A)1200	AGGREGATE BASE TYPE A	1,353.120	CY
0150	307(K)4200	STABILIZED SUBGRADE	128,695.330	SY
0160	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	6,600.410	SY
0170	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	787.730	TON
0180	405 5100	PERMEABLE FRICTION COURSE	6,703.430	TON
0190	407(B)7300	TACK COAT	33,524.300	GAL
0200	408 8100	PRIME COAT	46,787.000	GAL
0210	411(B)1300	SUPERPAVE, TYPE S3(PG 76-28 OK)	20,160.940	TON
0220	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	62,579.300	TON
0230	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,862.420	TON
0240	411(F)1700	STONE MATRIX ASPHALT	18,133.740	TON
0250	411(G)1800	RICH BOTTOM LAYER	17,511.450	TON
0260	412 3100	COLD MILLING PAVEMENT	81,137.280	SY
0270	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	171.280	CY
0280	501(G)1810	CLSM BACKFILL	14.000	CY
0290	509(A)0200	CLASS AA CONCRETE	993.600	CY
0291	509(B)0300	CLASS A CONCRETE	336.000	CY
0300	509(D)0500	CLASS C CONCRETE	113.660	CY
0310	511(A)2200	REINFORCING STEEL	192,633.950	LB
0320	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	826.510	TON
0330	602(B)2310	REVETMENT MATTRESSES	5,307.100	SY
0340	611(G)0354	INLET (SMD-TYPE 2)	24.000	EA
0350	611(G)7958	INLET GPI TYPE 2 (DES. 8)	1.000	EA
0360	611(H)0400	ADDITIONAL DEPTH IN INLET	4.830	VF
0370	612(C)3400	INLET ADJUST TO GRADE	3.000	EA
0380	613(A)5208	18" R.C.PIPE CLASS III	1,795.000	LF
0390	613(A)5216	24" R.C.PIPE CLASS III	587.000	LF
0400	613(A)5314	24" R.C.PIPE CLASS V	124.000	LF
0410	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	190.000	LF
0420	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	111.000	LF
0430	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
0440	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	100.000	LF
0450	613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	3.000	EA

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY - NHPPI-4000(201)FP			
0460	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0470	613(M)6960	TYPE A4 CULVERT END TREATMENT	6.000	EA
0480	613(M)7012	TYPE C6 CULVERT END TREATMENT	3.000	EA
0490	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0500	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	191.190	CY
0510	613(V)8000	TRENCH EXCAVATION	2,308.540	CY
0520	613(W)8130	36" JACKED CONDUIT	124.000	LF
0530	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0540	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	55,000.880	SY
0550	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
0560	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0570	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0580	624(A)3200	FENCE-STYLE WWF	6,876.000	LF
0590	624(E)3620	FENCE-STYLE CLF (6'HIGH, CLASS A)	214.000	LF
0610	629(A)7200	MAILBOX INSTALLATION-SINGLE	1.000	EA
0620	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	1.000	EA
0630	629(D)7500	REMOVE AND RESET MAILBOX	5.000	EA
0640	629(E)7600	MAILBOX	1.000	EA
0002	BRIDGE "A" - NHPPI-4000(201)FP			
0650	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0660	501(G)1800	CLSM BACKFILL	48.000	CY
0670	504(A)5200	APPROACH SLAB	141.600	SY
0680	504(B)5300	SAW-CUT GROOVING	941.200	SY
0690	504(D)5410	CONCRETE RAIL (TR3)	591.400	LF
0691	504(E)5520	42" F-SHAPED PARAPET	840.000	LF
0700	506(A)7200	STRUCTURAL STEEL	236,780.000	LB
0710	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
0720	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	24.000	EA
0730	507(C)8400	ELASTOMERIC BEARING PADS	24.000	EA
0740	509(A)0210	CLASS AA CONCRETE	256.800	CY
0750	509(B)0320	CLASS A CONCRETE	208.200	CY
0760	510(C)1450	SLOPE WALL (5")	798.000	SY
0770	511(A)2210	REINFORCING STEEL	115,450.000	LB
0780	514(A)5210	PILES, FURNISHED (HP 10X42)	295.000	LF
0790	514(B)5310	PILES, DRIVEN (HP 10X42)	295.000	LF
0800	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0810	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	198.000	SY
0820	516(A)8250	DRILLED SHAFTS 72" DIAMETER	138.000	LF
0830	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0840	517 9110	ELASTOMERIC COATING	888.000	SF
0850	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	152.000	LF
0860	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	80.000	LF
0870	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0880	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

	Line #		Item Description	Quantity	Unit
0003	BRIDGE "B" - NHPPI-4000(201)FP				
	0890	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0004	TRAFFIC SIGNING, STRIPING, AND BARRIER - NHPPI-4000(201)FP				
	0900	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	51,431.000	LF
	0910	516(A)8230	DRILLED SHAFTS 48" DIAMETER	100.000	LF
	0920	619(B)6432	REMOVAL OF CABLE BARRIER	10,896.000	LF
	0930	628 7100	INSTALLATION OF CABLE BARRIER SYSTEM	10,857.000	LF
	0940	628(C)7400	END ANCHORS	2.000	EA
	0950	804(A)2200	STRUCTURAL CONCRETE	0.300	CY
	0960	804(B)2300	REINFORCING STEEL	38.000	LB
	0970	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	5.000	EA
	0980	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	5.000	EA
	0990	850(A)1200	SHEET ALUMINUM SIGNS	135.500	SF
	1000	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	192.000	SF
	1010	850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	690.000	SF
	1020	851(C)2430	2 1/2" SQUARE TUBE POST	143.000	LF
	1030	852(E)3621	OVHD.SN.STR., MONOTUBE C1	4.000	EA
	1040	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	67,665.000	LF
	1050	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	11.000	LF
	1060	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	3.000	EA
	1070	870(A)1100	SAND FILLED IMPACT ATTEN.MODULE	38.000	EA
	1080	871(A)2200	IMPACT ATTENUATOR	4.000	EA
0005	TRAFFIC CONTROL - NHPPI-4000(201)FP				
	1090	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	129,798.000	LF
	1100	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	11,500.000	LF
	1110	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	12,875.000	LF
	1120	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	1,503.000	EA
	1130	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	1,447.000	EA
	1140	871(B)2300	CONST.ZONE IMPACT ATTEN.	840.000	SD
	1150	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	10.000	SD
	1160	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	27,830.000	LF
	1170	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	32,818.000	LF
	1180	880(A)6220	ARROW DISPLAY(TYPE C)	480.000	SD
	1190	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	35,420.000	SD
	1200	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	23,395.000	SD
	1210	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	36,550.000	SD
	1220	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	6,840.000	SD
	1230	880(D)6500	VERTICAL PANELS	107,220.000	SD
	1240	880(E)6607	WARNING LIGHTS(TYPE B)	41,400.000	SD
	1250	880(F)6700	DRUMS	86,640.000	SD
	1260	880(G)6805	CHANNELIZER CONES	180.000	SD
	1270	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	2,495.000	SD

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

Line #		Item Description	Quantity	Unit
0006	ROADWAY - NHPPI-4000-(235)FP			
1280	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
1290	202(A)2200	UNCLASSIFIED EXCAVATION	319,074.000	CY
1300	202(D)2500	UNCLASSIFIED BORROW	13,180.000	CY
1310	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
1320	221(B)2300	TEMPORARY SILT FENCE	1,000.000	LF
1330	221(C)2400	TEMPORARY SEDIMENT FILTER	14.000	EA
1340	221(C)2410	REINFORCED SILT FENCE	9,655.000	LF
1350	221(D)2500	TEMPORARY SEDIMENT BASIN	1.000	EA
1360	221(E)2600	TEMPORARY SILT DIKE	4,028.000	LF
1370	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	7.000	CY
1380	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	14.000	CY
1390	230(A)7200	SOLID SLAB SODDING	395,533.000	SY
1400	233(A)0200	VEGETATIVE MULCHING	161.800	AC
1410	241 3100	MOWING	161.800	AC
1420	303(A)1200	AGGREGATE BASE TYPE A	39,632.000	CY
1430	307(K)4200	STABILIZED SUBGRADE	194,337.000	SY
1440	310(B)5300	SUBGRADE, METHOD B	41,210.000	SY
1450	325 0100	SEPARATOR FABRIC	200,670.000	SY
1460	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	28,210.000	TON
1470	407(B)7300	TACK COAT	2,996.000	GAL
1480	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	2,579.000	TON
1490	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	37,877.000	TON
1500	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	1,720.000	TON
1510	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,592.000	TON
1520	412 3100	COLD MILLING PAVEMENT	7,887.000	SY
1530	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	82,557.000	SY
1540	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	100,150.000	SY
1550	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	500.000	SY
1560	414(G)5800	P.C. CONCRETE FOR PAVEMENT	55,389.000	CY
1570	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	116.100	CY
1580	509(A)0200	CLASS AA CONCRETE	337.000	CY
1590	509(D)0500	CLASS C CONCRETE	106.830	CY
1600	511(A)2200	REINFORCING STEEL	49,454.000	LB
1610	601(B)1220	TYPE I-A PLAIN RIPRAP	2,047.000	TON
1620	601(C)1300	TYPE I-A FILTER BLANKET	602.000	TON
1630	602(B)2310	REVETMENT MATTRESSES	25,635.000	SY
1640	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	1,673.000	LF
1650	611(G)0350	INLET (SMD-TYPE 1)	1.000	EA
1660	611(G)0354	INLET (SMD-TYPE 2)	5.000	EA
1670	611(G)7754	INLET CI DES. 2 (STD)	2.000	EA
1680	612(C)3400	INLET ADJUST TO GRADE	1.000	EA
1690	613(A)5216	24" R.C.PIPE CLASS III	574.000	LF
1700	613(A)5220	30" R.C.PIPE CLASS III	63.000	LF
1710	613(A)5322	42" R.C.PIPE CLASS V	216.000	LF
1720	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	555.000	LF
1730	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	224.000	LF

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

Line #		Item Description	Quantity	Unit
0006	ROADWAY - NHPPI-4000-(235)FP			
1740	613(B)5508	18" CORR. GALV. STEEL PIPE	1,546.000	LF
1750	613(B)5516	24" CORR. GALV. STEEL PIPE	26.000	LF
1760	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	156.000	LF
1770	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	2,360.000	LF
1780	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	19,000.000	LF
1790	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	1,920.000	LF
1800	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
1810	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA
1820	613(L)6732	42" PREFAB. CULVERT END SEC., ROUND	2.000	EA
1830	613(M)6964	TYPE B4 CULVERT END TREATMENT	8.000	EA
1840	613(M)6984	TYPE BB4 CULVERT END TREATMENT	4.000	EA
1850	613(M)6988	TYPE CC4 CULVERT END TREATMENT	2.000	EA
1860	613(Q)7500	OUTLET LATERAL HEADWALL	67.000	EA
1870	613(W)8135	42" JACKED CONDUIT	216.000	LF
1880	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
1890	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	100,713.000	SY
1900	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	44,405.000	SY
1910	619(B)6464	REMOVAL OF 6" CONCRETE DIVIDING STRIP	982.000	SY
1920	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	1,465.000	LF
1930	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
1940	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
1950	624(A)3200	FENCE-STYLE WWF	22,406.000	LF
1960	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	973.000	LF
1970	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	917.000	LF
1980	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	1,642.000	LF

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

	Line #		Item Description	Quantity	Unit
0007	BRIDGE 'A' - NHPPI-4000-(235)FP				
	1990	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	260.000	CY
	2000	501(G)1800	CLSM BACKFILL	230.000	CY
	2010	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
	2020	504(A)5200	APPROACH SLAB	414.800	SY
	2030	504(B)5300	SAW-CUT GROOVING	2,374.600	SY
	2040	504(D)5420	CONCRETE RAIL (TR4)	712.400	LF
	2050	506(A)7200	STRUCTURAL STEEL	434,480.000	LB
	2060	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	14.000	EA
	2070	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	42.000	EA
	2080	509 0110	SPECIAL CONCRETE FINISH	1.000	LSUM
	2090	509(A)0210	CLASS AA CONCRETE	471.000	CY
	2100	509(B)0320	CLASS A CONCRETE	372.200	CY
	2110	509(D)0510	CLASS C CONCRETE	25.000	CY
	2120	510(C)1450	SLOPE WALL (5")	1,186.000	SY
	2130	511 2100	MECHANICAL SPLICES	140.000	EA
	2140	511(A)2210	REINFORCING STEEL	3,040.000	LB
	2150	511(B)2310	EPOXY COATED REINFORCING STEEL	222,050.000	LB
	2160	514(A)5210	PILES, FURNISHED (HP 10X42)	164.000	LF
	2170	514(A)5220	PILES, FURNISHED (HP 12X53)	716.000	LF
	2180	514(B)5310	PILES, DRIVEN (HP 10X42)	164.000	LF
	2190	514(B)5320	PILES, DRIVEN (HP 12X53)	716.000	LF
	2200	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	2210	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,259.000	SY
	2220	516(A)8250	DRILLED SHAFTS 72" DIAMETER	420.000	LF
	2230	516(A)8255	DRILLED SHAFTS 84" DIAMETER	236.000	LF
	2240	516(C)8400	CROSSHOLE SONIC LOGGING	3.000	EA
	2250	518(B)0300	SEALED EXPANSION JOINTS	61.760	LF
	2260	523(A)3200	SEALER CRACK PREPARATION	418.000	LF
	2270	523(B)3300	SEALER RESIN	4.700	GAL
	2280	535 7180	(SP)AESTHETIC FORM LINERS (NON-BIDDABLE)	1.000	LSUM
	2290	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	262.000	LF
	2300	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	108.000	LF
	2310	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
	2320	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0008	BRIDGE 'B' - NHPPI-4000-(235)FP				
	2330	202(A)2210	UNCLASSIFIED EXCAVATION	12,240.000	CY
	2340	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	1,050.000	CY
	2350	509(A)0210	CLASS AA CONCRETE	2,403.500	CY
	2360	511(A)2210	REINFORCING STEEL	540,360.000	LB
	2370	619(B)6312	REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
	2380	619(B)6320	REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

	Line #		Item Description	Quantity	Unit
0009	TRAFFIC SIGNING, STRIPING, AND BARRIER - NHPPI-4000-(235)FP				
	2390	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	37,490.000	LF
	2400	509(A)0200	CLASS AA CONCRETE	76.000	CY
	2410	516(A)8230	DRILLED SHAFTS 48" DIAMETER	106.000	LF
	2420	619(B)6432	REMOVAL OF CABLE BARRIER	7,809.000	LF
	2430	628 7100	INSTALLATION OF CABLE BARRIER SYSTEM	7,936.000	LF
	2440	628(C)7400	END ANCHORS	2.000	EA
	2450	804(A)2200	STRUCTURAL CONCRETE	28.400	CY
	2460	804(B)2300	REINFORCING STEEL	6,228.000	LB
	2470	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	38.000	EA
	2480	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
	2490	850(A)1200	SHEET ALUMINUM SIGNS	640.700	SF
	2500	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	993.800	SF
	2510	850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	754.000	SF
	2520	851(A)2215	6"@25 GALV.STL.WD.FLANGE BM.POST	448.000	LF
	2530	851(A)2220	8"@31 GALV.STL.WD.FLANGE BM.POST	87.000	LF
	2540	851(B)2310	2 1/2"@5.79 GALV.STL.PIPE POST	56.000	LF
	2550	851(B)2315	3"@7.58 GALV.STL.PIPE POST	138.000	LF
	2560	851(B)2320	3 1/2"@9.11 GALV.STL.PIPE POST	84.000	LF
	2570	851(C)2430	2 1/2" SQUARE TUBE POST	624.500	LF
	2580	852(E)3621	OVHD.SN.STR., MONOTUBE C1	2.000	EA
	2581	852(E)3622	OVHD.SN.STR., MONOTUBE C2	2.000	EA
	2590	853 5100	DELINEATORS(TYPE 1, CODE 1)	49.000	EA
	2600	853 5105	DELINEATORS(TYPE 1, CODE 2)	57.000	EA
	2601	853 5120	DELINEATORS(TYPE 2, CODE 2)	14.000	EA
	2620	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	85,349.000	LF
	2630	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	623.000	LF
	2640	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	2,256.000	LF
	2650	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	199.000	LF
	2660	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	25.000	EA
	2661	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	132.000	EA
	2662	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	91.000	EA
	2670	870(A)1100	SAND FILLED IMPACT ATTEN.MODULE	19.000	EA
	2680	871(A)2210	(PL) IMPACT ATTENUATOR	4.000	EA
	2690	878(A)5200	MODULAR GLARE SCREEN (PERMANENT)	1,002.000	LF

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

	Line #		Item Description	Quantity	Unit
0010	TRAFFIC SIGNAL - NHPPI-4000-(235)FP				
	2700	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	173.000	LF
	2710	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	200.000	LF
	2720	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	40.000	LF
	2730	803(A)1210	PULL BOX(SIZE I)	4.000	EA
	2740	803(A)1220	PULL BOX(SIZE II)	2.000	EA
	2750	804(A)2200	STRUCTURAL CONCRETE	32.000	CY
	2760	804(B)2300	REINFORCING STEEL	4,729.200	LB
	2770	806(A)4236	32'MH POLE,20'TS & 10'LMA(G.STL.)	2.000	EA
	2780	806(A)4244	32'MH POLE,30'TS & 10'LMA(G.STL.)	1.000	EA
	2790	806(A)4248	32'MH POLE 35'TS & 10'LMA(G.STL.)	1.000	EA
	2800	806(A)4256	32'MH POLE 45'TS & 10'LMA(G.STL.)	2.000	EA
	2810	810(A)8200	SERVICE POLE	1.000	EA
	2820	811 9120	1/C NO.6 ELECT.COND.	100.000	LF
	2830	811 9130	1/C NO.10 ELECT.COND.	2,020.000	LF
	2840	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
	2850	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	12.000	EA
	2860	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	1.000	EA
	2870	831 3152	1WAY5SEC.ADJ.SIG.HD.S-17	1.000	EA
	2880	833 5100	BACKPLATE	14.000	EA
	2890	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	532.000	LF
	2900	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	110.000	LF
	2910	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	643.000	LF
	2920	840(B)0300	E.P.S. OPTICAL DETECTOR	6.000	EA
	2930	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	1,500.000	LF
	2940	840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	4.000	EA
	2950	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	40.500	SF

Proposal: 250331 **Let Date:** March 19, 2026 **Call Order:** 464
J/P Num: 21007(07) **Proj. Num:** NHPPI-4000-(201)FP
26422(05) NHPPI-4000-(235)FP
Counties: OKLAHOMA, POTTAWATOMIE
Description: GRADE, DRAIN, BRIDGE, AND SURFACE
I-40: FROM THE I-335 INTERCHANGE, EXTEND EAST NEAR NEWALLA.
PROJECT LENGTH = 5.104 MILES

	Line #		Item Description	Quantity	Unit
0011	TRAFFIC CONTROL - NHPPI-4000-(235)FP				
	2960	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	113,070.000	LF
	2970	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	74,555.000	LF
	2980	857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	6,000.000	EA
	2990	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	69,438.000	LF
	3000	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	6,900.000	EA
	3010	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	3,649.000	EA
	3020	871(B)2300	CONST.ZONE IMPACT ATTEN.	5,785.000	SD
	3030	871(C)2410	RELOCATION OF IMPACT ATTENUATOR	13.000	EA
	3040	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	33,155.000	LF
	3050	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	41,730.000	LF
	3060	878(B)5300	MODULAR GLARE SCREEN (TEMPORARY)	26,150.000	SD
	3070	880(A)6220	ARROW DISPLAY(TYPE C)	715.000	SD
	3080	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	26,610.000	SD
	3090	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	55,385.000	SD
	3100	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	47,060.000	SD
	3110	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	30,975.000	SD
	3120	880(D)6500	VERTICAL PANELS	62,645.000	SD
	3130	880(E)6607	WARNING LIGHTS(TYPE B)	76,010.000	SD
	3140	880(F)6700	DRUMS	173,520.000	SD
	3150	880(G)6805	CHANNELIZER CONES	18,200.000	SD
	3160	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	2,720.000	HOUR
	3170	882 8100	(SP)SMART WORK ZONE SYSTEM	1,100.000	SD
	3180	882 8105	(SP)SMART WK. ZONE SYS.-PORT.CHNG.MSG.SN	22,000.000	SD
	3190	882 8110	(SP)SMART WK. ZONE SYS.-PORT.TRAF.SENSOR	15,400.000	SD
	3200	882 8115	(SP)SMART WK ZONE SYS-PAN-TILT-ZOOM CMRA	4,400.000	SD
	3210	882 8120	(SP)SMART WK. ZONE SYS.-WEBSITE SYSTEM	1,100.000	SD
	3220	882 8125	(PL)SMART WORK ZONE SYSTEM SETUP	1.000	EA
	3230	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	2,680.000	SD
0012	STAKING - NHPPI-4000-(235)FP				
	3240	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0013	CONSTRUCTION - NHPPI-4000-(235)FP				
	3250	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	3260	640(A)1210	FIELD OFFICE	1.000	EA
	3270	641 2110	MOBILIZATION	1.000	LSUM