Proposal: 250332 **Let Date:** February 19, 2026 **Call Order:** 245
J/P Num: 32844(04) **Proj. Num:** STP-266D(135)CI
Counties: ROGERS
Description: BRIDGE AND APPROACHES
COUNTY ROAD (NS 4310 RD): OVER LITTLE PRYOR CREEK,
1.84 MILES SOUTH OF SH-66 NEAR CHELSEA.
PROJECT LENGTH = 0.317 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	10,352.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	3,336.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	203.000	LF
0060	230(A)7200	SOLID SLAB SODDING	20,320.000	SY
0070	303(A)1200	AGGREGATE BASE TYPE A	1,461.000	CY
0080	325 0100	SEPARATOR FABRIC	5,681.000	SY
0090	407(B)7300	TACK COAT	402.000	GAL
0100	408 8100	PRIME COAT	1,367.000	GAL
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,197.000	TON
0120	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	600.000	TON
0130	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	0.910	CY
0140	511(A)2200	REINFORCING STEEL	61.000	LB
0150	601(A)1100	TYPE I PLAIN RIPRAP	165.000	TON
0160	611(A)7252	PRECAST CONC RND 4' DIA MANHOLE	1.000	EA
0170	613(A)5204	15" R.C.PIPE CLASS III	16.000	LF
0180	613(A)5208	18" R.C.PIPE CLASS III	33.000	LF
0190	613(B)5508	18" CORR. GALV. STEEL PIPE	122.000	LF
0200	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0210	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0220	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	5.830	CY
0230	613(V)8000	TRENCH EXCAVATION	30.000	CY
0240	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0250	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	3,563.000	SY
0260	619(C)6600	SAWING PAVEMENT	88.000	LF
0270	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	300.000	LF
0280	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0290	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0300	626(A)5200	MONUMENTS	1.000	EA
0310	629(A)7200	MAILBOX INSTALLATION-SINGLE	1.000	EA

Proposal:250332 **Let Date:**February 19, 2026 **Call Order:**245
J/P Num:32844(04) **Proj. Num:**STP-266D(135)CI
Counties:ROGERS
Description:BRIDGE AND APPROACHES
COUNTY ROAD (NS 4310 RD): OVER LITTLE PRYOR CREEK,
1.84 MILES SOUTH OF SH-66 NEAR CHELSEA.
PROJECT LENGTH = 0.317 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO. 33448			
0320	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
0330	501(G)1800	CLSM BACKFILL	102.000	CY
0340	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	299.000	LF
0350	504(B)5300	SAW-CUT GROOVING	254.400	SY
0360	504(D)5410	CONCRETE RAIL (TR3)	281.300	LF
0370	506(A)7200	STRUCTURAL STEEL	330.000	LB
0380	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	3.000	EA
0390	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	3.000	EA
0400	509(A)0210	CLASS AA CONCRETE	81.400	CY
0410	509(B)0320	CLASS A CONCRETE	80.300	CY
0420	511(A)2210	REINFORCING STEEL	11,480.000	LB
0430	511(B)2310	EPOXY COATED REINFORCING STEEL	20,980.000	LB
0440	514(A)5210	PILES, FURNISHED (HP 10X42)	86.000	LF
0450	514(A)5220	PILES, FURNISHED (HP 12X53)	210.000	LF
0460	514(B)5310	PILES, DRIVEN (HP 10X42)	86.000	LF
0470	514(B)5320	PILES, DRIVEN (HP 12X53)	210.000	LF
0480	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0490	517 9110	ELASTOMERIC COATING	131.200	SF
0500	601(B)1230	TYPE I-A PLAIN RIPRAP	2,270.000	TON
0510	601(C)1310	TYPE I-A FILTER BLANKET	570.000	TON
0520	601(I)1700	FILTER FABRIC (RIPRAP)	2,270.000	SY
0530	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
0540	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	110.000	LF
0003	TRAFFIC			
0550	850(A)1200	SHEET ALUMINUM SIGNS	20.360	SF
0560	851(C)2415	2" SQUARE TUBE POST	50.000	LF
0570	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	6,607.000	LF
0580	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	22.000	LF
0590	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,260.000	SD
0600	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	360.000	SD
0610	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0620	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	360.000	SD
0630	880(E)6600	WARNING LIGHTS(TYPE A)	720.000	SD
0004	STAKING			
0640	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0650	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0660	641 2100	MOBILIZATION	1.000	LSUM