Proposal:250334 **Let Date:**November 20, 2025 **Call Order:**010
J/P Num:37300(08) **Proj. Num:**JKT-30702A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
JOHN KILPATRICK TURNPIKE (I-344): FROM W WILSHIRE BLVD, EXTEND NORTH IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 3.640 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	15,923.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,000.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(C)2400	TEMPORARY SEDIMENT FILTER	25.000	EA
0060	221(E)2600	TEMPORARY SILT DIKE	2,142.000	LF
0065	230(A)7200	SOLID SLAB SODDING	3,000.000	SY
0070	242 4101	STABILIZED CONSTRUCTION EXIT	4.000	EA
0080	307(K)4200	STABILIZED SUBGRADE	97,901.000	SY
0090	319(B)9300	OPEN-GRADED PORTLAND CEMENT BASE	18,971.000	SY
0100	325 0100	SEPARATOR FABRIC	97,901.000	SY
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	17,681.000	TON
0120	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	46,598.000	SY
0130	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	51,303.000	SY
0140	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	1,510.000	SY
0150	414(G)5800	P.C. CONCRETE FOR PAVEMENT	30,376.000	CY
0160	501(F)1700	GRANULAR BACKFILL	159.000	CY
0170	501(G)1810	CLSM BACKFILL	654.000	CY
0180	504(E)5500	CONCRETE PARAPET	364.000	LF
0190	509(B)0300	CLASS A CONCRETE	106.000	CY
0200	509(B)0310	CLASS A CONCRETE(LONG. BAR. DES. 1-A)	759.000	CY
0210	511(A)2200	REINFORCING STEEL	18,928.000	LB
0220	610(C)5400	4" CONCRETE DIVIDING STRIP	132.000	SY
0230	611(G)7700	SPECIAL INLET DRAIN	6.000	EA
0240	611(G)8155	INLET - LONG. BARRIER - TYPE I, DES.2	7.000	EA
0250	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	28.000	VF
0260	613(A)5208	18" R.C.PIPE CLASS III	412.000	LF
0270	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	3,535.000	LF
0280	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	55.000	LF
0290	613(M)7004	TYPE A6 CULVERT END TREATMENT	8.000	EA
0300	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0310	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	18,351.000	SY
0320	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	10,814.000	SY
0330	619(B)6396	REMOVAL OF GUARDRAIL	986.000	LF
0340	619(B)6416	REMOVAL OF CONCRETE MEDIAN BARRIER	226.000	LF
0350	619(B)6432	REMOVAL OF CABLE BARRIER	18,358.000	LF
0360	619(C)6600	SAWING PAVEMENT	38,485.000	LF
0370	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	14,975.000	LF

Proposal:250334 **Let Date:**November 20, 2025 **Call Order:**010
J/P Num:37300(08) **Proj. Num:**JKT-30702A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
JOHN KILPATRICK TURNPIKE (I-344): FROM W WILSHIRE BLVD, EXTEND NORTH IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 3.640 MILES

Line #		Item Description	Quantity	Unit
0002	TOLLING			
0380	506(A)7200	STRUCTURAL STEEL	2,400.000	LB
0390	509(A)0200	CLASS AA CONCRETE	27.000	CY
0400	511(B)2300	EPOXY COATED REINFORCING STEEL	3,080.000	LB
0410	516(A)8230	DRILLED SHAFTS 48" DIAMETER	140.000	LF
0430	802(B)0304	1" PVC SCH.40 PLASTIC CONDUIT BORED	1,355.000	LF
0440	802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,022.000	LF
0450	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	299.000	LF
0455	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	150.000	LF
0460	803(A)1200	PULL BOX	10.000	EA
0470	852(B)3300	GALV.STEEL OVERHEAD SIGN STRUCTURE	240.000	LF
0003	BRIDGE			
0480	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	390.000	CY
0490	501(G)1800	CLSM BACKFILL	460.000	CY
0500	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0510	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	637.000	LF
0520	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	678.500	LF
0530	504(A)5200	APPROACH SLAB	352.200	SY
0540	504(B)5300	SAW-CUT GROOVING	1,246.600	SY
0550	504(E)5520	42" F-SHAPED PARAPET	617.600	LF
0560	506(A)7200	STRUCTURAL STEEL	1,440.000	LB
0570	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	18.000	EA
0580	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	18.000	EA
0590	509(A)0210	CLASS AA CONCRETE	251.500	CY
0600	509(B)0320	CLASS A CONCRETE	277.200	CY
0610	510(C)1450	SLOPE WALL (5")	116.000	SY
0620	511 2100	MECHANICAL SPLICES	1,516.000	EA
0630	511(A)2210	REINFORCING STEEL	980.000	LB
0640	511(B)2310	EPOXY COATED REINFORCING STEEL	97,800.000	LB
0650	514(A)5220	PILES, FURNISHED (HP 12X53)	684.000	LF
0660	514(B)5320	PILES, DRIVEN (HP 12X53)	684.000	LF
0670	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0680	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,573.000	SY
0690	516(A)8255	DRILLED SHAFTS 84" DIAMETER	128.000	LF
0700	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
0710	517 9110	ELASTOMERIC COATING	5,060.000	SF
0720	518(B)0300	SEALED EXPANSION JOINTS	88.180	LF
0730	521(A)2200	PNEUMATICALLY PLACED MORTAR	8.600	SY
0740	523(A)3200	SEALER CRACK PREPARATION	617.800	LF
0750	523(B)3300	SEALER RESIN	6.900	GAL
0760	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	80.000	LF
0770	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:250334 **Let Date:**November 20, 2025 **Call Order:**010
J/P Num:37300(08) **Proj. Num:**JKT-30702A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
JOHN KILPATRICK TURNPIKE (I-344): FROM W WILSHIRE BLVD, EXTEND NORTH IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 3.640 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0780	853 5100	DELINEATORS(TYPE 1, CODE 1)	110.000	EA
0790	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	168,000.000	LF
0800	871(B)2300	CONST.ZONE IMPACT ATTEN.	5,180.000	SD
0810	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	48,000.000	LF
0820	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	3,400.000	LF
0830	880(A)6220	ARROW DISPLAY(TYPE C)	720.000	SD
0840	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	7,800.000	SD
0850	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	25,000.000	SD
0860	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	17,000.000	SD
0870	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,600.000	SD
0880	880(E)6600	WARNING LIGHTS(TYPE A)	14,000.000	SD
0890	880(F)6700	DRUMS	31,000.000	SD
0900	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	16,320.000	HOUR
0910	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,700.000	SD
0005	TRAFFIC SIGNING			
0920	805(A)3236	(PL)REMOVAL OF OVERHEAD SIGN STRUCTURE	1.000	EA
0930	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	7.000	EA
0940	850(A)1200	SHEET ALUMINUM SIGNS	76.000	SF
0950	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	468.000	SF
0960	851(C)2430	2 1/2" SQUARE TUBE POST	45.000	LF
0970	853 5165	BARRIER DELINEATORS(TYPE 2, CODE 1)	270.000	EA
0980	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	116,428.000	LF
0990	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	14,955.000	LF
1000	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	2.000	EA
1010	880(G)6810	TUBE CHANNELIZERS	18.000	EA
0006	TRAFFIC LIGHTING			
1020	802(A)0240	2" GALV.STEEL ELECT.COND. EXPOSED	19,460.000	LF
1030	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	406.000	LF
1040	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	962.000	LF
1050	803(A)1210	PULL BOX(SIZE I)	4.000	EA
1060	804(A)2200	STRUCTURAL CONCRETE	279.000	CY
1070	804(B)2300	REINFORCING STEEL	46,530.000	LB
1080	806(C)4524	40' MHP & TWIN H.L.MST.ARM(G.STL.)	101.000	EA
1090	809(A)7200	ROADWAY LUMINAIRE	202.000	EA
1100	810(A)8200	SERVICE POLE	4.000	EA
1110	811 9115	1/C NO.4 ELECT.COND.	49,912.000	LF
1120	811 9130	1/C NO.10 ELECT.COND.	35,383.000	LF
0007	STAKING			
1130	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal:250334 **Let Date:**November 20, 2025 **Call Order:**010
J/P Num:37300(08) **Proj. Num:**JKT-30702A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
JOHN KILPATRICK TURNPIKE (I-344): FROM W WILSHIRE BLVD, EXTEND NORTH IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 3.640 MILES

Line #		Item Description	Quantity	Unit
0008	CONSTRUCTION			
1140	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1150	640(A)1210	FIELD OFFICE	1.000	EA
1160	641 2110	MOBILIZATION	1.000	LSUM