Proposal: 250340 **Let Date:** February 12, 2026 **Call Order:** 120
J/P Num: 31890(04) **Proj. Num:** NHPP-021N(064)FP
Counties: COMANCHE
Description: BRIDGE AND APPROACHES
SH-7: OVER EAST CACHE CREEK, 0.483 MILES EAST OF THE I-44 INTERCHANGE IN THE CITY OF LAWTON.
PROJECT LENGTH = 0.151 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	2,240.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	387.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	1,115.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	49.000	LF
0070	230(A)7200	SOLID SLAB SODDING	7,739.000	SY
0080	232(B)9300	SEEDING METHOD B	2.000	AC
0090	233(A)0200	VEGETATIVE MULCHING	2.000	AC
0100	241 3100	MOWING	3.000	AC
0110	303(A)1200	AGGREGATE BASE TYPE A	510.000	CY
0120	307(K)4200	STABILIZED SUBGRADE	4,842.000	SY
0140	325 0100	SEPARATOR FABRIC	2,554.000	SY
0150	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	331.000	TON
0160	407(B)7300	TACK COAT	739.000	GAL
0170	408 8100	PRIME COAT	1,021.000	GAL
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,159.000	TON
0190	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	326.000	TON
0200	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	598.000	SY
0210	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1,296.000	SY
0220	414(G)5800	P.C. CONCRETE FOR PAVEMENT	500.000	CY
0230	613(B)5504	15" CORR. GALV. STEEL PIPE	372.000	LF
0240	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0250	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0260	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	655.000	SY
0270	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,889.000	SY
0280	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	724.000	SY
0290	619(B)6396	REMOVAL OF GUARDRAIL	738.000	LF
0300	619(B)6400	REMOVAL OF CURB	86.000	LF
0310	619(C)6600	SAWING PAVEMENT	598.000	LF
0320	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	638.000	LF
0330	623(G)1820	GUARDRAIL END TREATMENT (31")	3.000	EA
0340	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA
0350	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	14.000	EA

Proposal: 250340 **Let Date:** February 12, 2026 **Call Order:** 120
J/P Num: 31890(04) **Proj. Num:** NHPP-021N(064)FP
Counties: COMANCHE
Description: BRIDGE AND APPROACHES
SH-7: OVER EAST CACHE CREEK, 0.483 MILES EAST OF THE I-44 INTERCHANGE IN THE CITY OF LAWTON.
PROJECT LENGTH = 0.151 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE "A"			
0360	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
0370	501(G)1800	CLSM BACKFILL	236.000	CY
0380	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,445.000	LF
0390	504(A)5200	APPROACH SLAB	273.400	SY
0400	504(B)5300	SAW-CUT GROOVING	1,484.800	SY
0410	504(E)5520	42" F-SHAPED PARAPET	703.300	LF
0420	506(A)7200	STRUCTURAL STEEL	1,530.000	LB
0430	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	10.000	EA
0440	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
0450	509(A)0210	CLASS AA CONCRETE	336.000	CY
0460	509(B)0320	CLASS A CONCRETE	235.400	CY
0470	509(D)0510	CLASS C CONCRETE	6.000	CY
0480	511(A)2210	REINFORCING STEEL	510.000	LB
0490	511(B)2310	EPOXY COATED REINFORCING STEEL	144,000.000	LB
0500	514(A)5210	PILES, FURNISHED (HP 10X42)	236.000	LF
0510	514(A)5220	PILES, FURNISHED (HP 12X53)	1,221.000	LF
0520	514(B)5310	PILES, DRIVEN (HP 10X42)	236.000	LF
0530	514(B)5320	PILES, DRIVEN (HP 12X53)	1,221.000	LF
0540	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0550	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,351.000	SY
0560	516(A)8240	DRILLED SHAFTS 60" DIAMETER	248.000	LF
0570	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
0580	517 9110	ELASTOMERIC COATING	1,110.000	SF
0590	518(B)0300	SEALED EXPANSION JOINTS	41.000	LF
0600	523(A)3200	SEALER CRACK PREPARATION	38.000	LF
0610	523(B)3300	SEALER RESIN	0.500	GAL
0620	601(B)1230	TYPE I-A PLAIN RIPRAP	1,380.000	TON
0630	601(C)1310	TYPE I-A FILTER BLANKET	260.000	TON
0640	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	82.000	LF
0650	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	44.000	LF
0660	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0670	623 1100	(PL)GUARDRAIL CURBING	1.000	EA

Proposal: 250340 **Let Date:** February 12, 2026 **Call Order:** 120
J/P Num: 31890(04) **Proj. Num:** NHPP-021N(064)FP
Counties: COMANCHE
Description: BRIDGE AND APPROACHES
SH-7: OVER EAST CACHE CREEK, 0.483 MILES EAST OF THE I-44 INTERCHANGE IN THE CITY OF LAWTON.
PROJECT LENGTH = 0.151 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0680	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	5,000.000	LF
0690	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,300.000	LF
0700	871(B)2300	CONST.ZONE IMPACT ATTEN.	360.000	SD
0710	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	20.000	SD
0720	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,300.000	LF
0730	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,300.000	LF
0740	878(B)5300	MODULAR GLARE SCREEN (TEMPORARY)	23,400.000	SD
0750	880(A)6220	ARROW DISPLAY(TYPE C)	420.000	SD
0760	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,050.000	SD
0770	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,070.000	SD
0780	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,310.000	SD
0790	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,320.000	SD
0800	880(E)6600	WARNING LIGHTS(TYPE A)	6,250.000	SD
0810	880(F)6700	DRUMS	20,480.000	SD
0820	880(G)6805	CHANNELIZER CONES	4,180.000	SD
0830	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	550.000	SD
0004	SIGNING AND STRIPING			
0840	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	8.000	EA
0850	850(A)1200	SHEET ALUMINUM SIGNS	21.000	SF
0860	851(C)2415	2" SQUARE TUBE POST	28.000	LF
0870	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	4,250.000	LF
0880	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	200.000	LF
0890	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	100.000	LF
0005	STAKING			
0900	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0910	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0920	641 2100	MOBILIZATION	1.000	LSUM