Proposal:260016 **Let Date:**January 22, 2026 **Call Order:**086
J/P Num:37500(46) **Proj. Num:**T-26501B
Counties:OKLAHOMA
Description:BRIDGE AND APPROACHES
TURNER TURNPIKE: OVER DEEP FORK RIVER,
1.09 MILES EAST OF THE I-35 INTERCHANGE
IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.869 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	89,388.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	199,642.000	CY
0040	203 5100	TEST ROLLING	1.000	LSUM
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	209 9100	MACHINE GRADING	1,571.000	LF
0070	221(B)2300	TEMPORARY SILT FENCE	10,606.000	LF
0080	221(C)2400	TEMPORARY SEDIMENT FILTER	5.000	EA
0090	221(E)2600	TEMPORARY SILT DIKE	70.000	LF
0100	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	25.000	CY
0110	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	3.000	CY
0120	221(M)3400	TEMPORARY ENVIRONMENTAL FENCE	2,993.000	LF
0130	230(A)7200	SOLID SLAB SODDING	122,932.000	SY
0140	233(E)0600	(SP) HYDROMULCH	122,932.000	SY
0150	241 3100	MOWING	50.800	AC
0160	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0170	303(A)1200	AGGREGATE BASE TYPE A	12,924.000	CY
0180	307(K)4200	STABILIZED SUBGRADE	57,753.000	SY
0190	325 0100	SEPARATOR FABRIC	62,371.000	SY
0200	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	6,170.000	TON
0210	407(B)7300	TACK COAT	16,306.000	GAL
0220	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	24,413.000	TON
0230	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	6,883.000	TON
0240	412 3100	COLD MILLING PAVEMENT	6,827.000	SY
0250	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	10,632.000	SY
0260	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	24,977.000	SY
0270	414(G)5800	P.C. CONCRETE FOR PAVEMENT	10,877.000	CY
0280	509(D)0500	CLASS C CONCRETE	20.000	CY
0290	611(G)7700	SPECIAL INLET DRAIN	3.000	EA
0300	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
0310	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	500.000	LF
0320	613(Q)7500	OUTLET LATERAL HEADWALL	20.000	EA
0330	613(W)8115	18" JACKED CONDUIT	336.000	LF
0340	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0350	619(B)6300	REMOVAL OF HEADWALL	3.000	EA
0360	619(B)6352	REMOVAL OF FENCE	420.000	LF
0370	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	16,379.000	SY
0380	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	15,796.000	SY
0390	619(B)6368	REMOVAL OF DRAINAGE INLETS	1.000	EA
0400	619(B)6396	REMOVAL OF GUARDRAIL	6,437.000	LF
0410	619(B)6416	REMOVAL OF CONCRETE MEDIAN BARRIER	487.000	LF
0420	619(C)6600	SAWING PAVEMENT	184.000	LF
0430	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	3,287.000	LF
0440	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,995.000	LF

Proposal:260016 **Let Date:**January 22, 2026 **Call Order:**086
J/P Num:37500(46) **Proj. Num:**T-26501B
Counties:OKLAHOMA
Description:BRIDGE AND APPROACHES
TURNER TURNPIKE: OVER DEEP FORK RIVER,
1.09 MILES EAST OF THE I-35 INTERCHANGE
IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.869 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE			
0450	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
0460	501(G)1800	CLSM BACKFILL	566.400	CY
0470	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	3,344.000	LF
0480	504(A)5200	APPROACH SLAB	794.400	SY
0490	504(B)5300	SAW-CUT GROOVING	3,795.600	SY
0500	504(E)5520	42" F-SHAPED PARAPET	1,034.000	LF
0510	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	4,060.000	LB
0520	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	32.000	EA
0530	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	64.000	EA
0540	507(C)8400	ELASTOMERIC BEARING PADS	64.000	EA
0550	509(A)0210	CLASS AA CONCRETE	962.400	CY
0560	509(B)0320	CLASS A CONCRETE	624.300	CY
0570	511(A)2210	REINFORCING STEEL	4,860.000	LB
0580	511(B)2310	EPOXY COATED REINFORCING STEEL	375,790.000	LB
0590	514(A)5210	PILES, FURNISHED (HP 10X42)	4,018.000	LF
0600	514(B)5310	PILES, DRIVEN (HP 10X42)	4,018.000	LF
0610	514(L)6310	PILE SPLICE (NON-BIDDABLE)	1.000	EA
0620	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	6,517.000	SY
0630	516(A)8255	DRILLED SHAFTS 84" DIAMETER	1,280.000	LF
0640	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
0650	517 9110	ELASTOMERIC COATING	2,420.000	SF
0660	523(A)3200	SEALER CRACK PREPARATION	600.000	LF
0670	523(B)3300	SEALER RESIN	4.000	GAL
0680	601(B)1230	TYPE I-A PLAIN RIPRAP	2,600.000	TON
0690	601(C)1310	TYPE I-A FILTER BLANKET	640.000	TON
0700	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	304.000	LF
0710	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	80.000	LF
0720	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260016 **Let Date:**January 22, 2026 **Call Order:**086
J/P Num:37500(46) **Proj. Num:**T-26501B
Counties:OKLAHOMA
Description:BRIDGE AND APPROACHES
TURNER TURNPIKE: OVER DEEP FORK RIVER,
1.09 MILES EAST OF THE I-35 INTERCHANGE
IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.869 MILES

	Line #		Item Description	Quantity	Unit
0003	TRAFFIC SIGNING				
	0730	506(A)7200	STRUCTURAL STEEL	1,200.000	LB
	0740	509(A)0200	CLASS AA CONCRETE	18.100	CY
	0750	511(B)2300	EPOXY COATED REINFORCING STEEL	2,000.000	LB
	0760	516(A)8230	DRILLED SHAFTS 48" DIAMETER	90.000	LF
	0770	804(A)2200	STRUCTURAL CONCRETE	2.000	CY
	0780	804(B)2300	REINFORCING STEEL	258.000	LB
	0790	805(A)3236	(PL)REMOVAL OF OVERHEAD SIGN STRUCTURE	3.000	EA
	0800	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	14.000	EA
	0810	850(A)1200	SHEET ALUMINUM SIGNS	142.000	SF
	0820	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	135.000	SF
	0830	850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	1,045.000	SF
	0840	851(A)2210	6"@20 GALV.STL.WD.FLANGE BM.POST	38.000	LF
	0850	851(C)2430	2 1/2" SQUARE TUBE POST	186.000	LF
	0860	852(B)3300	GALV.STEEL OVERHEAD SIGN STRUCTURE	80.000	LF
	0870	853 5100	DELINEATORS(TYPE 1, CODE 1)	10.000	EA
	0880	853 5165	BARRIER DELINEATORS(TYPE 2, CODE 1)	105.000	EA
	0890	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	28,700.000	LF
0004	TRAFFIC SAFETY				
	0900	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	450.000	LF
	0910	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
	0920	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
	0930	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	12.000	EA
	0940	871(A)2200	IMPACT ATTENUATOR	2.000	EA
0005	TRAFFIC LIGHTING				
	0950	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	85.000	LF
	0960	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	195.000	LF
	0970	802(C)0430	2" HIGH DENSITY PE PIPE - TRENCHED	2,725.000	LF
	0980	803(A)1210	PULL BOX(SIZE I)	2.000	EA
	0990	804(A)2200	STRUCTURAL CONCRETE	36.530	CY
	1000	804(B)2300	REINFORCING STEEL	6,110.000	LB
	1010	806(C)4524	40' MHP & TWIN H.L.MST.ARM(G.STL.)	14.000	EA
	1020	809(A)7200	ROADWAY LUMINAIRE	28.000	EA
	1030	810(A)8200	SERVICE POLE	1.000	EA
	1040	811 9130	1/C NO.10 ELECT.COND.	12,655.000	LF

Proposal:260016 **Let Date:**January 22, 2026 **Call Order:**086
J/P Num:37500(46) **Proj. Num:**T-26501B
Counties:OKLAHOMA
Description:BRIDGE AND APPROACHES
TURNER TURNPIKE: OVER DEEP FORK RIVER,
1.09 MILES EAST OF THE I-35 INTERCHANGE
IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.869 MILES

	Line #		Item Description	Quantity	Unit
0006	TRAFFIC CONTROL				
	1050	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	48,500.000	LF
	1060	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	60,550.000	LF
	1070	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,045.000	SD
	1080	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	8,800.000	LF
	1090	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	14,605.000	LF
	1100	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	8,750.000	SD
	1110	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,550.000	SD
	1120	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	12,970.000	SD
	1130	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	200.000	SD
	1140	880(C)6420	WING BARRICADES	1,400.000	SD
	1150	880(E)6607	WARNING LIGHTS(TYPE B)	11,030.000	SD
	1160	880(E)6610	WARNING LIGHTS(TYPE C)	27,785.000	SD
	1170	880(F)6700	DRUMS	42,785.000	SD
	1180	880(K)7200	SURVEILLANCE TRAFFIC CONTROL	350.000	SD
	1190	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	2,800.000	HOUR
	1200	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	2,200.000	SD
0007	ITS INFRASTRUCTURE				
	1210	805(D)3544	(PL)REMOVE & RESET/RELOCATE ITS EQUIP.	1.000	EA
0008	STAKING				
	1220	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0009	CONSTRUCTION				
	1230	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1240	640(A)1210	FIELD OFFICE	1.000	EA
	1250	641 2110	MOBILIZATION	1.000	LSUM
0010	TOLLING				
	1260	506(A)7200	STRUCTURAL STEEL	2,400.000	LB
	1270	509(A)0210	CLASS AA CONCRETE	36.200	CY
	1280	511(B)2310	EPOXY COATED REINFORCING STEEL	4,000.000	LB
	1290	516(A)8230	DRILLED SHAFTS 48" DIAMETER	236.000	LF
	1300	610(A)5200	4" CONCRETE SIDEWALK	60.000	SY
	1310	648 6110	ELECTRIC SERVICE AND SERVICE CONNECTION	1.000	LSUM
	1320	650(C)8310	ELECTRICAL EQUIPMENT	1.000	LSUM
	1330	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	511.000	LF
	1340	804(A)2200	STRUCTURAL CONCRETE	1.200	CY
	1350	811 9165	3/C NO.3 ELECT.COND.	511.000	LF
	1360	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
	1370	852(B)3300	GALV.STEEL OVERHEAD SIGN STRUCTURE	160.000	LF