Proposal:260024 **Let Date:**January 22, 2026 **Call Order:**845
J/P Num:36448(04) **Proj. Num:**STP-272N(453)IG
Counties:TULSA, WAGONER
Description:WIDEN, RESURFACE, AND BRIDGE
CITY STREET (N 23RD ST):
FROM THE INTERSECTION OF E ALBANY ST,
EXTEND NORTH IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.887 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	25,290.000	CY
0030	202(C)2400	ROCK EXCAVATION	2,500.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	2,053.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	3,522.000	LF
0070	221(C)2400	TEMPORARY SEDIMENT FILTER	34.000	EA
0080	221(E)2600	TEMPORARY SILT DIKE	217.000	LF
0090	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	37.000	CY
0100	229 6100	DITCH LINER PROTECTION	194.000	LF
0110	230(A)7200	SOLID SLAB SODDING	17,164.000	SY
0120	233(A)0200	VEGETATIVE MULCHING	1.770	AC
0130	241 3100	MOWING	7.080	AC
0140	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0150	303(A)1200	AGGREGATE BASE TYPE A	8,396.000	CY
0160	310(B)5300	SUBGRADE, METHOD B	39,775.000	SY
0170	325 0100	SEPARATOR FABRIC	32,986.000	SY
0180	326(B)1300	GEOGRID REINFORCEMENT	32,186.000	SY
0190	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	13,538.000	TON
0200	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	3,300.000	TON
0210	411(E)1610	SUPERPAVE, TYPE S6(PG 70-28 OK)	689.000	TON
0220	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	180.000	TON
0230	412 3100	COLD MILLING PAVEMENT	6,141.000	SY
0240	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	637.000	SY
0250	414(G)5800	P.C. CONCRETE FOR PAVEMENT	107.000	CY
0260	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	41.000	CY
0270	509(A)0200	CLASS AA CONCRETE	38.000	CY
0280	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	9.000	CY
0290	509(D)0500	CLASS C CONCRETE	28.000	CY
0300	511(A)2200	REINFORCING STEEL	6,310.000	LB
0310	514(J)6100	TEMPORARY SHEET PILING	1.000	LSUM
0320	601(A)1100	TYPE I PLAIN RIPRAP	2,400.000	TON
0330	601(C)1300	TYPE I-A FILTER BLANKET	640.000	TON
0340	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	8,953.000	LF
0350	610(A)5200	4" CONCRETE SIDEWALK	1,727.000	SY
0360	610(A)5240	4" DECORATIVE CONCRETE SIDEWALK	179.000	SY
0370	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	925.000	SY
0380	610(I)6000	TACTILE WARNING DEVICE-NEW	140.000	SF
0390	611(A)7215	MANHOLE (5' DIA.)	5.000	EA
0400	611(A)7230	MANHOLE (8' DIA.)	5.000	EA
0410	611(B)7305	ADD'L.DEPTH IN MANHOLE (5' DIA.)	1.000	VF
0420	611(B)7320	ADD'L.DEPTH IN MANHOLE (8' DIA.)	10.000	VF
0430	611(G)0104	INLET W/LRG. JCT. BOX, CI, DES.1(A)	6.000	EA
0440	611(G)0144	INLET W/LRG. JCT. BOX, CI, DES.2	2.000	EA
0450	611(G)0148	INLET W/LRG. JCT. BOX, CI, DES.2(B)	1.000	EA

Proposal:260024 **Let Date:**January 22, 2026 **Call Order:**845
J/P Num:36448(04) **Proj. Num:**STP-272N(453)IG
Counties:TULSA, WAGONER
Description:WIDEN, RESURFACE, AND BRIDGE
CITY STREET (N 23RD ST):
FROM THE INTERSECTION OF E ALBANY ST,
EXTEND NORTH IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.887 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0460	611(G)0172	INLET W/LRG. JCT. BOX, CI, DES.3	8.000	EA
0470	611(G)0224	INLET W/SMALL JCT. BOX, CI, DES.1(A)	5.000	EA
0480	611(G)0304	INLET W/SMALL JCT. BOX, CI, DES.3	3.000	EA
0490	611(G)7754	INLET CI DES. 2 (STD)	1.000	EA
0500	611(G)7766	INLET CI DES. 2 (D)	1.000	EA
0510	611(G)9000	INLET CDI RCP DES. 1	5.000	EA
0520	611(H)0820	ADD'L DEPTH IN INLET W/LJB, CI, DES. 2	3.000	VF
0530	611(L)1600	JUNCTION BOXES	230.000	CF
0540	612(A)3200	MANHOLES ADJUST TO GRADE	4.000	EA
0550	612(E)3600	VALVE BOXES ADJUST TO GRADE	5.000	EA
0560	612(F)3700	METER BOXES ADJUST TO GRADE	3.000	EA
0570	612(G)3800	FIRE HYDRANT RESET	2.000	EA
0580	613(A)5236	54" R.C.PIPE CLASS III	1,729.000	LF
0590	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	10.000	LF
0600	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	29.000	LF
0610	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	1,959.000	LF
0620	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	1,153.000	LF
0630	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	1,235.000	LF
0640	613(EE)5981	36" CORRUGATED POLYPROPYLENE PIPE	55.000	LF
0650	613(EE)5985	42" CORRUGATED POLYPROPYLENE PIPE	496.000	LF
0660	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0670	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0680	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0690	619(B)6300	REMOVAL OF HEADWALL	15.000	EA
0700	619(B)6352	REMOVAL OF FENCE	2,359.000	LF
0710	619(B)6356	REMOVAL OF CURB AND GUTTER	477.000	LF
0720	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	32.000	SY
0730	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	8,206.000	SY
0740	619(B)6368	REMOVAL OF DRAINAGE INLETS	2.000	EA
0750	619(B)6372	REMOVAL OF MANHOLES	2.000	EA
0760	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	982.000	SY
0770	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	1,173.000	SY
0780	619(B)6396	REMOVAL OF GUARDRAIL	1,474.000	LF
0790	619(B)6404	REMOVAL OF SIDEWALK	149.000	SY
0800	619(B)6420	REMOVAL OF RIPRAP	1,082.000	SY
0810	619(B)6440	REMOVAL OF EXISTING PIPE	819.000	LF
0820	619(C)6600	SAWING PAVEMENT	850.000	LF
0830	624 3100	(PL) ORNAMENTAL FENCE	114.000	LF
0840	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	120.000	LF
0850	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	485.000	LF
0860	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	219.000	LF
0870	624(E)3625	FENCE-STYLE CLF (6'HIGH, CLASS B)	357.000	LF
0880	624(H)3900	(PL) GATE	1.000	EA
0890	629(A)7200	MAILBOX INSTALLATION-SINGLE	5.000	EA
0900	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	5.000	EA

Proposal:260024 **Let Date:**January 22, 2026 **Call Order:**845
J/P Num:36448(04) **Proj. Num:**STP-272N(453)IG
Counties:TULSA, WAGONER
Description:WIDEN, RESURFACE, AND BRIDGE
CITY STREET (N 23RD ST):
FROM THE INTERSECTION OF E ALBANY ST,
EXTEND NORTH IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.887 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0910	629(E)7600	MAILBOX	5.000	EA
0002	WATERLINE			
0920	616(B)2332	4" POLYVINYL CHLORIDE (PVC) PIPE	268.000	LF
0930	616(C)2400	3/4" COPPER WATER SERVICE PIPE	3.000	LF
0940	616(D)2538	2" COMB.AIR RELEASE ASSEMBLY AND VAULT	1.000	EA
0950	616(E)2900	3/4" CORPORATION STOPS	3.000	EA
0960	616(K)3508	4" SOLID SLEEVE	3.000	EA
0970	616(Q)4205	4" 45 DEGREE BEND	9.000	EA
0003	BRIDGE 'A' - NBI NO. 32731			
0980	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0990	501(G)1800	CLSM BACKFILL	321.100	CY
1000	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
1010	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,284.500	LF
1020	504(A)5200	APPROACH SLAB	347.600	SY
1030	504(B)5300	SAW-CUT GROOVING	1,105.200	SY
1040	504(D)5420	CONCRETE RAIL (TR4)	466.000	LF
1050	504(F)5600	HANDRAILING	466.000	LF
1060	506(A)7200	STRUCTURAL STEEL	1,840.000	LB
1070	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	14.000	EA
1080	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	28.000	EA
1090	507(C)8400	ELASTOMERIC BEARING PADS	28.000	EA
1100	509(A)0210	CLASS AA CONCRETE	512.000	CY
1110	509(B)0320	CLASS A CONCRETE	256.600	CY
1120	511 2100	MECHANICAL SPLICES	1,394.000	EA
1130	511(A)2210	REINFORCING STEEL	1,590.000	LB
1140	511(B)2310	EPOXY COATED REINFORCING STEEL	200,210.000	LB
1150	513(B)4300	CLASS B BRIDGE DECK REPAIR	67.000	SY
1160	513(C)4400	CLASS C BRIDGE DECK REPAIR	67.000	SY
1170	514(A)5210	PILES, FURNISHED (HP 10X42)	310.000	LF
1180	514(B)5310	PILES, DRIVEN (HP 10X42)	310.000	LF
1190	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1200	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,199.000	SY
1210	516(A)8240	DRILLED SHAFTS 60" DIAMETER	72.000	LF
1220	516(A)8250	DRILLED SHAFTS 72" DIAMETER	36.000	LF
1230	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
1240	517 9110	ELASTOMERIC COATING	846.000	SF
1250	523(A)3200	SEALER CRACK PREPARATION	551.700	LF
1260	523(B)3300	SEALER RESIN	7.200	GAL
1270	601(B)1230	TYPE I-A PLAIN RIPRAP	2,640.000	TON
1280	601(C)1310	TYPE I-A FILTER BLANKET	605.000	TON
1290	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	132.000	LF
1300	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000	LF
1310	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260024 **Let Date:**January 22, 2026 **Call Order:**845
J/P Num:36448(04) **Proj. Num:**STP-272N(453)IG
Counties:TULSA, WAGONER
Description:WIDEN, RESURFACE, AND BRIDGE
CITY STREET (N 23RD ST):
FROM THE INTERSECTION OF E ALBANY ST,
EXTEND NORTH IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 0.887 MILES

	Line #		Item Description	Quantity	Unit
0004	TRAFFIC SIGNING AND STRIPING				
	1320	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	16.000	EA
	1330	850(A)1200	SHEET ALUMINUM SIGNS	91.000	SF
	1340	851(C)2415	2" SQUARE TUBE POST	136.000	LF
	1350	855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	14,032.000	LF
	1360	855(B)7305	(SP) TRAFFIC STRIPE(PLASTIC)(ARROWS)	28.000	EA
0005	TRAFFIC CONTROL				
	1370	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	25,867.000	LF
	1380	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	25,867.000	LF
	1390	871(B)2300	CONST.ZONE IMPACT ATTEN.	366.000	SD
	1400	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	4,778.000	LF
	1410	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	5,286.000	LF
	1420	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	9,115.000	SD
	1430	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,333.000	SD
	1440	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,594.000	SD
	1450	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	17,400.000	SD
	1460	880(E)6600	WARNING LIGHTS(TYPE A)	42,394.000	SD
	1470	880(E)6610	WARNING LIGHTS(TYPE C)	50,818.000	SD
	1480	880(G)6805	CHANNELIZER CONES	50,818.000	SD
	1490	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,614.000	SD
0006	STAKING				
	1500	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION				
	1510	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1520	641 2110	MOBILIZATION	1.000	LSUM
0008	WATERLINE (NON-PARTICIPATING)				
	1530	616(B)2352	12" POLYVINYL CHLORIDE (PVC) PIPE	124.000	LF
	1540	616(K)3524	12" SOLID SLEEVE	4.000	EA
	1550	616(O)4045	12" 45 DEGREE FITTING	8.000	EA
0009	WASTEWATER (NON-PARTICIPATING)				
	1560	611(A)7210	MANHOLE (4' DIA.)	3.000	EA
	1570	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	7.000	VF
	1580	615(A)1224	10" POLYVINYL CHLORIDE (PVC) PIPE	495.000	LF
	1590	616(I)3330	20" STEEL CASING	20.000	LF