Proposal: 260027 **Let Date:** January 22, 2026 **Call Order:** 857

J/P Num: 31158(08) **Proj. Num:** CIRB-247C(060)RB
31714(08) CIRB-277C(073)RB
31714(04) CIRB-277C(071)RB

Counties: MAJOR, WOODWARD

Description: PAVEMENT REHABILITATION (ASPHALT)
COUNTY ROADS (EW-51/ EW 58): EW- 51: FROM 10.17 MILES WEST OF SH-34, EXTEND EAST NEAR SHARON. EW 58: FROM 10.34 MILES EAST OF US-60, EXTEND EAST NEAR SEILING. PROJECT LENGTH = 7.399 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY - CIRB-247C(060)RB			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	178.760	CY
0020	202(D)2500	UNCLASSIFIED BORROW	4,000.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	130.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	56.000	LF
0050	232(B)9300	SEEDING METHOD B	9.830	AC
0060	233(A)0200	VEGETATIVE MULCHING	9.830	AC
0070	303(A)1200	AGGREGATE BASE TYPE A	102.440	CY
0080	303(E)1600	COLD IN-PLACE RECYCLING	30,800.000	SY
0090	325 0100	SEPARATOR FABRIC	676.130	SY
0100	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	754.830	TON
0110	407(A)7200	FOG SEAL	3,080.000	GAL
0120	407(B)7300	TACK COAT	4,035.280	GAL
0130	410(A)0260	CSS-SPECIAL LIQUIFIED EMULSION	314.340	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	7,603.340	TON
0150	411(I)2000	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	100.000	TON
0160	509(D)0500	CLASS C CONCRETE	20.000	CY
0170	619(C)6600	SAWING PAVEMENT	44.000	LF
0002	TRAFFIC - CIRB-247C(060)RB			
0180	850(A)1200	SHEET ALUMINUM SIGNS	26.970	SF
0190	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	25,203.000	LF
0200	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	20.000	LF
0210	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,850.000	SD
0220	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,260.000	SD
0230	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	180.000	SD
0240	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	540.000	SD
0250	880(E)6600	WARNING LIGHTS(TYPE A)	2,610.000	SD
0260	880(I)7000	FLAGGER	90.000	SD
0270	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	90.000	SD
0003	CONSTRUCTION - CIRB-247C(060)RB			
0280	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM

Proposal: 260027 **Let Date:** January 22, 2026 **Call Order:** 857

J/P Num: 31158(08) **Proj. Num:** CIRB-247C(060)RB
31714(08) CIRB-277C(073)RB
31714(04) CIRB-277C(071)RB

Counties: MAJOR, WOODWARD

Description: PAVEMENT REHABILITATION (ASPHALT)
COUNTY ROADS (EW-51/ EW 58): EW- 51: FROM 10.17 MILES WEST OF SH-34, EXTEND EAST NEAR SHARON. EW 58: FROM 10.34 MILES EAST OF US-60, EXTEND EAST NEAR SEILING.
PROJECT LENGTH = 7.399 MILES

Line #		Item Description	Quantity	Unit
0004	ROADWAY - CIRB-277C(073)RB			
0290	202(A)2200	UNCLASSIFIED EXCAVATION	208.250	CY
0300	202(D)2500	UNCLASSIFIED BORROW	3,600.000	CY
0310	221(B)2300	TEMPORARY SILT FENCE	1,000.000	LF
0320	221(E)2600	TEMPORARY SILT DIKE	300.000	LF
0330	232(B)9300	SEEDING METHOD B	5.930	AC
0340	233(A)0200	VEGETATIVE MULCHING	5.930	AC
0350	303(A)1200	AGGREGATE BASE TYPE A	151.720	CY
0360	303(E)1600	COLD IN-PLACE RECYCLING	32,511.110	SY
0370	325 0100	SEPARATOR FABRIC	910.310	SY
0380	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	257.040	TON
0390	407(A)7200	FOG SEAL	3,251.110	GAL
0400	407(B)7300	TACK COAT	4,219.390	GAL
0410	410(A)0260	CSS-SPECIAL LIQUIFIED EMULSION	230.420	TON
0420	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	8,903.590	TON
0430	411(I)2000	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	200.000	TON
0440	509(B)0300	CLASS A CONCRETE	27.880	CY
0450	509(D)0500	CLASS C CONCRETE	20.000	CY
0460	511(A)2200	REINFORCING STEEL	1,638.560	LB
0470	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	44.000	LF
0480	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	92.000	LF
0490	613(A)5374	51" X 31" R.C.PIPE ARCH CLASS A-III	130.000	LF
0500	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	120.000	LF
0510	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	48.000	LF
0520	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	60.000	LF
0530	613(L)6608	21" X 15" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0540	613(L)6624	28" X 20" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0550	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0560	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0570	619(C)6600	SAWING PAVEMENT	44.000	LF
0005	TRAFFIC - CIRB-277C(073)RB			
0580	850(A)1200	SHEET ALUMINUM SIGNS	38.400	SF
0590	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	38,825.000	LF
0006	CONSTRUCTION - CIRB-277C(073)RB			
0600	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM

Proposal: 260027 **Let Date:** January 22, 2026 **Call Order:** 857

J/P Num: 31158(08) **Proj. Num:** CIRB-247C(060)RB
31714(08) CIRB-277C(073)RB
31714(04) CIRB-277C(071)RB

Counties: MAJOR, WOODWARD

Description: PAVEMENT REHABILITATION (ASPHALT)
COUNTY ROADS (EW-51/ EW 58): EW- 51: FROM 10.17 MILES WEST OF SH-34, EXTEND EAST NEAR SHARON. EW 58: FROM 10.34 MILES EAST OF US-60, EXTEND EAST NEAR SEILING.
PROJECT LENGTH = 7.399 MILES

Line #		Item Description	Quantity	Unit
0007	ROADWAY - CIRB-277C(071)RB			
0610	202(A)2200	UNCLASSIFIED EXCAVATION	86.930	CY
0620	202(D)2500	UNCLASSIFIED BORROW	4,100.000	CY
0630	221(B)2300	TEMPORARY SILT FENCE	1,000.000	LF
0640	221(E)2600	TEMPORARY SILT DIKE	300.000	LF
0650	232(B)9300	SEEDING METHOD B	6.660	AC
0660	233(A)0200	VEGETATIVE MULCHING	6.660	AC
0670	303(A)1200	AGGREGATE BASE TYPE A	71.360	CY
0680	303(E)1600	COLD IN-PLACE RECYCLING	32,212.890	SY
0690	325 0100	SEPARATOR FABRIC	428.140	SY
0700	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	294.690	TON
0710	407(A)7200	FOG SEAL	3,221.290	GAL
0720	407(B)7300	TACK COAT	4,116.180	GAL
0730	410(A)0260	CSS-SPECIAL LIQUIFIED EMULSION	228.310	TON
0740	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	9,714.810	TON
0750	411(I)2000	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	200.000	TON
0760	509(B)0300	CLASS A CONCRETE	46.880	CY
0770	509(D)0500	CLASS C CONCRETE	20.000	CY
0780	511(A)2200	REINFORCING STEEL	2,509.120	LB
0790	613(A)5224	36" R.C.PIPE CLASS III	189.000	LF
0800	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	168.000	LF
0810	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	56.000	LF
0820	613(A)5374	51" X 31" R.C.PIPE ARCH CLASS A-III	248.000	LF
0830	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	168.000	LF
0840	613(L)6624	28" X 20" PREFAB. CULVERT END SEC., ARCH	8.000	EA
0850	613(M)6908	TYPE C3 CULVERT END TREATMENT	2.000	EA
0860	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0870	619(C)6600	SAWING PAVEMENT	44.000	LF
0008	TRAFFIC - CIRB-277C(071)RB			
0880	850(A)1200	SHEET ALUMINUM SIGNS	16.610	SF
0890	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	45,791.000	LF
0900	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,450.000	SD
0910	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,000.000	SD
0920	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	300.000	SD
0930	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	6,150.000	SD
0940	880(E)6600	WARNING LIGHTS(TYPE A)	15,150.000	SD
0950	880(I)7000	FLAGGER	150.000	SD
0960	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	328.000	SD
0010	CONSTRUCTION - CIRB-277C(071)RB			
0970	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0980	641 2110	MOBILIZATION	1.000	LSUM