Proposal: 260034 **Let Date:** February 12, 2026 **Call Order:** 135
J/P Num: 31821(04) **Proj. Num:** STP-242C(095)PM
Counties: LOGAN, PAYNE
Description: WIDEN AND RESURFACE (ASPHALT)
SH-51: FROM 1 MILES EAST OF US-77, EXTEND EAST NEAR ORLANDO.
PROJECT LENGTH = 1.666 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	23,443.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	2,710.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	1,092.000	LF
0060	221(G)2800	TEMPORARY FIBER LOG	120.000	LF
0070	230(A)7200	SOLID SLAB SODDING	42,031.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	8.250	AC
0090	241 3100	MOWING	16.500	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	4,247.000	CY
0110	307(K)4200	STABILIZED SUBGRADE	21,597.000	SY
0120	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	21,597.000	SY
0130	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	2,035.000	TON
0140	407(B)7300	TACK COAT	4,692.000	GAL
0150	408 8100	PRIME COAT	11,777.000	GAL
0160	409(A)9200	FABRIC REINFORCEMENT	7,641.000	SY
0170	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	2,675.000	TON
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	5,937.000	TON
0190	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	2,969.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,906.000	TON
0210	412 3100	COLD MILLING PAVEMENT	31,491.000	SY
0220	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	3,997.000	SY
0230	414(G)5800	P.C. CONCRETE FOR PAVEMENT	944.000	CY
0240	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	45.000	CY
0250	504(E)5520	42" F-SHAPED PARAPET	160.000	LF
0260	509(A)0200	CLASS AA CONCRETE	100.000	CY
0270	509(D)0500	CLASS C CONCRETE	389.000	CY
0280	510(A)1200	RETAINING WALL	42.000	SY
0290	511(A)2200	REINFORCING STEEL	14,104.000	LB
0300	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	231.000	SY
0310	601(B)1220	TYPE I-A PLAIN RIPRAP	388.000	TON
0320	601(C)1300	TYPE I-A FILTER BLANKET	111.000	TON
0330	611(G)0354	INLET (SMD-TYPE 2)	3.000	EA
0340	613(A)5208	18" R.C.PIPE CLASS III	535.000	LF
0350	613(A)5216	24" R.C.PIPE CLASS III	171.000	LF
0360	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0370	613(M)6960	TYPE A4 CULVERT END TREATMENT	11.000	EA
0380	613(M)6964	TYPE B4 CULVERT END TREATMENT	4.000	EA
0390	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0400	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	280.000	SY
0410	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	704.000	LF
0420	619(C)6600	SAWING PAVEMENT	10,619.000	LF
0430	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	323.000	LF
0435	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0440	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
0460	624(A)3200	FENCE-STYLE WWF	5,549.000	LF
0470	624(B)3350	GATES-STYLE WWF (4.5'HIGH X 14'LONG)	2.000	EA

Proposal:260034 **Let Date:**February 12, 2026 **Call Order:**135
J/P Num:31821(04) **Proj. Num:**STP-242C(095)PM
Counties:LOGAN, PAYNE
Description:WIDEN AND RESURFACE (ASPHALT)
SH-51: FROM 1 MILES EAST OF US-77, EXTEND EAST NEAR ORLANDO.
PROJECT LENGTH = 1.666 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0480	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	1,090.000	LF
0002	TRAFFIC SIGNING			
0490	871(B)2300	CONST.ZONE IMPACT ATTEN.	510.000	SD
0500	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	5,875.000	LF
0510	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	4,425.000	LF
0520	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,370.000	SD
0530	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,185.000	SD
0540	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	855.000	SD
0550	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	375.000	SD
0560	880(E)6600	WARNING LIGHTS(TYPE A)	5,445.000	SD
0570	880(F)6700	DRUMS	8,730.000	SD
0580	880(I)7000	FLAGGER	90.000	SD
0590	880(W)7700	PILOT CAR	1.000	LSUM
0600	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	840.000	SD
0003	TRAFFIC CONTROL			
0610	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	5.000	EA
0620	850(A)1200	SHEET ALUMINUM SIGNS	478.000	SF
0630	851(C)2415	2" SQUARE TUBE POST	3.000	LF
0640	851(C)2420	2 1/4" SQUARE TUBE POST	540.000	LF
0650	851(C)2430	2 1/2" SQUARE TUBE POST	162.000	LF
0660	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	32,387.000	LF
0670	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	2,718.000	LF
0680	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	650.000	LF
0690	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	27.000	LF
0700	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	16.000	EA
0710	856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	9.000	EA
0720	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	1,900.000	EA
0004	STAKING			
0730	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0740	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0750	641 2110	MOBILIZATION	1.000	LSUM