**Proposal:** 260035 **Let Date:** February 12, 2026 **Call Order:** 140
**J/P Num:** 35129(04) **Proj. Num:** SSR-249C(096)SR
**Counties:** MAYES
**Description:** RESURFACE (ASPHALT)
US-412A: FROM 6.22 MILES WEST OF THE SH-82 JUNCTION, EXTEND EAST NEAR LOCUST GROVE.
PROJECT LENGTH = 5.21 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0010 | 303(A)1200 | AGGREGATE BASE TYPE A | 672.000 | CY |
| 0020 | 407(A)7200 | FOG SEAL | 42.000 | GAL |
| 0030 | 407(C)7500 | NT TACK MATERIAL | 5,121.000 | GAL |
| 0040 | 411(C)1420 | SUPERPAVE, TYPE S4(PG 70-28 OK) | 8,623.000 | TON |
| 0050 | 411(H)1900 | SUPERPAVE, TYPE S3(PATCH)(PG64-22OK) | 588.000 | TON |
| 0060 | 412 3100 | COLD MILLING PAVEMENT | 76,096.000 | SY |
| 0070 | 413(A)4210 | RUMBLE STRIP-CENTERLINE HMA-CON | 27,511.000 | LF |
| **0002** | TRAFFIC | | | |
| 0080 | 856(A)8207 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE) | 106,800.000 | LF |
| 0090 | 856(A)8219 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE) | 144.000 | LF |
| 0100 | 880(A)6220 | ARROW DISPLAY(TYPE C) | 4.000 | SD |
| 0110 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 480.000 | SD |
| 0120 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 488.000 | SD |
| 0130 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 1,494.000 | SD |
| 0140 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 432.000 | SD |
| 0150 | 880(E)6607 | WARNING LIGHTS(TYPE B) | 1,494.000 | SD |
| 0160 | 880(G)6800 | TUBE CHANNELIZERS | 4,593.000 | SD |
| 0170 | 880(I)7000 | FLAGGER | 56.000 | SD |
| 0180 | 882(A)8210 | PORT.CHANGEABLE MESSAGE SIGN | 180.000 | SD |
| **0003** | CONSTRUCTION | | | |
| 0190 | 641 2110 | MOBILIZATION | 1.000 | LSUM |