Proposal: 260039 **Let Date:** February 19, 2026 **Call Order:** 010
J/P Num: 36917(04) **Proj. Num:** WR-MC-147
Counties: OTTAWA
Description: PAVEMENT REHABILITATION (ASPHALT)
WILL ROGERS TURNPIKE (I-44): FROM 1.17 MILES
NORTHEAST OF SH-125, EXTEND NORTHEAST NEAR MIAMI.
PROJECT LENGTH = 7.413 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(B)7300	TACK COAT	32,365.000	GAL
0020	411 1100	(PL)CRACK SEALING ASPHALT PAVEMENT	77,334.000	LF
0030	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	43,648.000	TON
0040	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	11,791.000	TON
0050	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	880.000	TON
0060	412 3100	COLD MILLING PAVEMENT	380,676.000	SY
0070	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	77,334.000	LF
0080	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	77,334.000	LF
0002	TRAFFIC SIGNING AND STRIPING			
0090	850(A)1200	SHEET ALUMINUM SIGNS	56.000	SF
0100	853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	149.000	EA
0110	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	241,660.000	LF
0003	TRAFFIC CONTROL			
0120	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	41,750.000	EA
0130	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	120.000	SD
0140	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	500.000	LF
0150	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,000.000	LF
0160	880(A)6220	ARROW DISPLAY(TYPE C)	240.000	SD
0170	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,240.000	SD
0180	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,760.000	SD
0190	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	960.000	SD
0200	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0210	880(C)6420	WING BARRICADES	480.000	SD
0220	880(E)6600	WARNING LIGHTS(TYPE A)	3,840.000	SD
0230	880(F)6700	DRUMS	3,480.000	SD
0240	880(G)6805	CHANNELIZER CONES	26,424.000	SD
0250	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,440.000	HOUR
0260	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	240.000	SD
0004	STAKING			
0270	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0280	641 2110	MOBILIZATION	1.000	LSUM