Proposal: 260063 **Let Date:** March 19, 2026 **Call Order:** 405
J/P Num: 36313(04) **Proj. Num:** STP-210C(123)3P
Counties: CARTER
Description: PAVEMENT REHABILITATION (P.C. CONCRETE)
US-77: FROM THE INTERSECTION OF SH-142,
EXTEND NORTH NEAR ARDMORE.
PROJECT LENGTH = 7.16 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	311(B)6300	PROCESS EXISTING BASE & SURFACE,METHOD B	37,200.000	LF
0020	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	6,600.000	TON
0030	412 3100	COLD MILLING PAVEMENT	22,000.000	SY
0040	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	4,000.000	SY
0050	414(G)5800	P.C. CONCRETE FOR PAVEMENT	890.000	CY
0060	415 7100	CONCRETE JOINT SEALING	64,500.000	LF
0070	425 0100	DIAMOND GRINDING CONCRETE PAVEMENT	100,000.000	SY
0002	TRAFFIC			
0080	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	75,000.000	LF
0090	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	95,000.000	LF
0100	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	60.000	LF
0110	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD
0120	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,400.000	SD
0130	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,600.000	SD
0140	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,800.000	SD
0150	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,600.000	SD
0160	880(E)6600	WARNING LIGHTS(TYPE A)	3,300.000	SD
0170	880(G)6805	CHANNELIZER CONES	35,000.000	SD
0180	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	536.000	SD