Proposal:260067 **Let Date:**March 19, 2026 **Call Order:**435
J/P Num:36178(04) **Proj. Num:**STP-235B(102)PM
Counties:JOHNSTON
Description:INTERSECTION MODIFICATION
US-377: AT THE INTERSECTION OF SH-22, 3.16 MILES
EAST OF SH-1 INTERSECTION IN TISHOMINGO.
PROJECT LENGTH = 0.724 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	22,621.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	11,489.000	CY
0040	205(A)6210	TYPE A-SALVAGED TOPSOIL	8,077.000	CY
0050	221(B)2300	TEMPORARY SILT FENCE	5,693.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	462.000	LF
0070	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	29.000	EA
0080	230(A)7200	SOLID SLAB SODDING	58,149.000	SY
0090	233(E)0600	(SP) HYDROMULCH	58,149.000	SY
0100	242 4101	STABILIZED CONSTRUCTION EXIT	4.000	EA
0110	303(A)1200	AGGREGATE BASE TYPE A	3,988.000	CY
0120	307(K)4200	STABILIZED SUBGRADE	18,021.000	SY
0130	310(B)5300	SUBGRADE, METHOD B	4,129.000	SY
0140	317 7100	CEMENT TREATED BASE	5,021.000	SY
0150	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	21,473.000	SY
0160	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	317.000	TON
0170	407(B)7300	TACK COAT	1,772.000	GAL
0180	408 8100	PRIME COAT	5,434.000	GAL
0190	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	1,534.000	TON
0200	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	2,994.000	TON
0210	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	1,256.000	TON
0220	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	653.000	TON
0230	412 3100	COLD MILLING PAVEMENT	2,672.000	SY
0240	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	2,842.000	SY
0250	414(C)5400	CONT.REINF.P.C.C. PAVT.(PLACEMENT)	1,568.000	SY
0260	414(G)5800	P.C. CONCRETE FOR PAVEMENT	1,103.000	CY
0270	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	24.000	CY
0280	509(A)0200	CLASS AA CONCRETE	117.000	CY
0290	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	5.000	CY
0300	511(A)2200	REINFORCING STEEL	21,101.000	LB
0310	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	68.000	TON
0320	609(A)4220	CONC.CURB(4" MNTBLE-INTEGRAL)	390.000	LF
0330	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	2,621.000	LF
0340	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	5,422.000	LF
0350	610(B)5310	6" CONCRETE DRIVEWAY	789.000	SY
0360	610(C)5410	6" CONCRETE DIVIDING STRIP	479.000	SY
0370	610(J)6100	(PL) STAMPED CONCRETE FINISH	479.000	SY
0380	611(A)7210	MANHOLE (4' DIA.)	11.000	EA
0390	611(A)7215	MANHOLE (5' DIA.)	1.000	EA
0400	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	7.000	VF
0410	611(B)7305	ADD'L.DEPTH IN MANHOLE (5' DIA.)	1.000	VF
0420	611(G)7754	INLET CI DES. 2 (STD)	19.000	EA
0430	611(G)7758	INLET CI DES. 2 (B)	3.000	EA
0440	611(G)7762	INLET CI DES. 2 (C)	1.000	EA
0450	611(G)7766	INLET CI DES. 2 (D)	1.000	EA
0460	611(G)7770	INLET CI DES. 2 (2B)	4.000	EA

Proposal:260067 **Let Date:**March 19, 2026 **Call Order:**435
J/P Num:36178(04) **Proj. Num:**STP-235B(102)PM
Counties:JOHNSTON
Description:INTERSECTION MODIFICATION
US-377: AT THE INTERSECTION OF SH-22, 3.16 MILES
EAST OF SH-1 INTERSECTION IN TISHOMINGO.
PROJECT LENGTH = 0.724 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	611(G)7930	INLET GPI TYPE 1 (DES. 1)	1.000	EA
0480	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	42.000	VF
0490	611(H)0416	ADD'L DEPTH IN INLET CI DES. 2B	20.000	VF
0500	611(H)0417	ADD'L DEPTH IN INLET CI DES. 2C	2.000	VF
0510	611(H)0418	ADD'L DEPTH IN INLET CI DES. 2(D)	4.000	VF
0520	611(L)1600	JUNCTION BOXES	143.000	CF
0530	612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0540	613(A)5208	18" R.C.PIPE CLASS III	2,314.000	LF
0550	613(A)5216	24" R.C.PIPE CLASS III	59.000	LF
0560	613(A)5220	30" R.C.PIPE CLASS III	148.000	LF
0570	613(B)5508	18" CORR. GALV. STEEL PIPE	1,179.000	LF
0580	613(B)5516	24" CORR. GALV. STEEL PIPE	48.000	LF
0590	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	41.000	LF
0600	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	8,043.000	LF
0610	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0620	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0630	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0640	613(M)6960	TYPE A4 CULVERT END TREATMENT	1.000	EA
0650	613(P)7400	18" GALV. STEEL CULVERT END SEC. RND.	8.000	EA
0660	613(P)7404	24" GALV. STEEL CULVERT END SEC. RND.	2.000	EA
0670	613(P)7450	21" X 15" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
0680	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	680.000	CY
0690	613(V)8000	TRENCH EXCAVATION	1,733.000	CY
0700	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0710	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	22,144.000	SY
0720	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	770.000	SY
0730	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	350.000	SY
0740	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	8,513.000	SY
0750	619(B)6396	REMOVAL OF GUARDRAIL	589.000	LF
0760	619(C)6600	SAWING PAVEMENT	144.000	LF
0770	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	278.000	LF
0780	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0790	629(D)7500	REMOVE AND RESET MAILBOX	5.000	EA

Proposal:260067 **Let Date:**March 19, 2026 **Call Order:**435
J/P Num:36178(04) **Proj. Num:**STP-235B(102)PM
Counties:JOHNSTON
Description:INTERSECTION MODIFICATION
US-377: AT THE INTERSECTION OF SH-22, 3.16 MILES
EAST OF SH-1 INTERSECTION IN TISHOMINGO.
PROJECT LENGTH = 0.724 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC SIGNING AND STRIPING			
0800	804(A)2200	STRUCTURAL CONCRETE	11.000	CY
0810	804(B)2300	REINFORCING STEEL	3,380.000	LB
0820	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	14.000	EA
0830	850(A)1200	SHEET ALUMINUM SIGNS	338.000	SF
0840	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	558.000	SF
0850	851(A)2225	8"@35 GALV.STL.WD.FLANGE BM.POST	160.000	LF
0860	851(C)2430	2 1/2" SQUARE TUBE POST	480.000	LF
0870	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	19,110.000	LF
0880	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	855.000	LF
0890	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	30.000	LF
0900	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	21.000	EA
0910	856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	4.000	EA
0003	TRAFFIC LIGHTING			
0920	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,611.000	LF
0930	802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	40.000	LF
0940	803(A)1210	PULL BOX(SIZE I)	14.000	EA
0950	804(A)2200	STRUCTURAL CONCRETE	23.000	CY
0960	804(B)2300	REINFORCING STEEL	3,976.000	LB
0970	806(C)4490	30' MTG & 6' HLMA(G.STL.)	14.000	EA
0980	807 5100	BREAKAWAY BASE	14.000	EA
0990	810(A)8200	SERVICE POLE	1.000	EA
1000	811 9115	1/C NO.4 ELECT.COND.	3,340.000	LF
0004	TRAFFIC CONTROL			
1010	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	160.000	SD
1020	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	10,890.000	LF
1030	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	268.000	EA
1040	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,666.000	LF
1050	871(B)2300	CONST.ZONE IMPACT ATTEN.	104.000	SD
1060	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	30.000	LF
1070	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	11,954.000	SD
1080	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,502.000	SD
1090	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,130.000	SD
1100	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,692.000	SD
1110	880(E)6607	WARNING LIGHTS(TYPE B)	37,806.000	SD
1120	880(F)6700	DRUMS	17,314.000	SD
1130	880(I)7000	FLAGGER	160.000	SD
1140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	290.000	SD
0005	STAKING			
1150	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
1160	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1170	641 2110	MOBILIZATION	1.000	LSUM