Proposal: 260071 **Let Date:** March 19, 2026 **Call Order:** 455
J/P Num: 35131(04) **Proj. Num:** NHPP-030N(087)3P
Counties: NOWATA
Description: RESURFACE (ASPHALT)
US-169: FROM 7.6 MILES SOUTH OF THE US-60 INTERSECTION,
EXTEND NORTH NEAR NOWATA.
PROJECT LENGTH = 5.62 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	303(A)1200	AGGREGATE BASE TYPE A	762.000	CY
0020	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,096.000	TON
0030	407(B)7300	TACK COAT	8,713.000	GAL
0040	410(A)0240	(SP)HOT-IN-PLACE RECYCLED ASPH CONCRETE	84,368.000	SY
0050	410(A)0250	(SP)HOT-IN PLACE ASPHALT EMULSION	284.000	TON
0060	411(E)1610	SUPERPAVE, TYPE S6(PG 70-28 OK)	5,733.000	TON
0070	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	572.000	TON
0080	412 3100	COLD MILLING PAVEMENT	4,306.000	SY
0002	TRAFFIC			
0090	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	29,204.000	LF
0100	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	82,700.000	LF
0110	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	315.000	LF
0120	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	3.000	EA
0130	880(A)6220	ARROW DISPLAY(TYPE C)	9.000	SD
0140	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	480.000	SD
0150	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	318.000	SD
0160	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,356.000	SD
0170	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	312.000	SD
0180	880(E)6607	WARNING LIGHTS(TYPE B)	1,356.000	SD
0190	880(G)6800	TUBE CHANNELIZERS	3,306.000	SD
0200	880(I)7000	FLAGGER	42.000	SD
0003	CONSTRUCTION			
0210	641 2110	MOBILIZATION	1.000	LSUM