Proposal: 260076 **Let Date:** March 12, 2026 **Call Order:** 371
J/P Num: 35145(04) **Proj. Num:** SBR-019N(183)SB
Counties: TULSA
Description: BRIDGE REHABILITATION
US-64: OVER SHELL CREEK, 4.3 MILES EAST OF THE SH-151 INTERCHANGE NEAR SAND SPRINGS.
PROJECT LENGTH = 0.126 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE "A"			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0015	230(A)7200	SOLID SLAB SODDING	2,100.000	SY
0020	504(E)5520	42" F-SHAPED PARAPET	8.000	LF
0030	506(A)7200	STRUCTURAL STEEL	4,500.000	LB
0040	509(A)0210	CLASS AA CONCRETE	6.000	CY
0050	511(B)2310	EPOXY COATED REINFORCING STEEL	1,100.000	LB
0060	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0070	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0080	513(C)4400	CLASS C BRIDGE DECK REPAIR	10.000	SY
0090	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,690.000	SY
0100	517 9110	ELASTOMERIC COATING	1,090.000	SF
0110	518(B)0300	SEALED EXPANSION JOINTS	46.000	LF
0120	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	111.000	LF
0130	520(C)1400	EPOXY RESIN, ABOVE WATER	1.500	GAL
0140	521(A)2200	PNEUMATICALLY PLACED MORTAR	70.000	SY
0150	523(C)3400	DECK AREA SEALED (FLOODCOATS)	2,495.000	SY
0160	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	80.000	SF
0170	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	80.500	SY
0180	540 8116	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	LSUM
0190	540 8132	(PL)REPAIR BRIDGE ITEM (TYPE B)	1.000	LSUM
0200	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0210	619(B)6312	REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
0002	BRIDGE "B"			
0220	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0225	230(A)7200	SOLID SLAB SODDING	2,100.000	SY
0230	506(A)7200	STRUCTURAL STEEL	4,500.000	LB
0240	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0250	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0260	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,700.000	SY
0270	517 9110	ELASTOMERIC COATING	1,090.000	SF
0280	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	55.000	LF
0290	520(C)1400	EPOXY RESIN, ABOVE WATER	0.800	GAL
0300	521(A)2200	PNEUMATICALLY PLACED MORTAR	100.000	SY
0310	523(C)3400	DECK AREA SEALED (FLOODCOATS)	2,505.000	SY
0320	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	160.000	SF
0330	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	100.000	SY
0340	540 8116	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	LSUM
0350	540 8132	(PL)REPAIR BRIDGE ITEM (TYPE B)	1.000	LSUM

Proposal: 260076 **Let Date:** March 12, 2026 **Call Order:** 371
J/P Num: 35145(04) **Proj. Num:** SBR-019N(183)SB
Counties: TULSA
Description: BRIDGE REHABILITATION
US-64: OVER SHELL CREEK, 4.3 MILES EAST OF THE SH-151 INTERCHANGE NEAR SAND SPRINGS.
PROJECT LENGTH = 0.126 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0360	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	4,285.000	LF
0370	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	5,715.000	LF
0380	871(B)2300	CONST.ZONE IMPACT ATTEN.	500.000	SD
0390	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	950.000	LF
0400	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	950.000	LF
0410	880(A)6220	ARROW DISPLAY(TYPE C)	500.000	SD
0420	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,000.000	SD
0430	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,000.000	SD
0440	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,500.000	SD
0450	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,000.000	SD
0460	880(E)6600	WARNING LIGHTS(TYPE A)	2,000.000	SD
0470	880(F)6700	DRUMS	11,000.000	SD
0480	880(G)6805	CHANNELIZER CONES	15,000.000	SD
0490	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	264.000	SD
0004	SIGNING AND STRIPING			
0500	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	3,345.000	LF
0005	CONSTRUCTION			
0520	641 2100	MOBILIZATION	1.000	LSUM