Proposal:260077 **Let Date:**March 19, 2026 **Call Order:**485
J/P Num:36382(04) **Proj. Num:**NHPP-276N(082)AD
Counties:WOODS
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
US-64/US-281: FROM 0.098 MILES WEST OF THE US-281 INTERSECTION, EXTEND EAST IN THE CITY OF ALVA. US-281: FROM THE INTERSECTION OF US-64, EXTEND SOUTH IN THE CITY OF ALVA.
PROJECT LENGTH = 0.213 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	246.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	967.000	LF
0050	228 5120	EROSION CONTROL MAT TYPE 4	30.000	SY
0060	230(A)7200	SOLID SLAB SODDING	967.000	SY
0070	307(K)4200	STABILIZED SUBGRADE	114.000	SY
0080	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	84.000	SY
0090	414(G)5800	P.C. CONCRETE FOR PAVEMENT	22.000	CY
0100	504(F)5600	HANDRAILING	70.000	LF
0110	510(A)1200	RETAINING WALL	25.000	SY
0120	609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	95.000	LF
0130	609(C)4410	CONCRETE HEADER CURB (8"X 18")	19.000	LF
0140	610(A)5200	4" CONCRETE SIDEWALK	763.000	SY
0150	610(I)6000	TACTILE WARNING DEVICE-NEW	54.000	SF
0160	619(B)6356	REMOVAL OF CURB AND GUTTER	109.000	LF
0170	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	94.000	SY
0180	619(B)6404	REMOVAL OF SIDEWALK	755.000	SY
0190	619(B)6452	REMOVAL OF EXISTING RETAINING WALL	16.000	LF
0200	619(C)6600	SAWING PAVEMENT	200.000	LF
0002	TRAFFIC SIGNAL			
0210	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	20.000	LF
0220	802(C)0435	3" HIGH DENSITY PE PIPE - BORED	75.000	LF
0230	803(A)1210	PULL BOX(SIZE I)	1.000	EA
0240	804(A)2200	STRUCTURAL CONCRETE	0.360	CY
0250	804(B)2300	REINFORCING STEEL	34.900	LB
0260	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0270	806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	1.000	EA
0280	830 2100	PEDESTRIAN PUSH BUTTON	2.000	EA
0290	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	300.000	LF
0300	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	40.000	LF
0003	SIGNING AND STRIPING			
0310	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	6.000	EA
0320	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0330	836 7110	RECTANGULAR RAPID FLASHING BEACON	2.000	EA
0340	850(A)1200	SHEET ALUMINUM SIGNS	49.500	SF
0350	851(C)2415	2" SQUARE TUBE POST	84.000	LF
0360	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	340.000	LF
0370	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	200.000	LF

Proposal:260077 **Let Date:**March 19, 2026 **Call Order:**485
J/P Num:36382(04) **Proj. Num:**NHPP-276N(082)AD
Counties:WOODS
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
US-64/US-281: FROM 0.098 MILES WEST OF THE US-281 INTERSECTION, EXTEND EAST IN THE CITY OF ALVA. US-281: FROM THE INTERSECTION OF US-64, EXTEND SOUTH IN THE CITY OF ALVA. PROJECT LENGTH = 0.213 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0380	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	1,200.000	LF
0390	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,200.000	LF
0400	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD
0410	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	960.000	SD
0420	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0430	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,200.000	SD
0440	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	720.000	SD
0450	880(E)6607	WARNING LIGHTS(TYPE B)	3,600.000	SD
0460	880(F)6700	DRUMS	1,440.000	SD
0470	880(G)6805	CHANNELIZER CONES	1,200.000	SD
0480	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	240.000	SD
0005	STAKING			
0490	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0500	641 2100	MOBILIZATION	1.000	LSUM