Proposal: 260079 **Let Date:** March 19, 2026 **Call Order:** 473
J/P Num: 33765(09) **Proj. Num:** STP-271C(089)PM
Counties: TILLMAN
Description: BRIDGE AND APPROACHES
SH-36: OVER LITTLE DEEP RED CREEK AND UNNAMED CREEK, 3.13 MILES NORTH OF US-70 NEAR GRANDFIELD.
PROJECT LENGTH = 0.264 MILES.

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,314.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,063.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	2,800.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	98.000	LF
0070	230(A)7200	SOLID SLAB SODDING	14,500.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	3.000	AC
0090	307(K)4200	STABILIZED SUBGRADE	5,967.000	SY
0100	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	100.000	TON
0110	407(B)7300	TACK COAT	715.000	GAL
0120	408 8100	PRIME COAT	2,347.000	GAL
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	2,035.000	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	700.000	TON
0150	601(A)1100	TYPE I PLAIN RIPRAP	2,348.000	TON
0160	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0170	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	4,022.000	SY
0180	619(B)6396	REMOVAL OF GUARDRAIL	554.000	LF
0190	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	350.000	LF
0200	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0210	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0220	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	1,144.000	LF
0002	BRIDGE 'A'			
0230	202(A)2210	UNCLASSIFIED EXCAVATION	2,440.000	CY
0240	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	360.000	CY
0250	509(A)0210	CLASS AA CONCRETE	814.400	CY
0260	511(A)2210	REINFORCING STEEL	138,410.000	LB
0270	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260079 **Let Date:**March 19, 2026 **Call Order:**473
J/P Num:33765(09) **Proj. Num:**STP-271C(089)PM
Counties:TILLMAN
Description:BRIDGE AND APPROACHES
SH-36: OVER LITTLE DEEP RED CREEK AND UNNAMED CREEK, 3.13 MILES NORTH OF US-70 NEAR GRANDFIELD.
PROJECT LENGTH = 0.264 MILES.

Line #		Item Description	Quantity	Unit
0003	BRIDGE 'B'			
0280	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	160.000	CY
0290	501(G)1800	CLSM BACKFILL	145.200	CY
0300	503(A)4220	PRESTRESSED CONCRETE BEAMS (TYPE II)	720.000	LF
0310	504(A)5200	APPROACH SLAB	281.200	SY
0320	504(B)5300	SAW-CUT GROOVING	923.600	SY
0330	504(D)5420	CONCRETE RAIL (TR4)	413.400	LF
0340	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	1,530.000	LB
0350	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	10.000	EA
0360	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
0370	509(A)0210	CLASS AA CONCRETE	168.800	CY
0380	509(B)0320	CLASS A CONCRETE	152.000	CY
0390	509(D)0510	CLASS C CONCRETE	45.000	CY
0400	511(B)2310	EPOXY COATED REINFORCING STEEL	73,810.000	LB
0410	514(A)5210	PILES, FURNISHED (HP 10X42)	212.000	LF
0420	514(A)5220	PILES, FURNISHED (HP 12X53)	910.000	LF
0430	514(B)5310	PILES, DRIVEN (HP 10X42)	212.000	LF
0440	514(B)5320	PILES, DRIVEN (HP 12X53)	910.000	LF
0450	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0460	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	662.000	SY
0470	516(A)8235	DRILLED SHAFTS 54" DIAMETER	206.000	LF
0480	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
0490	517 9110	ELASTOMERIC COATING	1,042.000	SF
0500	518(B)0300	SEALED EXPANSION JOINTS	43.170	LF
0510	523(A)3200	SEALER CRACK PREPARATION	43.000	LF
0520	523(B)3300	SEALER RESIN	0.500	GAL
0530	601(B)1230	TYPE I-A PLAIN RIPRAP	1,130.000	TON
0540	601(C)1310	TYPE I-A FILTER BLANKET	230.000	TON
0550	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	84.000	LF
0560	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	46.000	LF
0570	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0004	TRAFFIC SINGING AND STRIPING			
0580	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	4,800.000	LF
0005	TRAFFIC CONTROL			
0590	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	35,640.000	SD
0600	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,160.000	SD
0610	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,620.000	SD
0620	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,400.000	SD
0630	880(E)6600	WARNING LIGHTS(TYPE A)	10,800.000	SD
0640	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	328.000	SD
0006	STAKING			
0650	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 260079 **Let Date:** March 19, 2026 **Call Order:** 473
J/P Num: 33765(09) **Proj. Num:** STP-271C(089)PM
Counties: TILLMAN
Description: BRIDGE AND APPROACHES
SH-36: OVER LITTLE DEEP RED CREEK AND UNNAMED CREEK, 3.13 MILES NORTH OF US-70 NEAR GRANDFIELD.
PROJECT LENGTH = 0.264 MILES.

Line #		Item Description	Quantity	Unit
0007	CONSTRUCTION			
0660	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0670	641 2100	MOBILIZATION	1.000	LSUM