Proposal:260080 **Let Date:**March 19, 2026 **Call Order:**040
J/P Num:35835(04) **Proj. Num:**MU-MC-46B
Counties:MUSKOGEE
Description:SHOULDER AND GUARDRAIL REPLACEMENT
MUSKOGEE TURNPIKE (SH-351): FROM 0.45 MILES NORTH OF THE I-40 INTERCHANGE, EXTEND NORTH NEAR MUSKOGEE.
PROJECT LENGTH = 19.480 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	1,000.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	6,500.000	CY
0030	203 5100	TEST ROLLING	1.000	LSUM
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	19,000.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	8,000.000	LF
0070	230(A)7200	SOLID SLAB SODDING	250,000.000	SY
0080	303(A)1200	AGGREGATE BASE TYPE A	1,800.000	CY
0090	310(B)5300	SUBGRADE, METHOD B	184,893.000	SY
0100	407(A)7200	FOG SEAL	858.000	GAL
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	43,506.000	TON
0120	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	961.000	TON
0130	412 3100	COLD MILLING PAVEMENT	190,919.000	SY
0140	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	205,709.000	LF
0150	619(B)6396	REMOVAL OF GUARDRAIL	17,619.000	LF
0160	623 1100	(PL)GUARDRAIL CURBING	9.000	EA
0170	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	18,563.000	LF
0180	623(G)1820	GUARDRAIL END TREATMENT (31")	33.000	EA
0190	623(I)2040	GUARDRAIL BRIDGE CONN (D-BF RETROFIT)	9.000	EA
0002	TRAFFIC			
0200	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	38.000	EA
0210	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	10.000	EA
0220	850(A)1200	SHEET ALUMINUM SIGNS	390.000	SF
0230	851(C)2415	2" SQUARE TUBE POST	468.000	LF
0240	853 5115	DELINEATORS(TYPE 2, CODE 1)	977.000	EA
0250	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	200,640.000	LF
0260	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	420.000	SD
0270	880(A)6220	ARROW DISPLAY(TYPE C)	720.000	SD
0280	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,680.000	SD
0290	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,780.000	SD
0300	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,520.000	SD
0310	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,230.000	SD
0320	880(C)6420	WING BARRICADES	840.000	SD
0330	880(E)6600	WARNING LIGHTS(TYPE A)	1,230.000	SD
0340	880(F)6700	DRUMS	735.000	SD
0350	880(G)6805	CHANNELIZER CONES	147,000.000	SD
0360	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	25.000	HOUR
0370	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	720.000	SD
0003	STAKING			
0380	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0390	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0400	641 2110	MOBILIZATION	1.000	LSUM