Proposal:260083 **Let Date:**June 18, 2026 **Call Order:**200
J/P Num:32098(04) **Proj. Num:**STP-201C(069)PM
Counties:ADAIR
Description:WIDEN AND RESURFACE
SH-100: FROM 8.3 MILES WEST OF US-59, EXTEND EAST NEAR STILWELL.
PROJECT LENGTH = 6.117 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	64,534.000	CY
0030	202(C)2400	ROCK EXCAVATION	1,000.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	4,151.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	55,033.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	12,306.000	LF
0080	230(A)7200	SOLID SLAB SODDING	399,224.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	98.000	AC
0100	241 3100	MOWING	196.000	AC
0110	303(A)1200	AGGREGATE BASE TYPE A	6,489.000	CY
0120	307(K)4200	STABILIZED SUBGRADE	90,571.000	SY
0130	325 0100	SEPARATOR FABRIC	32,265.000	SY
0140	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	7,409.000	TON
0150	407(B)7300	TACK COAT	18,557.000	GAL
0160	408 8100	PRIME COAT	42,931.000	GAL
0170	409(A)9200	FABRIC REINFORCEMENT	22,390.000	SY
0180	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	2,737.000	TON
0190	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	23,209.000	TON
0200	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	8,629.000	TON
0210	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	7,728.000	TON
0220	411(D)1520	SUPERPAVE, TYPE S5(PG 70-28 OK)	5,543.000	TON
0230	411(D)1530	SUPERPAVE, TYPE S5(PG 64-22 OK)	3,725.000	TON
0240	412 3100	COLD MILLING PAVEMENT	60,304.000	SY
0250	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	214.000	CY
0260	509(A)0200	CLASS AA CONCRETE	697.000	CY
0270	509(D)0500	CLASS C CONCRETE	1,655.000	CY
0280	511(A)2200	REINFORCING STEEL	105,307.000	LB
0290	601(A)1100	TYPE I PLAIN RIPRAP	1,020.000	TON
0300	610(B)5310	6" CONCRETE DRIVEWAY	601.000	SY
0310	611(G)8008	INLET CDI RCB DES. 3	1.000	EA
0320	611(G)8012	INLET CDI RCB DES. 4	1.000	EA
0330	611(G)8024	INLET CDI RCB DES. 7	2.000	EA
0340	611(G)9000	INLET CDI RCP DES. 1	1.000	EA
0350	611(G)9004	INLET CDI RCP DES. 2	1.000	EA
0360	611(G)9008	INLET CDI RCP DES. 3	2.000	EA
0370	611(G)9012	INLET CDI RCP DES. 4	2.000	EA
0380	613(A)5208	18" R.C.PIPE CLASS III	83.000	LF
0390	613(A)5216	24" R.C.PIPE CLASS III	105.000	LF
0400	613(A)5220	30" R.C.PIPE CLASS III	105.000	LF
0410	613(A)5224	36" R.C.PIPE CLASS III	128.000	LF
0420	613(A)5228	42" R.C.PIPE CLASS III	14.000	LF
0430	613(B)5508	18" CORR. GALV. STEEL PIPE	2,071.000	LF
0440	613(B)5516	24" CORR. GALV. STEEL PIPE	461.000	LF
0450	613(B)5524	30" CORR. GALV. STEEL PIPE	116.000	LF
0460	613(B)5528	36" CORR. GALV. STEEL PIPE	137.000	LF
0470	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	56.000	LF

Proposal:260083 **Let Date:**June 18, 2026 **Call Order:**200
J/P Num:32098(04) **Proj. Num:**STP-201C(069)PM
Counties:ADAIR
Description:WIDEN AND RESURFACE
SH-100: FROM 8.3 MILES WEST OF US-59, EXTEND EAST NEAR STILWELL.
PROJECT LENGTH = 6.117 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0480	613(B)5616	35" X 24" CORR. GALV. STEEL PIPE ARCH	434.000	LF
0490	613(B)5620	42" X 29" CORR. GALV. STEEL PIPE ARCH	294.000	LF
0500	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	32.000	EA
0510	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	15.000	EA
0520	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0530	613(L)6732	42" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0540	613(M)6960	TYPE A4 CULVERT END TREATMENT	31.000	EA
0550	613(M)6964	TYPE B4 CULVERT END TREATMENT	6.000	EA
0560	613(M)6968	TYPE C4 CULVERT END TREATMENT	2.000	EA
0570	613(M)6972	TYPE D4 CULVERT END TREATMENT	2.000	EA
0580	613(M)6980	TYPE AA4 CULVERT END TREATMENT	6.000	EA
0590	613(M)6984	TYPE BB4 CULVERT END TREATMENT	8.000	EA
0600	613(M)6988	TYPE CC4 CULVERT END TREATMENT	4.000	EA
0610	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0620	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	34,720.000	SY
0630	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	242.000	SY
0640	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	7,368.000	SY
0650	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	10,086.000	SY
0660	619(B)6396	REMOVAL OF GUARDRAIL	699.000	LF
0670	619(B)6508	REMOVE AND RESET CATTLE GUARD	1.000	EA
0680	619(C)6600	SAWING PAVEMENT	49,910.000	LF
0690	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	2,038.000	LF
0700	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	3.000	EA
0710	623(G)1820	GUARDRAIL END TREATMENT (31")	6.000	EA
0720	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	395.000	LF
0730	629(A)7200	MAILBOX INSTALLATION-SINGLE	25.000	EA
0740	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	6.000	EA
0750	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	42.000	EA
0760	629(E)7600	MAILBOX	42.000	EA

Proposal:260083 **Let Date:**June 18, 2026 **Call Order:**200
J/P Num:32098(04) **Proj. Num:**STP-201C(069)PM
Counties:ADAIR
Description:WIDEN AND RESURFACE
SH-100: FROM 8.3 MILES WEST OF US-59, EXTEND EAST NEAR STILWELL.
PROJECT LENGTH = 6.117 MILES

Line #		Item Description	Quantity	Unit
0002	WATERLINE RELOCATION			
0770	202(C)2400	ROCK EXCAVATION	500.000	CY
0780	616(B)2332	4" POLYVINYL CHLORIDE (PVC) PIPE	16,488.000	LF
0790	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	3,257.000	LF
0800	616(D)2534	2" AIR RELIEF VALVE ASSEMBLY & METER CAN	9.000	EA
0810	616(D)2630	2" GATE VALVE	4.000	EA
0820	616(D)2642	4" GATE VALVE	23.000	EA
0830	616(D)2646	6" GATE VALVE	4.000	EA
0840	616(E)2905	1" CORPORATION STOPS	15.000	EA
0850	616(F)3005	METER INSTALLATION 5/8"	24.000	EA
0860	616(I)3360	2" HDPE CASING	1,890.000	LF
0870	616(I)3364	4" HDPE CASING	175.000	LF
0880	616(I)3369	8" HDPE CASING	390.000	LF
0890	616(O)3901	CONNECT TO EXISTING WATER LINE	18.000	EA
0900	616(P)4101	1" POLYETHYLENE WATER SERVICE PIPE	2,354.000	LF
0910	616(P)4108	2" HDPE PIPE	253.000	LF
0920	616(P)4128	4" HDPE PIPE	296.000	LF
0930	616(P)4132	4" HDPE PIPE (BORED)	1,905.000	LF
0940	616(P)4140	6" HDPE PIPE (BORED)	595.000	LF
0950	616(V)4800	HYDROSTATIC PRESSURE TESTING & DISINFECT	1.000	LSUM
0003	STRIPING			
0960	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	64,602.000	LF
0970	805(A)3200	REMOVAL OF SIGN FOOTING	48.000	EA
0980	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	74.000	EA
0990	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
1000	850(A)1200	SHEET ALUMINUM SIGNS	445.000	SF
1010	851(C)2420	2 1/4" SQUARE TUBE POST	704.000	LF
1020	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	49.000	EA
1030	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	124,948.000	LF
1040	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	889.000	LF
1050	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	346.000	LF
1060	856(B)8303	(SP) TRAF.STR.(PLURAL-COMPONENT)(SYM,WRD,ETC)	8.000	EA

Proposal:260083 **Let Date:**June 18, 2026 **Call Order:**200
J/P Num:32098(04) **Proj. Num:**STP-201C(069)PM
Counties:ADAIR
Description:WIDEN AND RESURFACE
SH-100: FROM 8.3 MILES WEST OF US-59, EXTEND EAST NEAR STILWELL.
PROJECT LENGTH = 6.117 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
1070	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	58,352.000	LF
1080	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	52,352.000	LF
1090	858(A)0212	PAVE.MARKERS CLASS A TYPE 2	11,672.000	EA
1100	871(B)2300	CONST.ZONE IMPACT ATTEN.	450.000	SD
1110	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	60.000	SD
1120	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,250.000	LF
1130	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,580.000	SD
1140	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,342.000	SD
1150	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,420.000	SD
1160	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,212.000	SD
1170	880(D)6500	VERTICAL PANELS	2,430.000	SD
1180	880(E)6600	WARNING LIGHTS(TYPE A)	4,500.000	SD
1190	880(F)6700	DRUMS	19,740.000	SD
1200	880(G)6805	CHANNELIZER CONES	16,170.000	SD
1210	880(I)7000	FLAGGER	120.000	SD
1220	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	628.000	SD
0005	CONSTRUCTION STAKING			
1230	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
1240	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1250	640(A)1210	FIELD OFFICE	1.000	EA
1260	641 2110	MOBILIZATION	1.000	LSUM