Proposal: 260095 **Let Date:** April 09, 2026 **Call Order:** 570
J/P Num: 32704(04) **Proj. Num:** NHPP-015N(037)PM
Counties: TULSA
Description: BRIDGE REHABILITATION
SH-51: OVER 21ST STREET, 2.1 MILES SOUTHEAST OF THE US-75 INTERCHANGE IN THE CITY OF TULSA.
PROJECT LENGTH = 0.124 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(B)7300	TACK COAT	159.000	GAL
0020	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	238.000	TON
0030	411(I)2010	SUPERPAVE, TYPE S4(PATCH)(PG76-28OK)	26.000	TON
0040	412 3100	COLD MILLING PAVEMENT	2,119.000	SY
0002	BRIDGE "A" - NBI 17303			
0050	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0060	504(A)5200	APPROACH SLAB	289.600	SY
0070	504(B)5300	SAW-CUT GROOVING	1,225.000	SY
0080	504(E)5520	42" F-SHAPED PARAPET	458.600	LF
0090	509(A)0210	CLASS AA CONCRETE	228.500	CY
0100	511 2100	MECHANICAL SPLICES	752.000	EA
0110	511(B)2310	EPOXY COATED REINFORCING STEEL	74,530.000	LB
0120	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0130	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0140	513(B)4300	CLASS B BRIDGE DECK REPAIR	101.000	SY
0150	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	641.000	SY
0160	517 9110	ELASTOMERIC COATING	1,428.000	SF
0170	518(E)0600	PREFORMED SILICONE EXPANSION JOINTS	121.000	LF
0180	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	390.000	LF
0190	520(C)1400	EPOXY RESIN, ABOVE WATER	12.100	GAL
0200	521(A)2200	PNEUMATICALLY PLACED MORTAR	7.000	SY
0210	523(A)3200	SEALER CRACK PREPARATION	178.000	LF
0220	523(B)3300	SEALER RESIN	1.600	GAL
0230	540 8112	(PL)REPAIR BRIDGE ITEMS	7.000	SY
0240	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	3.000	EA
0250	540 8136	(PL)REPAIR BRIDGE ITEM (TYPE B)	9.000	EA
0260	540 8152	(PL)REPAIR BRIDGE ITEM (TYPE C)	2.000	EA
0270	542 9110	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	LSUM
0280	542 9121	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE B)	1.000	EA
0290	542 9131	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE C)	10.000	EA
0300	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260095 **Let Date:**April 09, 2026 **Call Order:**570
J/P Num:32704(04) **Proj. Num:**NHPP-015N(037)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
SH-51: OVER 21ST STREET, 2.1 MILES SOUTHEAST OF THE
US-75 INTERCHANGE IN THE CITY OF TULSA.
PROJECT LENGTH = 0.124 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE "B" - NBI 17304			
0310	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0320	504(A)5200	APPROACH SLAB	289.600	SY
0330	504(B)5300	SAW-CUT GROOVING	1,227.000	SY
0340	504(E)5520	42" F-SHAPED PARAPET	458.600	LF
0350	509(A)0210	CLASS AA CONCRETE	228.500	CY
0360	511 2100	MECHANICAL SPLICES	752.000	EA
0370	511(B)2310	EPOXY COATED REINFORCING STEEL	74,410.000	LB
0380	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0390	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0400	513(B)4300	CLASS B BRIDGE DECK REPAIR	101.000	SY
0410	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	639.000	SY
0420	517 9110	ELASTOMERIC COATING	1,428.000	SF
0430	518(E)0600	PREFORMED SILICONE EXPANSION JOINTS	121.000	LF
0440	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	840.000	LF
0450	520(C)1400	EPOXY RESIN, ABOVE WATER	16.000	GAL
0460	521(A)2200	PNEUMATICALLY PLACED MORTAR	23.000	SY
0470	523(A)3200	SEALER CRACK PREPARATION	178.000	LF
0480	523(B)3300	SEALER RESIN	1.600	GAL
0490	540 8112	(PL)REPAIR BRIDGE ITEMS	7.000	SY
0500	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	3.000	EA
0510	540 8136	(PL)REPAIR BRIDGE ITEM (TYPE B)	2.000	EA
0520	542 9110	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	LSUM
0530	542 9121	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE B)	1.000	EA
0540	542 9131	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE C)	10.000	EA
0550	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0004	TRAFFIC CONTROL			
0560	413(E)4600	(PL)RUMBLE STRIP-TEMPORARY	1,260.000	SD
0570	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	4,295.000	LF
0580	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	15,529.000	LF
0590	857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	1,635.000	EA
0600	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	5,576.000	LF
0610	871(B)2300	CONST.ZONE IMPACT ATTEN.	840.000	SD
0620	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,800.000	LF
0630	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,912.500	LF
0640	880(A)6220	ARROW DISPLAY(TYPE C)	840.000	SD
0650	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,460.000	SD
0660	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,342.000	SD
0670	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	10,584.000	SD
0680	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,830.000	SD
0690	880(E)6607	WARNING LIGHTS(TYPE B)	14,952.000	SD
0700	880(E)6616	WARNING LIGHTS(TYPE D)	44,709.000	SD
0710	880(F)6700	DRUMS	38,094.000	SD
0720	880(G)6800	TUBE CHANNELIZERS	2,016.000	SD
0730	880(G)6805	CHANNELIZER CONES	6,615.000	SD
0740	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	896.000	SD

Proposal:260095 **Let Date:**April 09, 2026 **Call Order:**570
J/P Num:32704(04) **Proj. Num:**NHPP-015N(037)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
SH-51: OVER 21ST STREET, 2.1 MILES SOUTHEAST OF THE US-75 INTERCHANGE IN THE CITY OF TULSA.
PROJECT LENGTH = 0.124 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC SIGNING AND STRIPING			
0750	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	4.000	EA
0760	850(A)1200	SHEET ALUMINUM SIGNS	64.000	SF
0770	851(C)2430	2 1/2" SQUARE TUBE POST	152.000	LF
0780	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	5,950.000	LF
0790	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,017.000	LF
0800	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	45.000	EA
0810	871(A)2200	IMPACT ATTENUATOR	1.000	EA
0006	STAKING			
0820	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
0830	641 2110	MOBILIZATION	1.000	LSUM